## TM 11-854

# INSTRUCTION BOOK FOR RADIO RECEIVER R-388/URR

Manufactured By
Barker and Williamson, Inc.
Order No. 19624-Phila-50
5 September 1951

# INSTRUCTION BOOK FOR RADIO RECEIVER R-388/URR

Manufactured By
Barker and Williamson, Inc.
Order No. 19624-Phila-50
5 September 1951

### **CONTENTS**

Par	ragraph	Page	Par	ragraph	Page
CHAPTER 1. INTRODUCTION	ON.		Section II. Preventive mainte-		
Section I. General.			nance services.		
Scope	1	9	Definition of preventive main-		
Forms and records	$\frac{1}{2}$	9	tenance	27	26
	4	J	General preventive maintenance		
Section II. Description and data.			techniques	28	26
Purpose and use	3	9	Performing preventive mainte-	2.0	
Technical characteristics	$\frac{4}{2}$	11	nance	29	27
Packaging data	5	12	Section III. Lubrication and		
Description of receiver	6	13	weatherproofing.		
Running spares	7	14	Lubrication	30	28
Additional equipment required	8	14	Weatherproofing	31	28
			Rustproofing and painting	32	29
CHAPTER 2. OPERATING			Section IV. Trouble shooting at		
INSTRUCTIONS.			organizational maintenance		
Castian I Comica management of			level.		
Section I. Service upon receipt of			Scope	33	29
Radio Receiver R-388/URR.	0	15	Visual inspection	34	$\frac{23}{29}$
Siting	9	15	Trouble shooting, using equip-	94	40
Uncrating, unpacking, and	10	15	ment performance checklist	35	30
checking new equipment	10	15 18	Equipment performance check-	55	90
Installation	$\begin{array}{c} 11 \\ 12 \end{array}$	19	list	36	30
Service upon receipt of used or	14	19	1150	-90	90
reconditioned equipment	13	20	CHAPTER 4. THEORY OF		
	10	20	OPERATION.		
Section II. Controls and operation			OPERATION.		
under usual conditions.	- 4	20	Section I. Electrical theory of re-		
Controls and their use	14	20	ceiver.		
Starting procedure	$\frac{15}{16}$	$\begin{array}{c} 22 \\ 22 \end{array}$	General	37	34
Types of operation	$\frac{10}{17}$	$\frac{22}{24}$	Radio-frequency amplifier V101	38	37
Calibrating receiver  Zeroing meter	18	$\frac{24}{24}$	First mixer	39	38
Stopping procedure	$\frac{18}{19}$	$\frac{24}{25}$	Intermediate mixer	40	43
Operating precautions and notes	$\frac{19}{20}$	$\frac{25}{25}$	Variable intermediate frequency	41	44
	20	4.)	Second mixer	42	45
Section III. Operation under un-			High-frequency crystal oscilla-		
usual conditions.			tor	43	45
General	21	25	Variable frequency oscillator	44	46
Operation in arctic climates	22	25	Crystal filter	45	47
Operation in tropical climates	23	25	Intermediate-amplifier stages	46	48
Operation in desert climates	24	25	Detector	47	51
			I-f output	48	51
CHAPTER 3. ORGANIZAT		۸L	Avc and a-v-c amplifier	49	51
MAINTENANCE INSTRU	CTIO	NS.	Noise limiter and a-f amplifier	50	52
			Beat-frequency oscillator	51	54
Section I. Organizational tools			Calibration oscillator	52 50	54
and equipment.	0-	0.0	Power supply	53 5.4	56 57
Tools and materials	25	26	INPUT-OUTPUT METER	54 55	5 <b>7</b>
Special tools	26	26	Bandswitching	55	57

Pa	ragraph	Page	Paragrap	oh Page
Section II. Mechanical function-			I-f amplifiers and crystal filter	
ing of receiver.			unit alinement 84	86
	- 0	0.1	Bfo adjustment 85	86
General description	56 5 <b>7</b>	61	Alinement of dial 86	87
Tuning mechanisms	<b>57</b>	61	Tuning step 2 and variable i-f	
Band change mechanisms	58	61	(for even-numbered steps). 87	87
Frequency indication	59	63	Tuning step 3 and variable i-f	
			(for odd-numbered steps) 88	87
CHAPTER 5. FIELD MAIN	TENIA	NCE	Tuning steps 4 through 7 89	87
CHAPTER S. FIELD MAIN	IENAI	ACE	Tuning steps 8 through 15 90	88
INSTRUCTIONS.			Tuning steps 16 through 30 91	88
			R-f alinement, tuning step 1 92	88
Section I. Trouble shooting at			Vfo alinement 93	89
field maintenance level.			Alinement of inductor L124 94	89
Trouble-shooting procedures	60	65		
Trouble-shooting data	61	66	Section IV. Final testing.	
Test equipment required for	01	00		
trouble shooting	62	66	General 95	89
General precautions	63	66	Test equipment required for	
Checking filaments and B+	00	00	final testing 96	89
circuits for shorts	64	67	Beat-frequency oscillator 97	89
Operational test	65	67	Sensitivity 98	89
Trouble-shooting chart	66	67	Signal plus noise-to-noise ratio 99	90
Mechanical trouble - shooting	00	01	Selectivity 100	90
data	67	79	A-v-c characteristic 101	90
Signal substitution notes	$\frac{67}{68}$	79 79	Over-all distortion for an input	
A-f tests			of 1,000 uv 102	90
Fixed i-f tests	69 70	80		
Variable i-f tests	70 71	80		
R-f tests	71 70	80	CHAPTER 6. SHIPMENT AND	LIM-
	72 72	81	ITED STORAGE AND DEMOL	ITION
Stage gain chart	73	81		
Section II. Repair.			TO PREVENT ENEMY USE.	
•			Section I. Shipment and limited	
Replacement of parts	74	82	storage.	
Removal of vfo	<b>7</b> 5	82	D' 11	0.1
Tuning and band-change gear-			Disassembly 103	91
ing	76	82	Repacking for shipment and	
R-f slug rack	77	83	limited storage 104	91
Replacement of dial cables	78	84	~	
Refinishing	79	85	Section II. Demolition of materiel	
			to prevent enemy use.	
Section III. Alinement procedures.			General	91
-			Destruction of equipment 106	91
General	80	85	Destruction of equipment 100	31
Test equipment for alinement				
and adjustment	81	85	APPENDIX I. REFERENCES	92
Crystal oscillator V105 trimmer				
adjustment	82	85		
100-kc calibration oscillator ad-			APPENDIX II. IDENTIFICA-	
justment	83	86	TION TABLE OF PARTS	97

#### LIST OF ILLUSTRATIONS

Fig.~N	To. $Title$	Page	Fig. N	To. $Title$	Page
1	Radio Receiver R-388/URR		20	Crystal oscillator, tuning step 1 only, schematic diagram	46
2	Receiver in use, simplified block diagram		21	Vfo, shield cover removed	48
3	Receiver in use with frequency-shift		22	Crystal filter, schematic diagram	49
0	converter for reception of radio-		23	I-f stages, schematic diagram	50
	teletype signals, simplified block diagram		24	Detector and i-f output stages, schematic diagram	51
4	Radio Receiver R-388/URR, front view		25	Avc and a-v-c amplifier stages, schematic diagram	53
5	Radio Receiver R-388/URR, rear view		26	Limiter and audio amplifier stages, schematic diagram	54
6	Siting, good and bad locations	16	27	Beat-frequency oscillator, schematic	
7	Packaging and packing of Radio Re-			diagram	55
	ceiver R-388/URR	17	28	Calibration oscillator, schematic dia-	~ c
8	Radio Receiver R-388/URR, tube lo-		20	gram	
0	cation diagram		29	Power supply, schematic diagram.	57
9	Radio Receiver R-388/URR, rear view, showing connections	19	30	Functional diagram of tuning, band changing, and frequency indicating mechanisms	
10	Radio Receiver R-388/URR, front panel		31	Dial and bandswitching gearbox	
11	Radio Receiver R-388/URR, over-all		32	Tube voltage and resistance chart	
	block diagram		33	Radio Receiver R-388/URR, top view	
12	Radio Receiver R-388/URR, signifi-	-		· · · · · · · · · · · · · · · · · · ·	
	cant block diagram of bands	36	34	Bottom view of chassis, compartmented	
13	R-f amplifier, tuning step 1, sche matic diagram		35	Bottom view of chassis, compartment 1, capacitors	
14	R-f amplifier, tuning steps 2 and 3		36	Bottom view of chassis, compartment	
. ~	schematic diagram			1	
15	R-f amplifier, tuning steps 4 through 30, schematic diagram		37	Bottom view of chassis, compartment 2	
16	First mixer, tuning step 1 only, sche matic diagram		38	Bottom view of chassis, compartment 3	74
17	First mixer, tuning steps 4 through 30, schematic diagram		39	Replacement of dial cables	85
18	Intermediate mixer, schematic dia		40	Resistor color codes	95
<b>T</b> ()	gram		41	Capacitor color codes	96
19	Second mixer and variable interme		42	Radio Receiver R-388/URR, schematic diagram (rear of instruction b	



#### RESCUE.

In case of electric shock, shut off the high voltage at once and ground the circuits. If the high voltage cannot be turned off without delay, free the victim from contact with the live conductor as promptly as possible. Avoid direct contact with either the live conductor or the victim's body. Use a dry board, dry clothing, or other nonconductor to free the victim. An ax may be used to cut the high-voltage wire. Use extreme caution to avoid the resulting electric flash.

#### SYMPTOMS.


- a. Breathing stops abruptly in electric shock if the current passes through the breathing center at the base of the brain. If the shock has not been too severe, the breath center recovers after a while and normal breathing is resumed, provided that a sufficient supply of air has been furnished meanwhile by artificial respiration.
- **b.** The victim is usually very white or blue. The pulse is very weak or entirely absent and unconsciousness is complete. Burns are usually present. The victim's body may become rigid or stiff in a very few minutes. This condition is due to the action of electricity and is not to be considered rigor mortis. Artificial respiration must still be given, as several such cases are reported to have recovered. The ordinary and general tests for death should never be accepted.

#### TREATMENT.

a. Start artificial respiration immediately. At the same time send for a medical officer, if assistance is available. Do not leave the victim unattended. Perform artificial respiration at the scene of the accident, unless the victim's or operator's life is endangered from such action. In this case only, remove the victim to another location, but no farther than is necessary for safety. If the new location is more

than a few feet away, artificial respiration should be given while the victim is being moved. If the method of transportation prohibits the use of the Shaeffer prone pressure method, other methods of resuscitation may be used. Pressure may be exerted on the front of the victim's diaphragm, or the direct mouth-to-mouth method may be used. Artificial respiration, once started, must be continued, without loss of rhythm.

- **b.** Lay the victim in a prone position, one arm extended directly overhead, and the other arm bent at the elbow so that the back of the hand supports the head. The face should be turned away from the bent elbow so that the nose and mouth are free for breathing.
- c. Open the victim's mouth and remove any foreign bodies, such as false teeth, chewing gum, or tobacco. The mouth should remain open, with the tongue extended. Do not permit the victim to draw his tongue back into his mouth or throat.
- d. If an assistant is available during resuscitation, he should loosen any tight clothing to permit free circulation of blood and to prevent restriction of breathing. He should see that the victim is kept warm, by applying blankets or other covering, or by applying hot rocks or bricks wrapped in cloth or paper to prevent injury to the victim. The assistant should also be ever watchful to see that the victim does not swallow his tongue. He should continually wipe from the victim's mouth any frothy mucus or saliva that may collect and interfere with respiration.
- e. The resuscitating operator should straddle the victim's thighs, or one leg, in such manner that:
- (1) the operator's arms and thighs will be vertical while applying pressure on the small of the victim's back;
- (2) the operator's fingers are in a natural position on the victim's back with the little finger lying on the last rib;
- (3) the heels of the hands rest on either side of the spine as far apart as convenient without allowing the hands to slip off the victim;
- (4) the operator's elbows are straight and locked.
  - f. The resuscitation procedure is as follows:
- (1) Exert downward pressure, not exceeding 60 pounds, for 1 second.
- (2) Swing back, suddenly releasing pressure, and sit up on the heels.
- (3) After 2 seconds rest, swing forward again, positioning the hands exactly as before, and apply pressure for another second.
- g. The forward swing, positioning of the hands, and the downward pressure should be accomplished in one continuous motion, which requires 1 second. The release and backward swing require 1 second. The addition of the 2-second rest makes a total of 4



seconds for a complete cycle. Until the operator is thoroughly familiar with the correct cadence of the cycle, he should count the seconds aloud, speaking distinctly and counting evenly in thousands. Example: one thousand and one, one thousand and two, etc.

h. Artificial respiration should be continued until the victim regains normal breathing or is pronounced dead by a medical officer. Since it may be necessary to continue resuscitation for several hours, relief operators should be used if available.

#### RELIEVING OPERATOR.

The relief operator kneels beside the operator and follows him through several complete cycles. When the relief operator is sure he has the correct rhythm. he places his hands on the operator's hands without applying pressure. This indicates that he is ready to take over. On the backward swing, the operator moves and the relief operator takes his position. The relieved operator follows through several complete cycles to be sure that the new operator has the correct rhythm. He remains alert to take over instantly if the new operator falters or hesitates on the cycle.

#### STIMULANTS.

a. If an inhalant stimulant is used, such as aro-

matic spirits of ammonia, the individual administering the stimulant should first test it himself to see how close he can hold the inhalant to his own nostril for comfortable breathing. Be sure that the inhalant is not held any closer to the victim's nostrils, and then for only 1 or 2 seconds every minute.

**b.** After the victim has regained consciousness, he may be given hot coffee, hot tea, or a glass of water containing 12 teaspoon of aromatic spirits of ammonia. Do not give any liquids to an unconscious victim.

#### CAUTIONS.

- **a.** After the victim revives, keep him LYING QUIETLY. Any injury a person may have received may cause a condition of shock. Shock is present if the victim is pale and has a cold sweat, his pulse is weak and rapid, and his breathing is short and gasping.
- **b.** keep the victim lying flat on his back, with his head lower than the rest of his body and his hips elevated. Be sure that there is no tight clothing to restrict the free circulation of blood or hinder natural breathing. Keep him warm and quiet.
- c. A resuscitated victim must be watched carefully as he may suddenly stop breathing. Never leave a resuscitated person alone until it is CERTAIN that he is fully conscious and breathing nor mally.




Figure 1. Radio Receiver R-388/URR.

#### **CHAPTER 1**

#### **INTRODUCTION**

#### Section I. GENERAL

#### 1. Scope

This instruction book contains instructions for the installation, operation, maintenance, and repair of Radio Receiver R-388/URR. In addition to these instructions, there are two appendixes covering a list of references and an identification table of parts.

#### 2. Forms and Records

The following forms will be used for reporting unsatisfactory conditions of Army materiel and equipment.

- a. DD Form 6, Report of Damaged or Improper Shipment, will be filled out and forwarded as prescribed in SR 745-45-5 (Army), NAV DEPT SERIAL 85P00 (Navy), and AFR 71-4 (Air Force).
- b. DA AGO Form 468, Unsatisfactory Equipment Report, will be filled out and forwarded to the Office of the Chief Signal Officer as prescribed in SR 700-45-5.
- c. USAF Form 54, Unsatisfactory Report, will be filled out and forwarded to Commanding General, Air Materiel Command, Wright-Patterson Air Force Base, Dayton, Ohio, as prescribed in SR 700-45-5 and AFR 65-26.
- d. DA AGO Form 419, Preventive Maintenance Checklist for Signal Corps Equipment,

will be prepared in accordance with instructions on the back of the form.

e. Use other forms and records as authorized.

#### Section II. DESCRIPTION AND DATA

#### 3. Purpose and Use

- a. Radio Receiver R-388/URR is a communications receiver, having exceptional frequency stability and calibration accuracy. The receiver covers the frequency range from .5 to 30.5 mc (megacycles). Although useful as a general purpose communications receiver, its accuracy and stability make it especially useful where it is desired to receive known frequencies without searching or frequent readjustment, and for the reception of frequency-shift keying transmissions. It is therefore particularly adaptable to the reception of radioteletype signals.
- b. The receiver is intended for use as part of fixed or mobile installations. See the appropriate instruction book for complete details on each application.
- c. Figure 2 is a simplified block diagram of the receiver in use and shows the minimum additional equipment required for operation.
- d. Figure 3 is a simplified block diagram of the receiver in use with Radio Set AN/GRC-26A for the reception of radioteletype signals.




Figure 2. Receiver in use, simplified block diagram.




Figure 3. Receiver in use with frequency-shift converter for reception of radioteletype signals, simplified block diagram.

4. Technical Characteristics	Avc (automatic
a. Performance.	volume control) Less than 4-db increase in audio power output with an increase in r-f
Frequency range5 mc to 30.5 mc.	(radio-frequency) sig-
Receiver type Double or triple conversion superheterodyne.	nal from 5 to 125,000 uv (microvolts).
I-f frequency 500 kc (kilocycles).	Noise limiter Series type ahead of first audio stage, effective
Types of reception Voice, c-w (continuous- wave), and frequency- shift.	for c-w operation.  Output impedances 4- and 600-ohm impedances.
Number of tubes 18.	Audio-frequency
Tuning Linear, divided into thirty 1-mc tuning steps.	response With 1,000 cps (cycles per second) reference, response down not
Calibration Direct reading in mc and kc.	more than 3 db at 200 cps, and not more than
Method of	7 db at 2,500 cps.
calibration Built-in crystal oscillator (100 kc).	Antenna input impedance Unbalanced to match
Calibration points Every 100 kc.	short whip antenna
Frequency stability Over-all stability within	(50 ohms, 100 uuf (micromicrofarads)).
1 kc for average conditions; within 2 kc for extreme conditions.	Power requirements . 85 watts at 115 or 230 volts, 45 to 70 cps.
	Weight
Sensitivity A-m (amplitude - modu- lated) signal input of	b. Tuning Steps.
5 mv (millivolts) max-	BAND CHANGE switch position Coverage (mc)
imum required to pro- duce 500 mw (milli-	No. 1
watts) power output	No. 2
at a signal plus noise-	No. 3
to-noise ratio of 10 to 1.	No. 5
Selectivity Approximately 6 kc at 6 db (decibels) down,	No. 6
and not greater than	No. 7
20 kc at 60 db down	No. 9
(total bandwidth)	No. 10 9.5 to 10.5
from resonant fre- quency. With crystal	No. 11
filter in operation, at	No. 12
6 db down, the band-	No. 13
width may be varied	No. 15
from approximately .2 kc to 2.0 kc.	No. 16
	No. 17
Spurious signal responses Down at least 50 db.	No. 18

#### b. Tuning Steps (contd).

#### d. TUBE TABLE.

A separate carton contains the spare parts, all

of which are packed individually.

		· · ·					
		E switch position		erage (mc)	Symbol	Type	Function
		• • • • • • • • • • • • • • • • • • • •			V101	6AE5	R-f amplifier
					V102	6BE6	First mixer
No.	23		22.5	5 to 23.5	V103	6BE6	Intermediate mixer
		• • • • • • • • • • • • • • • • • • • •			V104	6BA6	Calibration oscillator
					V104 V105	6AK5	
							Crystal oscillator
					V106	6BE6	Second mixer
					V107	6BA6	First i-f (intermediate-frequency) amplifier
					V108	6BA6	Second i-f amplifier
c. H	HIGH-FR	REQUENCY OSC	ILLATOR V	105 Crys-	V109	6BA6	Third i-f amplifier
		D INJECTION			V110	12AX7	Detector and avc rectifier
		Receiver	Crystal	Injection	V110 V111	12AU7	Avc amplifier and i-f output
Crystal		frequency	frequency	frequency	V111 V112		
1	$egin{array}{c} 1 \ 2 \end{array}$	.5 to 1.5 1.5 to 2.5	4	8 and 12	V 112	12AX7	Noise limiter and a-f (au-
	3	2.5 to 3.5					dio-frequency) voltage amplifier
2	4	3.5 to 4.5	6	6	V113	6AQ5	A-f power amplifier
3	5	4.5 to 5.5	8	8	V114	6BA6	Beat-frequency oscillator
	6	5.5 to 6.5		8	V115	5V4	Power rectifier
	$\frac{13}{14}$	12.5 to 13.5 13.5 to 14.5		$\frac{16}{16}$	V116	0A2	Voltage regulator
4	7	6.5 to 7.5	10	10	V001	6BA6	Variable-frequency oscilla-
4	8	7.5 to 8.5	10	10	, 552	02110	tor
	17	16.5 to 17.5		20	V002	6BA6	Buffer amplifier
	18	17.5 to 18.5		20	7 002	01110	Builet amplifier
	27	26.5 to 27.5		30			
_	28	27.5 to 28.5	10	30	5. Pack	kaging Data	ı
5	$\frac{9}{10}$	8.5 to 9.5 9.5 to 10.5	12	$\frac{12}{12}$	Dodie T	) D (	200 /IIDD 1 24
	$\frac{10}{21}$	20.5 to 21.5		$\frac{12}{24}$			388/URR and its spare parts
	$\frac{1}{22}$	21.5 to 22.5		24			ort shipment in a wooden box. er and wooden box, protection
6	11	10.5 to 11.5	14	14			are, and vapors is obtained by
	12	11.5 to 12.5		14			ges and two cartons. The ar-
	25	24.5 to 25.5		28			e protective layers is shown in
	26	25.5 to 26.5		28	-		t panel of the receiver is pro-
7	15	14.5 to 15.5	9	18			d wooden frame. All sides of
	16	15.5 to 16.5		18			added with corrugated card-
8	19	18.5 to 19.5	11	22		_	ica gel are placed within the
0	20	19.5 to 20.5	10	22 26			the receiver to absorb any
9	$\begin{array}{c} 23 \\ 24 \end{array}$	22.5 to 23.5 23.5 to 24.5	13	$\frac{26}{26}$			when the receiver is packed.
	<b>4</b> ⁴±	20.0 10 24.0		20	·	o located III	mich one receiver is packed.

10

29

30

28.5 to 29.5

29.5 to 30.5

10.6


32

**32** 

#### 6. Description of Receiver (figs. 4 and 5)


- a. Radio Receiver R-388/URR is an 18-tube superheterodyne receiver for receiving a-m phone signals and c-w signals in the frequency range of .5 mc to 30.5 mc. The tuning range is divided into thirty 1-mc tuning steps which are selected by the BAND CHANGE knob at the lower right end of the receiver. Each change of band causes a different slide-rule type scale, graduated in tenths of megacycles, to appear in the upper MEGACYCLES dial opening. The center knob is the main tuning control, and it turns the KILOCYCLES dial which is visible through the lower opening. This dial is graduated in 1-kc intervals, and rotates exactly 10 times while the slide-rule MEGACYCLES dial is covering 1 mc. Frequency is read by adding the readings of both dials.
- b. The receiver is constructed as a panel and shelf assembly for rack mounting. Top and bottom covers on the chassis protect it from dust.

- c. Headphone and speaker jacks are provided at the lower left corner of the front panel. In addition, both 4- and 600-ohm output terminals are provided at the rear of the chassis.
- d. The receiver has a 100-kc crystal calibration oscillator which enables checking dial calibration every 1/10-mc interval throughout the tuning range. Intermediate dial readings are within 300-cycle accuracy.
- e. A coaxial antenna input connector and a coaxial connector for tapping the i-f output are also provided at the rear of the chassis.
- f. A second terminal board on the rear of the chassis permits connection of an external circuit to control the built-in remote-disabling relay.
- g. Power is applied through the cord extending from the rear of the chassis, with an overload protection fuse for the power input circuit also located at the rear of the receiver.



TM854-4

Figure 4. Radio Receiver R-388/URR, front view.



TM854-5

Figure 5. Radio Receiver R-388/URR, rear view.

#### 7. Running Spares

A group of running spares is supplied with the receiver to provide replacements for all normally expendable items, such as tubes, pilot lamps, and fuses. The following is a list of running spares:

- 1 tube, type 5V4G.
- 1 tube, type 6AK5.
- 1 tube, type 6AQ5.
- 1 tube, type 6BA6.
- 1 tube, type 6BE6.
- 1 tube, type 12AU7.
- 1 tube, type 12AX7.
- 1 tube, type 0A2.
- 5 fuses, cartridge type,  $1\frac{1}{2}$  ampere, 250 volts.
- 1 lamp, Mazda #47.

#### 8. Additional Equipment Required

The following material is *not* supplied as part of Radio Receiver R-388/URR but is necessary for its operation.

- a. A suitable antenna for the reception of 500-kc to 30.5-mc signals, either single wire or doublet, and a good ground connection where possible.
- b. A 115- or 230-watt source of ac (alternating current), capable of providing at least 80 watts of power.
- c. A headset or a loudspeaker of suitable impedance.
- d. A standard cabinet rack for mounting the receiver.

#### **CHAPTER 2**

#### **OPERATING INSTRUCTIONS**

## Section I. SERVICE UPON RECEIPT OF RADIO RECEIVER R-388/URR

#### 9. Siting (fig. 6)

The best location for radio equipment depends on the tactical situation and local conditions, such as the following: possible installation in a vehicle, the terrain, the type of housing available, the need to house the equipment where it cannot be seen, and the need of easy access to messengers. Best reception is obtained when the antenna is located in an open area with no large structures nearby which may cause attenuation of incoming signals. Avoid operation near steel structures. Choose, if possible, a location on a hilltop or elevation.

## 10. Uncrating, Unpacking, and Checking New Equipment

*Note*. For used or reconditioned equipment, refer to paragraph 13.

a. General. Equipment may be shipped in oversea packing cases (subpar. b below) or in domestic packing cases (subpar. e below). When new equipment is received, select a location where the equipment may be unpacked without exposure to the elements and which is convenient to the permanent or semipermanent installation of the equipment. Aside from checking to make sure that all carrying cases are present and that the equipment is undamaged, no special unpacking and uncrating procedures are necessary for equipment shipped in carrying cases.

Caution: Be careful in uncrating, unpacking, and handling the equipment; it is easily damaged. If it becomes damaged or exposed, a complete overhaul might be required or the equipment might be rendered useless.

b. Step-by-Step Instructions for Uncrating and Unpacking Export Shipments (fig.

- 7). (1) Place the packing case as near the operating position as convenient.
  - (2) Cut and fold back the steel straps.
- (3) Remove the nails with a nail puller. Remove the top and one side of the packing case. Do not attempt to pry off the sides and top; this may damage the equipment.
- (4) Remove the waterproof metal container or moistureproof barrier and any excelsior or corrugated paper covering the equipment inside the case.
- (5) Remove the equipment from its inner case and place it on the workbench or near its final location.
- (6) Inspect the equipment for possible damage incurred during shipment.
- c. OPENING CARDBOARD CARTON AND WATER-PROOF BARRIER. No special instructions are needed for opening the waterproof paper barrier and removing the equipment from the cardboard carton.
- d. CHECKING. Check the contents of the carton against the master packing slip. Check for broken tubes and check that tubes and crystal are inserted in the correct positions (par. 11).
- e. Unpacking Domestic Packing Cases. Radio equipment may be received in domestic packing cases. The instructions given in subparagraph b above also apply to unpacking domestic shipments. Cut the metal bands. Open the cartons that protect the equipment; or, if heavy wrapping paper has been used, remove it carefully and take out the components. Check the contents of the packing case against the master packing slip.

*Note*. Save the original packing cases and containers for both export and domestic shipments. They can be used again when the equipment is repacked for storage or shipment.










Figure 6. Siting, good and bad locations.




Figure 7. Packaging and packing of Radio Receiver R-388/URR.

#### 11. Installation

To install Radio Receiver R-388/URR proceed as follows:

a. Before installing the equipment, check the tubes. Remove the top dust cover from the chassis by removing the three screws which hold the dust cover to the rear of the chassis. A Phillips-head screw driver is mounted on the outside of the dust cover at the rear of the receiver (fig. 5). Check all tubes and crystals to see that they are in the correct sockets (fig. 8) and that none are broken. Note that all tubes except V115 are held in place by means of standard tube shields of the bayonet mounting type. Tube V115 and crystal Y111 are held in place by a strap and wingnut as shown. After

checking, replace the dust cover by first mating the three cut-outs along the upper edge of the dust cover with the three studs on the chassis, and then replacing the three hold-down screws on the back.

- b. Check the  $1\frac{1}{2}$ -ampere fuse mounted in the fuse holder at the rear of the chassis.
- c. The radio receiver is intended for mounting in a standard rack mounting. The front panel is 19 inches wide and  $10\frac{1}{2}$  inches high, and is slotted for mounting screws at points  $1\frac{1}{2}$ ,  $3\frac{3}{4}$ ,  $6\frac{3}{4}$ , and 9 inches from the bottom. A depth of  $13\frac{1}{4}$  inches must be available. For complete instructions on the installation of the receiver as part of complete radio sets, see the instruction book covering the particular set.




Figure 8. Radio Receiver R-388/URR, tube location diagram.

#### 12. Connections

When the radio receiver is to be installed as part of a particular unit, make all connections as described in the instruction book covering that set. When the radio receiver is to be used independently, make connections (figs. 2 and 9) as follows:

- a. Antenna Connection. (1) Connect the antenna and ground, by means of a coaxial cable and connector, to the ANTENNA jack (J101) on the rear of the receiver.
- (2) If the receiver is to be operated in conjunction with a transmitter, the receiver disabling relay (terminals 1 and 2 of E101) should be connected to the transmitter in such a way that the relay is energized by a 12-volt dc (direct current) when the transmitter is radiating.

- b. Power Connection. (1) The input power connection is made with the cord and plug (P101) which is permanently attached to the rear of the receiver chassis. Connection to a source of 115-volt 45- to 70-cycle ac should be made.
- (2) If it is required to operate the receiver on 230-volt 45- to 70-cycle ac, the leads from the power transformer (T108) will have to be reconnected inside the receiver as follows:
- (a) Disconnect transformer leads No. 2 and 3 from the input cord and power switch (S113), respectively, but leave leads No. 1 and 4 connected.
- (b) Connect leads No. 2 and 3 together, solder, and cover the splice with electricians tape.




Figure 9. Radio Receiver R-388/URR, rear view, showing connections.

- c. SPEAKER CONNECTION. (1) A speaker or an audio line, with approximately 600 ohms input impedance, can be connected by means of a standard cord and plug at the SPEAKER jack (J102) on the front panel. It can also be connected at the 600-ohm and ground terminals of the AUDIO terminal board (E102) at the rear of the receiver.
- (2) A speaker with a 4-ohm voice coil can be connected only by means of the 4-ohm and ground terminals of the AUDIO terminal board.
- d. HEADPHONES CONNECTION. Headphones of 600 or more ohms imepdance can be connected by means of a standard cord and plug at the PHONES jack (J103) on the front panel.
- e. I-F OUTPUT CONNECTION. When radioteletype reception is desired, connection to the radioteletype converters can be made by plugging in a 70-ohm coaxial cord and connector at the IF OUTPUT jack (J104) on the rear of the receiver. The radioteletype converter must be capable of tuning to the receiver 500 kc intermediate frequency.

## 13. Service Upon Receipt of Used or Reconditioned Equipment

- a. Follow the instructions in paragraph 10 for uncrating, unpacking, and checking the equipment.
- b. Check the used or reconditioned equipment for tags or other indications pertaining to changes in the wiring of the equipment. If any changes in wiring have been made, note the change in this manual, preferably on the schematic diagram.
- c. Check the operating controls for ease of rotation. If lubrication is required, refer to the lubrication instructions in chapter 3, section II.
- d. Perform the installation and connection procedures given in paragraphs 11 and 12.

#### Section II. CONTROLS AND OPER-ATION UNDER USUAL CONDITIONS

14. Controls and Their Use (fig. 10)

Table I lists the controls of the radio receiver and indicates their functions.

## TABLE I

Control	Function
OFF-STANDBY-ON switch (S113)	In OFF position, opens primary power circuit to turn equipment off completely. In STANDBY position, excites transformer producing filament and plate voltage but does not apply plate or screen voltage to three i-f amplifier tubes, thereby disabling receiver. In ON position (provided REMOTE relay is not energized) receiver is completely operative.
RF GAIN (R148)	Varies amount of fixed bias on r-f amplifier and three i-f amplifier tubes.
AUDIO GAIN (R154)	Controls audio power output.
BAND CHANGE knob	Band selector. Switches coils, capacitors, crystals, tuned circuits, tubes, and MEGACYCLES scale as required for each of 30 tuning steps. Each half revolution introduces another 1-mc tuning step.

#### TABLE I

### CONTROLS (contd)

Control	Function
MEGACYCLES scale	Indicates to nearest tenth mc (100 kc) the frequency to which receiver is tuned. Graduated in 10 divisions of 1/10 mc each, each division corresponding to one full turn of KILOCYCLES dial knob. The 1.5- to 2.5-mc and 2.5- to 3.5-mc band graduations are printed in red to indicate that the red scale on the KILOCYCLES dial must be used when operating on these bands.
KILOCYCLES dial knob	Main tuning control. Moves indicator across MEGA-CYCLES scale and turns KILOCYCLES dial. MEGACYCLES scale indicator moves one division for each full turn (100 divisions) of KILOCYCLES dial.
KILOCYCLES dial	Indicates tens and units figures, in kc, of frequency to which receiver is tuned. Combined with reading of MEGACYCLES dial gives tuned frequency in kc. For example, a reading of 14.1 on MEGACYCLES dial and a reading of 78 on KILOCYCLES dial indicates the frequency is 14,178 kc. There are two scales of 100 graduations each, running in opposite directions, one red, the other black. The red scale is used only for the 2.5- to 1.5-mc and 3.5- to 2.5-mc tuning steps.
ZERO ADJ. knob	Moves indicator line on KILOCYCLES dial a few divisions in either direction for calibration purposes.
BFO OFF-ON switch	Varies frequency of bfo (beat-frequency oscillator) to change pitch of audio tone for c-w reception. Frequency range is about 498.5 kc to 501.5 kc.
CALIBRATE OFF-ON switch (S118)	In ON position, 100-kc crystal oscillator V104 is operative for calibration purposes.
AVC OFF-ON switch (S115)	In ON position AVC is operative.
LIMITER OFF-ON switch (S116)	In ON position, automatic noise limiter is operative.
CRYSTAL FILTER SELECTIVITY switch (S114)	In position 0, crystal filter is not used and selectivity is broadest. In positions 1 through 4, crystal filter is in circuit with selectivity, becoming progressively sharper at higher numbers.

#### TABLE I

#### **CONTROLS** (contd)

Control	Function
CRYSTAL FILTER PHASING knob (capacitor C188)	Used for attenuating unwanted heterodyne frequencies. Raises or lowers, slightly, the rejection slot of the crystal filter.
METER INPUT-OUTPUT toggle switch (S117)	In OUTPUT position, connects meter to measure audio power output. In INPUT position connects meter as an S meter. Switch is momentary action type with INPUT as the normal position.
CAL. screw (C224)	Screw-driver adjustment for precise adjustment of crystal calibration to 100 kc.
BFO PITCH control	Adjusts the pitch of incoming c-w signals to suit the operator (bfo on).
Jacks and terminals	
ANTENNA jack (J101)	Connects antenna.
REMOTE terminal strip (E101)	Connects disabling relay with 12-volt d-c source.
IF OUTPUT jack (J104)	Connects i-f output to dual diversity unit for reception of radioteletype signals.
AUDIO terminal strip (E102)	Provides connection for loudspeaker.
FUSE (F101)	$1\frac{1}{2}$ -ampere cartridge fuse in series with a-c line.

#### 15. Starting Procedure

a. Preliminary. Set the front panel controls as follows:

Control	Position
RF GAIN	Between 7 and 9.
AUDIO GAIN	Between 1 and 2.
BAND CHANGE knob	To band desired.
BFO OFF-ON switch.	OFF.
CALIBRATE OFF-ON switch	OFF.
AVC OFF-ON switch	ON.
LIMITER OFF-ON switch	OFF.
CRYSTAL FILTER	
SELECTIVITY switch	0.
CRYSTAL FILTER	Alined with
PHASING control	mark on panel.

- b. STARTING. (1) Turn OFF-STANDBY-ON switch to ON.
- (2) Turn AUDIO GAIN control clockwise until noise or signal is heard. If there is no response, see paragraph 36.

#### 16. Types of Operation

- a. RADIO TELEGRAPH RECEPTION. (1) Place BFO switch to the ON position.
  - (2) Turn BFO PITCH control to midposition.
- (3) Carefully set KILOCYCLES control to frequency of desired signal. If c-w signal is present, the beat note will vary as the exact frequency is approached. Tune for zero beat.




Figure 10. Radio Receiver R-388/URR, front panel.

- (4) Turn BFO PITCH control to position 1, 2, 3, or 4 as required to produce a desirable operating tone or to make signal readable above interference or unwanted signals on adjacent frequencies.
  - (5) Throw LIMITER switch to ON position.
  - (6) Throw AVC switch to ON position.
- (7) Readjust AUDIO GAIN and RF GAIN controls to give suitable volume and best signal-to-noise ratio. See paragraph 36.
- (8) If unwanted heterodynes interfere with the signal, move CRYSTAL FILTER PHASING control back and forth until a setting is found for which the heterodyne is most attenuated. (The control will have to be moved farther for low-frequency heterodynes than for high ones.)

- b. Tone or Voice Reception. (1) Carefully set KILOCYCLES control to frequency of desired signal. If tone or voice signal is present, tune for loudest or least distorted signal.
- (2) Turn CRYSTAL FILTER SELECTIVITY control to a higher position only if necessary to minimize interference from unwanted signals on adjacent frequencies.
- (3) Throw LIMITER switch to ON position only if noise of the impulse type is being picked up.
- (4) Readjust AUDIO GAIN and RF GAIN controls to give suitable volume and best signal-to-noise ratio.
- (5)) If unwanted heterodynes interfere with the signal, move CRYSTAL FILTER PHASING control back and forth until a setting is found for which the heterodyne is most attenuated.

- c. Making Frequency Measurements. To determine accurately the frequency of an unknown signal or to make any frequency measurement, proceed as follows:
- (1) Calibrate the receiver in accordance with the instructions given in paragraph 17b.
- (2) Leave BFO switch at ON, and do not move BFO PITCH control after calibrating.
- (3) Tune in the signal. A beat note should be audible as the exact frequency of the signal is approached. Using only the KILOCYCLES control, tune until the beat note is zero beat.
- (4) The receiver is now tuned to the exact frequency of the signal that can be read on the dials.

#### 17. Calibrating Receiver

- a. Although the over-all tuning accuracy of the receiver is within about 1 kc, every 100-kc portion of the tuning range can be individually calibrated to an accuracy of about 300 cycles by means of the built-in 100-kc crystal oscillator and the ZERO ADJ. knob of the tuning dial. This oscillator emits a fundamental frequency of 100 kc and also every harmonic, 200 kc, 300 kc, etc., that is needed to cover the frequency range of the receiver. Three methods of calibrating the receiver can be used.
- b. Use the following procedure to calibrate any portion of the tuning range:
- (1) With the receiver on but the antenna disconnected, turn the dials to the nearest frequency which is an exact multiple of 100 kc in the range it is desired to calibrate. (For example, if it is desired to calibrate for a frequency of 14,230 kc, turn the dials to 14,200 kc.)
- (2) Turn the BFO switch to the ON position and set the BFO PITCH control to line up exactly with the index on the panel.
- (3) Turn the CALIBRATE switch to ON. A beat note should be audible.
- (4) Turn the KILOCYCLES control so that zero beat is obtained. Do *not* touch the BFO PITCH control.

- (5) Turn ZERO ADJ. control to move the dial indicator until it lines up exactly with 0 on the KILOCYCLES dial. The dial will now read accurately in this region.
- c. To adjust the 100-kc calibration crystal to exact frequency against standard frequency transmissions, such as those from station WWV (Bureau of Standards radio station located in Washington, D. C. (but only for frequencies which are exact multiples of 100 kc)), use the following procedure.
- (1) With the receiver on and the antenna connected, tune in the standard frequency signal. The BFO switch should be at ON and the BFO PITCH control knob marker position set to coincide with the panel mark. Using the main tuning knob, tune the WWV signal to zero beat.
- (2) Do not change the BFO PITCH and main tuning knob positions. Turn the CALIBRATE switch to ON.
- (3) If an audio signal is heard, carefully adjust the screw-driver CAL. adjustment for zero beat. The 100-kc signal harmonic is now exactly on frequency.
- d. To avoid the necessity of recalibrating a frequency range every time it is used, the lower edge of the opening for the KILOCYCLES dial is engraved with a 10-division scale. By making a record or log of the calibrated position of the hairline for any frequency range, the hairline can be reset to the same position without calibrating whenever the receiver is again tuned to the same frequency range.

#### 18. Zeroing Meter

To zero-set the meter for use as an input meter, proceed as follows.

- a. Turn the receiver on.
- b. Place the BFO switch in the OFF position.
- c. Turn the AVC switch ON.
- d. Turn the CALIBRATE switch to OFF.
- e. Turn the RF GAIN control to position 10.
- f. Short circuit the antenna terminals, and turn METER ZERO control R140 (on receiver chassis) until the INPUT meter reads zero.

#### 19. Stopping Procedure

To turn off the receiver, turn the OFF-STAND-BY-ON switch to OFF.

#### 20. Operating Precautions and Notes

The following notes will aid the operator in securing maximum performance from the receiving equipment.

- a. The AVC control should be in the ON position for practically all reception. However, it may be turned off for c-w reception if desired.
- b. For the best reception of weak keyed signals through noise picked up on the antenna or generated in the receiver, set the RF GAIN control to a higher number and reduce the setting of the AUDIO GAIN control to give the desired audio output level. The LIMITER control should be in the ON position.
- c. For the reception of phone or voice signals, keep the AVC control on and place the RF GAIN control as high as possible; use the AUDIO GAIN control to vary the output level in the loudspeaker or headset.

## Section III. OPERATION UNDER UNUSUAL CONDITIONS

#### 21. General

The operation of Radio Receiver R-388/URR may be difficult in regions where extreme cold, heat, humidity and moisture, sand conditions, etc., prevail. In the following paragraphs instructions are given on procedures for minimizing the effect of these unusual operating conditions.

#### 22. Operation in Arctic Climates

Subzero temperatures and climatic conditions associated with cold weather affect the efficient operation of the equipment. Instructions and precautions for operation under such adverse conditions follow:

- a. Handle the equipment carefully.
- b. Keep the equipment warm and dry, if possible.
- c. Wear a knitted woolen cap over the earphones when operating in the open air with headsets that do not have rubber earpieces. Frequently, when headsets without rubber earpieces are worn, the edges of the ears may freeze without the operator's being conscious of this condition. Never flex rubber earcaps, since this action may render them useless. If water gets into the receivers, or if moisture condenses within them, it may freeze and impede the actuation of the diaphragm. When this happens, remove the bakelite cap and remove the ice and moisture from the receiver.
- d. When equipment which has been exposed to the cold is brought into a warm room, it will start to sweat and will continue to do so until it reaches room temperature. When the equipment has reached room temperature, dry it thoroughly. This condition also arises when equipment warms up during the day after exposure during a cold night.

#### 23. Operation in Tropical Climates

When operated in tropical climates, radio equipment may be installed in tents, huts, or, when necessary, in underground dugouts. When equipment is installed below ground and when it is set up in swampy areas, moisture conditions are more acute than normal in the tropics. Ventilation is usually very poor, and the high relative humidity causes condensation of moisture on the equipment whenever the temperature of the equipment becomes lower than the ambient air. To minimize this condition, place lighted electric bulbs under the equipment.

#### 24. Operation in Desert Climates

- a. Conditions similar to those encountered in tropical climates often prevail in desert areas. Use the same measures to insure proper operation of the equipment.
- b. The main problem which arises with equipment operation in desert areas is the large

amount of sand, dust, and dirt which enters the moving parts of radio equipment, such as gears and bearings. The ideal preventive precaution is to house the equipment in a dustproof shelter. Since, however, such a building is seldom available and would require air conditioning, the next best precaution is to make the building in which the equipment is located as dustproof as possible with available materials. Hang wet sacking over the windows and doors, cover the inside walls with heavy paper, and secure the side walls of tents with sand to prevent their flapping in the wind.

- c. Never tie power cords, signal cords, or other wiring connections to either the inside or the outside of tents. Desert areas are subject to sudden wind squalls which may jerk the connections loose or break the lines.
- d. Take care to keep the equipment as free from dust as possible. Make frequent preventive maintenance checks (ch. 3). Pay particular attention to the condition of the lubrication of the equipment. Excessive amounts of dust, sand, or dirt that come into contact with oil and grease result in grit, which will damage the equipment.

#### CHAPTER 3

#### ORGANIZATIONAL MAINTENANCE INSTRUCTIONS

## Section I. ORGANIZATIONAL TOOLS AND EQUIPMENT

#### 25. Tools and Materials

The tools and materials contained in Tool Equipment TE-41 (the ordinary hand tools and materials normally available to organizational maintenance personnel) are required for organizational maintenance of the receiver. The tools are listed in Department of the Army Supply Catalog SIG 6-TE-41.

#### 26. Special Tools

- a. A set of four wrenches of different sizes for set screws of the fluted socket type is mounted in a tension clasp on the under side of the dust cover.
- b. A 3/16-inch steel rod with a 90° bend, machined at each end to handle Phillips type screws, is mounted on the outer side rear of the dust cover, in a retainer.

c. Two phenolic alinement tools are mounted inside the receiver in a tension clasp near the meter.

## Section II. PREVENTIVE MAINTENANCE SERVICES

#### 27. Definition of Preventive Maintenance

Preventive maintenance is work performed on equipment (usually when the equipment is not in use) to keep it in good working order so that break-downs and needless interruptions in service will be kept to a minimum. Preventive maintenance differs from trouble shooting and repair since its object is to prevent certain troubles from occurring. See AR 750-5.

#### 28. General Preventive Maintenance Techniques

a. Use #0000 sandpaper to remove corrosion, never use emery paper.

- b. Use a clean, dry, lint-free cloth or a dry brush for cleaning.
- (1) If necessary, except for electrical contacts, moisten the cloth or brush with Solvent, dry-cleaning (SD), then wipe the parts dry with a clean cloth.
- (2) Clean electrical contacts with a cloth moistened with carbon tetrachloride. Then wipe them dry with a clean cloth.
- c. If available, use dry compressed air at a line pressure not exceeding 60 pounds per square inch to remove dust from inaccessible places; be careful however, or mechanical damage from the air blast may result.
- d. For further information on preventive maintenance techniques refer to TB SIG 178.

#### 29. Performing Preventive Maintenance

The following preventive maintenance operations should be performed by organizational personnel at the intervals indicated, unless these intervals are reduced by the local commander, or unless the conditions of operation dictate otherwise.

**Caution:** Screws, bolts, and nuts should not be tightened carelessly. Fittings tightened beyond the pressure for which they are designed may be damaged or broken.

#### **DAILY**

- 1. Clean exterior of cabinet and dial faces.
- 2. Set ZERO ADJ. on KILOCYCLES dial (ch. 4).
  - 3. Check for loose dial knobs.

#### WEEKLY

- 1. Check calibration oscillator (par. 17) against station WWV or some other stable frequency source.
- 2. Check the meter for zero adjustment. Use a nonmetallic screw driver to adjust METER ZERO control R140 located inside the receiver to the left of the BFO PITCH shaft.
- 3. Blow dust out of interior of receiver, upper surface only, and dust off MEGA-CYCLE dial cylinder.
- 4. Inspect fuse F101 and its fuse holder for corrosion, cracks, and lack of tension sufficient to insure good contact.
- 5. Inspect power transformer T108 for excessive heating or lamination buzz.

#### MONTHLY

Remove receiver from rack. Disconnect all outlets. Make visual inspection of the following, replace if necessary and clean.

- 1. Check tube sockets for dirt and corrosion. To remove shields, press down, turn counterclockwise and lift over tube.
  - 2. Check tubes, replace if necessary.

**Caution:** These tubes, except the rectifier, are of the miniature type, with wire pins that bend easily. If it has been determined that a particular tube is malfunctioning, check the pins and sockets for possible misalinement before discarding.

3. Turn receiver over, dial face downward, on a flat surface so that the draw handles support it. With a Phillips screw driver remove 15 screws from base plate and 4 screws from folded top end of plate.

#### MONTHLY (contd)

Slide off plate exposing under side of receiver.

- 4. Check for corrosion and leaking electrolyte, particularly about base of the filter unit, C217, and the bathtub capacitors.
- 5. Inspect base plate for telltale signs of solder or electrolyte stains.
- 6. Inspect resistors for blistering, discoloration, or other indications of overheating.
- 7. Check relay for indications of malfunctioning. Usually the r-f section will be faulty if the relay is burned out. Burnish contacts.
- 8. With probe, using light pressure, check for loose connections and cold solder joints.
- 9. Inspect switch disks for dirt, corrosion, and loose contacts.

**Caution:** Do not insert probe or screw driver between contacts of switches. This action may *spring* the contacts.

- 10. Check PHONES and SPEAKER jacks J103 and J102 for tight fit and good contact.
- 11. Check wires, cords, cables, shields, and tubing, for cracks, cuts, frayed insulation, grounds, and shorts.
- 12. Check crystal terminal strip on the chassis under side for secure fit. If the crystals are to be removed, it is recommended that they be taken out and replaced individually so that they will not be returned to the wrong sockets.
- 13. Check mounting screws in tube sockets, etc., for mechanical looseness.
- 14. Inspect variable capacitors for dirt, corrosion, and bent plates.

#### MONTHLY (contd)

- 15. Check coils for dirt, corrosion, and damaged turns.
- 16. Check the dry disk rectifier, CR101, for loose connections.
- 17. Check band switching gears and cams for excessive accumulation of grit (par. 30).
  - 18. Dust the interior.
- 19. Replace base plate and screws, using caution when tightening.

## Section III. LUBRICATION AND WEATHERPROOFING

#### 30. Lubrication Instructions

- a. The lubrication requirements of Radio Receiver R-388/URR are minimum. It is only necessary to cover the tuning gear train teeth cam edges and slug table riders with a light grease film of AN-G-25 viscosity.
- b. Gasoline will not be used as a cleaning fluid for any purpose.
- c. Remove old grease with lint-free cloth moistened with carbon tetrachloride or solvent (SD).
  - d. Wipe with dry cloth and apply lubricant.

#### 31. Weatherproofing

a. General. Signal Corps equipment, when operated under severe climatic conditions, such as prevail in tropical, arctic, and desert regions, requires special treatment and maintenance. Fungus growth, insects, dust, corrosion, salt spray, excessive moisture, and extreme temperatures are harmful to most materials.

- b. TROPICAL MAINTENANCE. A special moisture proofing and fungiproofing treatment has been devised which, if properly applied, provides a reasonable degree of protection. This treatment is explained in TB SIG 13 and TB SIG 72.
- c. WINTER MAINTENANCE. Special precautions necessary to prevent poor performance or total operational failure of equipment in extremely low temperatures are explained in TB SIG 66 and TB SIG 219.
- d. DESERT MAINTENANCE. Special precautions necessary to prevent equipment failure in areas subject to extremely high temperatures, low humidity, and excessive sand and dust are explained in TB SIG 75.
- e. Lubrication. The effects of extreme cold and heat on materials and lubricants are explained in TB SIG 69. Observe all precautions outlined in TB SIG 69, and pay strict attention to all lubrication orders when operating equipment under conditions of extreme cold or heat. Refer to section III of this chapter for detailed instructions.

#### 32. Rustproofing and Painting

a. When the finish on the front panel has been badly scarred or damaged, rust and corrosion can be prevented by touching up bared surfaces. Use #00 or #000 sandpaper to clean the surface down to the bare metal; obtain a smooth bright finish.

**Caution:** Do not use steel wool. Minute particles frequently enter the equipment and cause short circuits.

b. To touch up, apply paint with a small brush. When numerous scars and scratches warrant a complete repainting of the front panel, remove all knobs, mask the shafts, jacks, dials, meter, and trim, and spray-paint the entire panel. Remove rust spots, before painting, by cleaning the corroded metal with solvent (SD). In severe cases it may be necessary to use solvent (SD) to soften the rust, and to use sandpaper to prepare the spot for painting. Paint used will be authorized and consistent with existing regulations.

## Section IV. TROUBLE SHOOTING AT ORGANIZATIONAL MAINTENANCE LEVEL

*Note.* Trouble shooting performed by field maintenance personnel will be published in a field maintenance manual for this equipment. When the manual is published, it will be listed in SR 310-20-4.

#### 33. Scope

The trouble shooting and repair work that can be performed at the organizational maintenance level (operators and repairmen) is necessarily limited in scope by the tools, test equipment, and replaceable parts issued, and by the existing tactical situation. Accordingly, trouble shooting is based on the performance of the equipment and the use of the senses in determining which part is at fault.

#### 34. Visual Inspection

- a. Failure of this equipment to operate properly will usually be caused by one or more of the following faults.
  - (1) Burned-out fuse.
  - (2) Defective tube.
  - (3) Faulty antenna connections.
  - (4) Faulty loudspeaker or phone connections.
  - (5) Antenna or lead-in grounded.
  - (6) Defective plug and cord.
  - (7) Line voltage low or not applied.
- (8) Corrosion or excessive accumulation of dirt in the set.
  - (9) Break-in relay burned out.
  - (10) Dial knobs loose.
- b. When failures are encountered and the cause is not immediately apparent, check as many of the above items as is practicable before starting a detailed examination of the receiver components. If possible, obtain information from the operator of the equipment regarding performance at the time the trouble occurred.

## 35. Trouble Shooting, Using Equipment Performance Checklist

- a. GENERAL. The equipment performance checklist will help the operator locate trouble in the equipment. This list indicates the item to be checked, the normal indications of correct operation, and the corrective measures the operator can take. To use the list, follow the items in numerical sequence.
- b. ACTION OR CONDITION. For some items, the information given in the action or condition column consists of various switch and control settings under which the item is to be checked. For other items it represents an action that must be taken to check the normal conditions given in the normal indications column.
- c. NORMAL INDICATIONS. The normal indications listed include the visible and audible signs that the operator should perceive when he checks the items. If the indications are not normal, the operator should apply the recommended corrective measures.
- d. Corrective Measures. The corrective measures listed are those the operator can make without turning in the equipment for repairs. A reference in the table to chapter 5 indicates that the trouble cannot be corrected during operation and that trouble shooting must be done by the higher echelons. This would be a normal procedure. However, if the tactical situation requires that communication be maintained, and if the set is not completely disabled, the operator must maintain the set in operation as long as it is possible to do so.

#### 36. Equipment Performance Checklist

	Item No.	Item	Action or condition	Normal indications	Corre <b>ct</b> ive measures
Р	1	Antenna.	Lead-in wire con- nected.		
R					
E	2	Loudspeaker.	Speaker cords con- nected to AUDIO terminals at rear		
P			of set.		
A	3	Phones.	Inserted securely in PHONES jack.		
R			,		
A	4	Dual diversity converter.	Lead-in inserted securely in IF OUTPUT jack.		
Т			OUTIOT Jack.		
О	5	Line cord.	Line cord plug inserted into socket of 110-volt 50-60		
R			cycle a-c source.		
Y	6	CRYSTAL FILTER SELECTIV- ITY control.	Set at zero position.		

#### 36. Equipment Performance Checklist (contd)

	Item No.	Item	Action or condition	Normal indications	Corrective measures
	7	LIMITER OFF-ON switch.	Rotate to OFF.		
	8	AVC OFF-ON control.	Set at ON.		
	9	RF GAIN control.	Set at 10.		
	10	BFO OFF-ON control.	Turn to OFF.		
	11	AUDIO GAIN control.	Set at 7.		
	12	CALIBRATE OFF-ON switch.	Turn to OFF.		
S T A R T	13	OFF-STAND- BY - ON switch.	Turn to ON.	Dial lamp lights.	Check fuse F101 at rear of set. If blown, try to determine cause by visual inspection before inserting new fuse. Check line cord and power source.
				Rushing noise is heard at output.	Check tubes first by feeling. Look for tube too hot or cold. Tap tube lightly and listen for pop which indicates defect. Replace tube with one known to be in good condition. Check speaker and connections. Look for short or ground if speaker is remotely operated.

#### 36. Equipment Performance Checklist (contd)

	Item No.	Item	Action or condition	Normal indications	Corrective measures
E Q U I P P E R	14	KILOCYCLES dial knob.	Set BAND CHANGE switch at any desired position. Tune across entire band by rotating KILOCYCLES dial knob.	Receiver tracking on signals. Meter in input position fluctuates with varying signal strength.	If normal signals are heard, but meter shows no reaction, trouble shooting is necessary. If no signals or weak signals are heard check antenna for firm connections. Check shield for fraying that might ground antenna. Check soldered connections for corrosion or high resistance. Check ground along antenna. Vary ANT. TRIM con-
O R				·	trol for optimum reception.
M A N	15	BAND CHANGE switch.	Check each of the tuning steps. Use procedures outlined in item 14 above.		
C E	16	PHONES jack.	Insert phones plug into jack.	Signals are audible.	Check phones, cord and plug. Check for tight fit in jack.
	17	RF GAIN control.	With set tuned to a particular sta- tion, rotate con- trol.	Strength of signal increases then decreases.	Refer to chapter 5, section II.
	18	AUDIO GAIN control.	Rotate control.	Signal strength changes proportionally.	Refer to chapter 5, section II.

#### 36. Equipment Performance Checklist (contd)

Item No.	Item	Action or condition	Normal indications	Corrective measures
19	AVC OFF-ON switch.	Turn to ON.	Signal level stabilizes. Meter becomes insensitive.	Refer to chapter 5, section II.
20	CRYSTAL FILTER SELECTIV- ITY switch.	Rotate switch through posi- tions 1, 2, 3, 4.	Tuning becomes progressively sharper.	Refer to chapter 5, section II.
21	CRYSTAL FILTER PHASING control.	Rotate control in arc about centering index.	Undesirable heter- odynes should be tuned out.	Refer to chapter 5, section II.
22	LIMITER OFF-ON switch.	Turn switch to ON. Tune to station on one of the lower bands.	Noise peaks are reduced.	Refer to chapter 5, section II.
23	BFO OFF-ON switch.	Turn switch to ON and tune in a c-w station on one of the higher bands.	Beat-frequency signal is heard at output.	Check BFO tube V114. Refer to chapter 5, section II.
24	BFO PITCH control.	With BFO OFF-ON switch ON, rotate BFO PITCH control.	A change in audio pitch is noted at output.	Refer to chapter 5, section II.
25	ANT. TRIM control.	Rotate control in small arc.	As optimum match is met, signal increases.	Refer to chapter 5, section II.
26	CALIBRATE OFF - ON oscillator switch.	Turn to ON. Turn BFO OFF-ON switch ON. Ro- tate main tuning dial through 1 mc.	Audio beat note is heard at every 100 kc.	Refer to chapter 5, section II.

#### CHAPTER 4

#### THEORY OF OPERATION

## Section I. ELECTRICAL THEORY OF RECEIVER

#### 37. General

- a. Although Radio Receiver R-388/URR uses the basic superheterodyne principle, it differs from the conventional types: It uses single, double, or triple conversion (mixing) when tuning over the entire frequency spectrum of .5 to 30.5 mc.
- b. The tuning range is divided into thirty 1-mc steps by a system of switches and coils in the r-f amplifier, first mixer, crystal oscillator, and variable i-f circuits. Band changing in 1-mc steps consists of moving powdered iron slugs into selected coils changing the L-C (inductance-capacitance) ratio of the tank circuits by varying the inductances, thus changing the resulting resonant frequencies. Fine tuning is then attained by a cam arrangement controlling the precise position of the powdered iron slugs suspended from a common shaft (pars. 57 and 58). By changing coils and repeating the slug tuning procedure, a highly selective and stable system is attained.
- c. When an incoming signal on bands 4 to 30 (3.5- to 30.5-mc) is mixed with the predetermined frequency of the crystal oscillator, V105, the first mixed output frequency (fig. 12) will always be either in the 2.5- to 1.5- or the 3.5- to 2.5-mc range, depending on the variable i-f switch which selects the 2.5- to 1.5-mc pass for the even-numbered bands and the 3.5- to 2.5-mc pass for the odd-numbered bands. The signal is then fed to the second mixer, V106, and beat with a calibrated variable frequency oscillator-buffer amplifier signal (V001, V002) to produce an i-f output frequency of 500 kc. This 500-kc output is then fed through a crystal filtering

network, Y112. From then on the equipment follows a conventional pattern, with three stages of i-f amplification (V107, V108, and V109); an avc-detector section, V110; beat-frequency oscillator V114; avc amplifier and i-f output V111; noise limiter and a-f voltage amplifier V112; and audio power amplifier V113 sections (fig. 11).

- d. The only exceptions to the procedures as outlined above are tuning steps 1, 2, and 3. Tuning step 1 uses an intermediate mixer, V103, between the first and second mixers as described above. The 4-mc crystal selected by switch S109 (fig. 42) will produce a crystal oscillator (V105) output signal of 12 mc (third harmonic) for the first mixer. The first mixer, V102, output to the intermediate mixer, V103, will then be in the order of 11.5 mc to 10.5 mc. At the same time, by means of split plate-tank-coil tuning, crystal oscillator V105 will also feed to the intermediate mixer, an 8-mc signal (second harmonic of 4 mc) which, when beat with the 11.5mc to 10.5-mc input signal will cause the intermediate mixer to produce a signal in the 3.5- to 2.5-mc range. This signal is then applied to the second mixer, V106, where it is beat with the 3- to 2-mc output of the vfo (variable frequency oscillator) to obtain an intermediate frequency of 500 kc (fig. 11). Since bands 2 and 3 correspond to the input frequencies of the second mixer (2.5- to 1.5- and 3.5- to 2.5mc), incoming signals on these bands are fed directly from the r-f amplifier to the second mixer, V106.
- e. The power supply uses a conventional full-wave high-vacuum rectifier, V115, for 115-volt operation, with a two-section choke input filter.
- f. The equipment uses 18 tubes, 3 of which are dual-triodes. Their functions are discussed in the following circuit descriptions.






Figure 11. Radio Receiver R-388/URR, over-all block diagram.



### BLOCK DIAGRAM BANDS 2-3



### BLOCK DIAGRAM BAND I




Figure 12. Radio Receiver R-388/URR, significant block diagrams of bands.

### 38. Radio-frequency Amplifier V101

The r-f amplifier stage uses a type 6AK5 miniature pentode, V101, the output of which is coupled into either the first or second mixer stages, depending on the position of the BAND CHANGE switch. In tuning step 1, the receiver

uses triple conversion and the r-f amplifier output feeds into the grid circuit of the first mixer. In tuning steps 4 through 30, the amplifier output is also fed into the first mixer, and the receiver uses double conversion. In tuning steps 2 and 3, the amplifier feeds into the grid circuit of the second mixer and the receiver uses single conversion.




Figure 13. R-f amplifier, tuning step 1, schematic diagram.

a. Tuning Step 1. With the BAND CHANGE switch at tuning step 1 (.5 to 1.5 mc), the following action taken place in the r-f amplifier (fig. 13). The incoming signal at AN-TENNA jack J101 is applied to the grid circuit through capacitor C233 which, with ANT. TRIM variable capacitor C230, forms the antenna matching network. The r-f amplifier grid circuit is tuned to resonance with the signal by permeability-tuned inductance L101. Trimmer capacitor C102 is adjusted to improve the response at the h-f (high-frequency) end. Capacitor C101 is large (820 uuf) so that the effect of tube input capacitance changes (Miller effect) in frequency will be negligible. The tuned r-f signal is then fed through capacitor

C113 to the control grid, pin 1, of V101. Resistors R101 and R102 are the grid return and decoupling resistors, respectively. Capacitor C114 provides the interstage avc (automatic volume control) decoupling. Capacitor C111 couples calibration oscillator tube V104 output to the grid of V101. The cathode and suppressor grids of tube V101 are grounded. The screen grid, pin 6, potential is determined by dropping resistor R104. Resistor R104, in conjunction with capacitor C115 forms the screen decoupling network. The r-f amplifier output is impedance-coupled to the grid of the first mixer tube, V102, by resistor R105, capacitor C117, and permeability-tuned inductor L110. Resistor R105 is the r-f amplifier tube V101 plate load. Capacitor C126 and resistor R106 form the tube V101 plate decoupling network. Capacitor C118 is used to approximately tune the resonant circuit and trimmer. Capacitor (C119) is the alinement trimmer for inductor L110. Capacitors C116 and C117 are the interstage coupling capacitors.

- b. TUNING STEP 2. Figures 14 and 42 show the circuit components of the r-f amplifier when tuned to step 2 (2.5 to 1.5 mc). The function of the grid circuit is essentially the same as that for tuning step 1, with the exception that antenna coupling capacitor C234 is cut into the circuit by switch S102 (fig. 42) while switch S103 (fig. 42) cuts in the grid tank composed of capacitors C104 and C103 and inductor L102 (par. 55). The plate circuit is tuned by permeability-tuned inductor L116, band-setting trimmers C175 and C177; alinement trimmer C174 provides the vernier tuning of the tank. Capacitor C220 provides the interstage coupling. Permeability-tuned inductor L118 in conjunction with band-setting trimmers C181, C179, and alinement trimmer C180 forms the tuned grid circuit for the second mixer, V106.
- c. Tuning Step 3. The r-f amplifier functions in the same manner for tuning step 3 (3.5 to 2.5 mc) as explained for tuning step 2 with the exception of the change in tuning components for the grid and plate circuit (fig. 14). In tuning step 3, as with all the odd-numbered tuning steps, permeability-tuned inductors L116 and L118 are shunted with trimmer inductors L117 and L119 to lower the tuned frequency. Refer to paragraph 55 for bandswitch information.
- d. Tuning Steps 4 through 30. The r-f amplifier grid and plate tuning components for tuning steps 4 to 7 (3.5 to 7.5 mc), tuning steps 8 to 15 (7.5 to 15.5 mc), and tuning steps 16 to 30 (15.5 to 30.5 mc) are shown in figure 15.

### 39. First Mixer

The purpose of the first mixer, V102 (a pentagrid converter tube, type 6BE6), is to mix electronically the amplified r-f output of tube

V101 on all tuning steps (except 2 and 3) with the output of the crystal oscillator tube, V105, type 6AK5. The first mixer output frequency will always be either in the 2.5- to 1.5-mc range or in the 3.5- to 2.5-mc range, depending on whether the tuning steps are even-numbered or odd-numbered, respectively. In tuning step 1, the first mixer output is applied to the input side of the intermediate mixer, and in tuning steps 4 through 30 the first mixer output is applied to the input side of the second mixer (fig. 12). The first mixer is not used in tuning steps 2 and 3. Table II of paragraph 54 shows the grid and plate components of the first mixer circuit for the different tuning steps.

a. TUNING STEP 1 (.5 to 1.5 MC). In tuning step 1 (fig. 16), the signal voltage is heterodyned with a 12-mc signal from the crystal oscillator, V105, so that the usable output of the mixer will be between 11.5 to 10.5 mc. Capacitor C116 couples the output of r-f amplifier V101 to the grid (pin 1) of the first mixer tube. V102. The mixer grid r-f circuit consists of permeability-tuned inductor L110, fixed trimmer capacitor C118, and alinement trimmer capacitor C119. The .5- to 1.5-mc signal is applied to what is normally called the oscillator grid and the 12-mc oscillator signal from the crystal oscillator, V105, is applied to the control grid (pin 7) of the first mixer tube, V102. The 12-mc oscillator signal is applied through capacitor C136 and across the grid resistor R108 which is connected between pin 7 grid and ground. Electronic mixing of the two injected voltages results in the usual sum, difference, and original voltages being produced and present in the plate current stream. The difference voltage (11.5 to 10.5 mc) r-f signal is selected by the tuned circuit in the mixer plate circuit for application to the succeeding stage, the intermediate mixer, V103. The signal voltage is developed across the plate load inductor L114, which is permeabilitytuned as part of the ganged slug racks. The developed r-f voltage is impedance-coupled into the intermediate mixer stage, through capacitor C137 to inductor L115 which is the grid coil for the intermediate mixer. The plate circuit of the first mixer, V102, is decoupled from the power supply by resistor R110 and capacitor C138. The first mixer uses cathode bias, which is developed







Figure 14. R-f amplifier, tuning steps 2 and 3, schematic diagram.



TUNING STEPS 4 THROUGH 7 (3.5-7.5 MC)



TUNING STEPS 8 THROUGH 15 (7.5-15.5 MC)



TUNING STEPS 16 THROUGH 30 (15.5-30.5 MC)

Figure 15. R-f amplifier, tuning steps 4 through 30, schematic diagram.

by cathode current flow through bias resistor R107. Capacitor C134 is the cathode bypass capacitor. The screen voltage is supplied through voltage-dropping resistor R109 which is bypassed by capacitor C135.

b. Tuning Steps 4 through 30 (3.5 to 30.5 MC). The first mixer circuit for tuning steps 4 through 30 is shown in figure 17. The circuit is the same as for tuning step 1, except that the grid and plate tuning components change through the various frequency ranges and the output of the first mixer is fed to the input side of the second mixer, V106, instead of to the intermediate mixer, V103. Figure 15 shows the grid tuning components for the first mixer, V102. Capacitor C116 (fig. 17) is connected from the plate of V101 to the grid (pin 1) of the first mixer V102 and provides the r-f coupling to the grid coils. Capacitor C133 parallels capacitor C116 in tuning steps 4 through 7 (the lower

INDUCTANCE LII4 IS TUNED SIMULTANEOUSLY

WITH THE R-F UNIT.

frequency tuning steps), where increased capacitive coupling is required. The output of the first mixer will be in the range of 2.5 to 1.5 mc on the even-numbered tuning steps, and 3.5 to 2.5 mc on the odd-numbered tuning steps. Inductor L116 is used to tune to the i-f frequency in plate circuit on the even-numbered tuning steps. On the odd-numbered tuning steps, inductor L116 is shunted by L117 to enable tuning to a higher i-f frequency. Only inductor L116 is tuned by the slug rack. Capacitors C177 and C175 are fixed trimmers. Trimmer capacitor C174 is used for alinement. Signals are transferred from the plate load inductance of the first mixer to the grid circuit of the second mixer, V106, by impedance coupling through capacitors C220 and C221. The grid circuit of the second mixer is tuned by inductor L118 on the even-numbered tuning steps, and by inductor L118 shunted by L119 on the odd-numbered tuning steps. Plate circuit decoupling for the first mixer, V102, is provided by resistor R124 and capacitor C178.





Figure 16. First mixer, tuning step 1 only, schematic diagram.

TM854-16



NOTES:

Figure 17. First mixer, tuning steps 4 through 30, schematic diagram.

FROM PIN 5
R-F AMPL

### 40. Intermediate Mixer (fig. 18)

The intermediate mixer, V103, tube type 6BE6, operates only on tuning step 1. Its purpose is to beat a signal from the first mixer in the range of 11.5 to 10.5 mc with a 8-mc signal from the h-f oscillator, V105, so that a signal will be fed to the second mixer V106 in the range of 3.5 to 2.5 mc. The r-f signal across permeability-tuned inductor L114 in the plate circuit of the first mixer, V102, is impedance-coupled to inductor L115 in the intermediate mixer grid circuit (fig. 18). Capacitor C137 provides the coupling, and capacitor C138 is the plate bypass to ground for the first mixer. Trimmer capacitors C139 and C140, in conjunction with inductor

L115, form the grid tank circuit of V103. The signal impressed on the control grid (pin 7) of V103 is beat with the crystal oscillator (V105) frequency, introduced at injection grid (pin 1), through capacitor C143. Resistor R112 is the injection grid resistor. Resistor R111 provides the cathode bias; capacitor C141 is the cathode bypass to ground. The operating voltage of the screen grid (pin 6) is determined by dropping resistor R113. Capacitor C142 is the screen grid r-f bypass. Resistor R124 and capacitor C178 provide the plate circuit decoupling (fig. 18). The output at the plate (pin 5) is fed through a 1,250-kc wave trap consisting of inductor L124 and capacitor C159 and the variable i-f coil section to the second mixer, V106.




Figure 18. Intermediate mixer, schematic diagram.

### 41. Variable Intermediate Frequency

The variable intermediate frequency consists of two ranges: one for a frequency of 2.5 to 1.5 mc and the other for 3.5 to 2.5 mc, used on even-numbered and odd-numbered bands, respectively. Using two variable i-f bands in this manner, cuts in half the number of crystals

necessary in the h-f oscillator, since each crystal fundamental frequency, or useful harmonic thereof, is used for two bands. Inductors L116 and L118 are the 2.5- to 1.5-mc coils, and are the coils in which the tuning slugs travel. The 3.5- to 2.5-mc range is obtained by shunting L116 with L117, and L118 with L119 to raise the resonant frequencies of L116 and L118.




Figure 19. Second mixer and variable intermediate frequency, schematic diagram.

Tank switch sections S110 and S111 alternately switch in and switch out shunting coils L117 and L119 as the band switch is rotated. Bandsetting capacitors C175 and C177 tune inductor L116. Trimmer capacitor C174 facilitates alinement at the h-f end of the coil. Capacitors C179 and C181 are fixed trimmers for variable inductor L118, and C180 is the alinement trimmer. Capacitors C176 and C182 are the alinement trimmers for h-f tuning of L117 and L119, respectively. Capacitors C220 and C221 provide the coupling for coils L116 and L118 and L117 and L119, respectively.

#### 42. Second Mixer

The purpose of second mixer V106 is to mix electronically the i-f signal with the signal from the vfo so that an intermediate frequency of 500-kc will be developed at the second mixer, V106, output. The second mixer stage uses a 6BE6 pentagrid converter type tube. The vfo signal is fed through a shielded cable, across the filter network composed of inductor L125 and capacitor C168 (fig. 19). This network shunts to ground 500-kc noise from the vfo to keep it out of the 500-kc i-f amplifier channel. Capacitor C184 reduces the higher order harmonics from the variable frequency oscillator. The oscillator signal is applied to the injection grid at pin 1 and the variable i-f signal is applied at the control grid (pin 7) for mixing. The i-f output at the plate (pin 5) of the second mixer, V106, represents the input frequencies, their sums, and their differences. The desired 500-kc signal voltage is developed across the primary of transformer T101. Resistor R123 is the injection grid resistor. Resistor R127 and capacitor C183 are the cathode bias resistor and bypass capacitor, respectively. Capacitor C185, in conjunction with resistor R128, forms the screen (pin 6) decoupler. Resistor R128 is the voltage-dropping resistor for the screen grid. Resistor R129 and capacitor C186 decouple the plate circuit. The plate supply voltage is applied through resistor R129 and the primary of T101. The output signal voltage from the plate is conducted through a shielded cable to the primary of transformer T101 (where the plate circuit is tuned) and coupled to the i-f crystal filter stage.

### 43. High-frequency Crystal Oscillator

The h-f oscillator, V105, type 6AK5, is a modified Pierce oscillator using 10 frequency-controlling crystals, each so selected that when its fundamental or harmonic signal is beat with the signal voltage in the first mixer, V102, it will produce in the mixer a usable output frequency between 2.5 and 1.5 mc or 3.5 and 2.5 mc on all tuning steps except steps 1, 2, and 3. On tuning step 1, the h-f oscillator produces a 12-mc signal for introduction to the first mixer, V102, and an 8-mc signal for introduction to the intermediate mixer, V103 (figs. 11 and 12). The h-f oscillator, V105, is not used in tuning steps 2 and 3, the signal on these steps being fed directly from the r-f amplifier to the second mixer, V106, through the variable i-f coils.

a. Tuning Step 1. Four-mc crystal Y110 is placed across the grid (pin 1) and the cathode (pin 7) of V105. With the operating voltage applied, oscillations are maintained by the inphase feedback voltage being produced across r-f choke L120 in the oscillator tube cathode circuit. Capacitors C165 and C166 form the oscillator feedback network. Capacitor C167 trims the total crystal circuit to 32 uuf for proper operation and frequency. Resistor R115 is the oscillator grid resistor. Oscillator tube screen voltage is obtained through voltagedropping resistor R114, and the screen grid is held at r-f ground potential by capacitor C164. Resistor R117 is the plate voltage-dropping resistor for V105. Inductor L121 is split-tuned to provide second and third harmonic voltages of the crystal fundamental for application to intermediate mixer V103 and first mixer V102, respectively, in the following manner: The plate current flow of V105 through inductor L121 (upper half of coil) contains the fundamental and its harmonics. The tap on inductor L121 is held at r-f ground potential by capacitor C163, but the plate current flow through the upper half of the coil induces in the lower portion of the coil the fundamental and all of its harmonics. The top portion of inductor L121, fixed trimmer C161, and alinement trimmer C162 form a parallel-resonant circuit tuned to the third harmonic (12 mc) of crystal Y110. The developed oscillator voltage is coupled to first mixer V102 by capacitor C136. The lower portion of inductor L121, fixed trimmer C145, and alinement trimmer C144 form a parallel-resonant circuit tuned to the second harmonic (8 mc) of crystal Y110. The oscillator voltage developed is applied to intermediate mixer V103 through capacitor C143.

b. Tuning Steps 4 through 12. On tuning steps 4 through 12, wafer switch S108 back contacts (fig. 42) provide the B+ voltage to V105 through plate load resistor R116. The h-f oscillator plate circuit is not tuned and the fundamental of the crystal frequency is taken from the plate for injection into first mixer V102. On these tuning steps, inductor L121 is not in

the oscillator plate circuit. (See paragraph 4c for a listing of crystal frequencies used, and the injection frequencies for tuning steps 4 through 12.)

c. Tuning Steps 13 through 30. On tuning steps 13 through 30, the basic circuit arrangement of crystal oscillator V105 remains the same (fig. 20), but only the upper half of inductor L121 is tuned to secure the desired harmonic voltage for application to first mixer V102 (fig. 42). Capacitors C146 through C162 are switched by S108 across the upper half of L121 to form resonant circuits at the desired harmonic frequencies.




Figure 20. Crystal oscillator, tuning step 1 only, schematic diagram.

### 44. Variable-frequency Oscillator

The vfo unit is composed of an oscillator and a buffer amplifier, electrically isolated and shielded from the rest of the receiver by a hermetically sealed metal case. The vfo tunes over the 2- to 3-mc frequency spectrum. The purpose of the buffer amplifier is to isolate the oscillator from varying load changes, amplify the oscillator voltage, and provide to the oscillator an in-phase

feedback voltage to sustain oscillations. A voltage regulator tube V116 type 0A2 is shunted across the B+ line to the oscillator plate to eliminate frequency drift due to plate voltage variations.

a. OSCILLATOR V001. Oscillator tube V001 is a type 6BA6, arranged in a circuit similar to a Hartley but different in that the in-phase feedback voltage is obtained from the amplifier

tube V002 screen circuit through capacitor C008. The oscillator tank circuit consists of trimmer inductor L002, permeability - tuned inductor L001, and tank capacitor C001 in parallel with temperature-compensating capacitors C002 and C003. The value of C002 will differ from receiver to receiver, the correct value being selected for a particular oscillator by factory test. The oscillator is tuned by movement of the iron core within the inductor L001 form. The powdered iron core, or slug, traverses a lead screw which is rotated by the receiver tuning control. Inductor L001 is tapped near the ground end and is connected through capacitor C008 to the screen of V002, resulting in some of the amplified oscillator voltage being fed back to the inductor (L001) to sustain oscillations. C004 and R001 are the grid capacitor and resistor, respectively. The oscillator tube is triode-connected and obtains its plate voltage through plate load resistors R002 and R003. The value of resistor R002 determines the amount of r-f voltage coupled to amplifier tube V002. The r-f voltage drop across resistor R002 is coupled to the control grid of V002 through capacitor C007 and through capacitor C005 to the ground or cathode of V002.

b. Buffer Amplifier V002. The buffer amplifier isolates the oscillator from the load (V106) and provides a small feedback voltage to sustain oscillations in the oscillator grid tank. Tube V002, type 6BA6, is pentode-connected, and obtains its drive from the oscillator voltage developed across grid resistor R005. The amplifier r-f output voltage is developed across plate load resistor R006 and coupled to second mixer V106 (pin 1) through capacitor C009 and a length of coaxial cable. The screen grid (pin 6) of V002 is supplied with the correct potential through voltage-dropping resistor R007. Both the oscillator V001 and buffer amplifier V002 plate circuits are decoupled from the power supply by resistor R004 and capacitor C006.

c. Voltage Regulation. Both the oscillator and buffer amplifier tubes secure their plate and screen voltage from a regulated source. The plate supply end of resistor R004 is connected to voltage regulator tube V116, type 0A2, anode (pins 5 and 1). The regulator tube is seriesconnected with current-limiting resistor R181

across terminal 2 of power supply filter choke L122 and ground.

### 45. Crystal Filter

A 500-kc crystal, Y112, is used in a highly selective crystal filter i-f circuit (fig. 22) to enable the separation of the wanted signal from the interfering signals. A phasing capacitor, C188, is provided to shift the crystal rejection slot (parallel resonant frequency) so that unwanted signals can be eliminated. The SE-LECTIVITY control, by selection of resistors, varies the series resistance of the crystal circuit, thereby changing crystal Q and bandpass.

a. The secondary winding of transformer T101, crystal Y112, and phasing capacitor C188 form a bridge. Capacitor C187 (10 uuf) is shunted across crystal Y112 to bring the crystal holder capacitance up to the design factor chosen by the manufacturers of this receiver. When phasing capacitor C188 is adjusted to equal the total shunt capacitance presented by the Y112 crystal holder and C187, the following circuit conditions exist: An incoming 500-kc signal develops equal and opposite signal voltages across the halves of the secondary winding of T101. The reactive drop across C188 is equal to and opposite to the voltage developed across the crystal holder capacitance. Since the crystal is at series resonance at 500 kc, its impedance is low and the voltage generated across the upper half of T101 is applied through the low impedance (Y112) and across transformer T102. The impedance of Y112 rises sharply for frequencies off resonance, resulting in attenuation of a 500-kc carrier's extreme sidebands and adjacent signal frequencies.

b. A variable control of the i-f bandpass is obtained by the insertion of resistors in series with the crystal circuit. The SELECTIVITY control provides a choice of  $5^{\circ}$  of selectivity or bandpass. In position 0, the crystal is shorted out and the selectivity is determined by the Q of the L/C receiver circuits alone. In position 1, the selectivity of the circuit is lowest because of the series insertion of the high impedance represented by a parallel-resonant circuit consisting of T102 and its trimmer. In positions 2,




Figure 21. Vfo, shield cover removed.

3, and 4, resistors R130, R131, and R132, respectively, are switched in series with Y112 to r-f ground. Resistor R132, being the lowest in value, allows development of highest Q of Y112 and narrowest bandpass.

c. Capacitor C188 not only neutralizes the voltages passed by the crystal holder, but serves to shift the rejection slot of the crystal filter circuit. The crystal holder and crystal act as a parallel resonant circuit at frequencies slightly higher than the series resonant frequency, and

PHASING capacitor C188 can be used to change the effective capacitance of the crystal circuit.

### 46. Intermediate-amplifier Stages

There are three i-f stages in Receiver R-388/URR: V107, V108, and V109. Each stage uses a 6BA6 miniature pentode. Tuning between stages is done with permeability-tuned transformers T102, T103, T104, and T105. The purpose of the i-f stages is to amplify and provide selectivity for the 500-kc intermediate frequency




Figure 22. Crystal filter, schematic diagram.

before the audio note is separated in the succeeding detector stage. An incoming signal is coupled to the first i-f section by permeabilitytuned inductor T102. The signal developed across T102 is applied to the control grid (pin 1) of V107, through a grounded shield. The grid voltage is developed across resistor R125. Resistor R133, in conjunction with capacitor C189, forms the grid a-v-c decoupling unit. Operating voltage for the screen (pin 6) is taken from the voltage divider consisting of resistors R126 and R134. Capacitor C190 is the screen bypass. The plate supply voltage is fed from the OFF-STANDBY-ON switch S113 through load resistor R135, which, in conjunction with capacitor C191, also serves to prevent interstage coupling. The output from the first mixer plate (pin 5) is coupled to the second mixer by permeability-tuned transformer T103, and applied to the control grid (pin 1) of the second i-f tube V108. Resistor R136 and capacitor C193, form the grid a-v-c decoupling. (Fixed bias in the form of an a-v-c- voltage is applied to the grids of all the i-f tubes, when this circuit is placed in operation by switch S115.) R137 is the voltage-dropping resistor for the screen. Capacitor C194 is the screen bypass

to ground. The plate supply voltage is fed through load resistor R138 and coil L104 to the plate (pin 5). Resistor R138 and capacitor C195 form the plate decoupling circuit. The amplified signal from the plate is coupled to the third i-f stage through permeability-tuned transformer T104. Capacitor C196 is shunted across the primary and secondary of the transformer to increase the transformer coupling and to give the proper bandwidth. A center tap on the transformer secondary feeds the signal voltage to the grid (pin 1) of the third i-f stage, V109. Fixed bias voltage and an a-v-c voltage is applied to the grid through resistor R139. This resistor, with capacitor C197, also forms the decoupling network for the grid circuit. Capacitor C198A is the cathode bypass. The plate supply voltage is applied through decoupling resistor R142 and the primary of transformer T105 to pin 5. Resistor R141 drops the screen voltage. Capacitor C199 is the screen bypass to ground. Resistor R142 and capacitor C200 provide the plate decoupling. The output of V109 is coupled to the detector by transformer T105. Capacitor C201, shunted across the transformer primary and secondary, increases the coupling and gives the proper bandwidth.




Figure 23. I-f stages, schematic diagram.

#### 47. Detector

The detector tube, V110A, is a triode with grid and plate tied together for diode operation (fig. 24). The i-f signal voltage across winding 6-3 of T105 is applied across the diode plate and cathode. Rectification occurs on the positive half cycle and the rectified current flows through T105 secondary, terminals 6 to 3, and through the diode load resistors R150 and R151 to ground

and return to cathode. Capacitor C202 is the i-f filter capacitor. That portion of the developed a-f voltage appearing across R151 is applied to limiter V112A and the following a-f stage. I-f signal voltage for the a-v-c circuit is taken from the detector plate and applied through capacitor C204 to the a-v-c tube V110B cathode (fig. 25). The i-f output tube secures its i-f signal from coupling to the detector diode plate through C226.




Figure 24. Detector and i-f output stage, schematic diagram.

### 48. I-f Output

The i-f output tube, V111B, type 12AU7, functions as a cathode follower to provide a low impedance i-f output at coaxial connector J104. The i-f signal is applied to the follower grid from a voltage divider consisting of resistors R177 and R178 which are in series with capacitor C226 between the detector tube plate and ground. Only that portion of the entire drop appearing across R178 of the divider is utilized for follower grid voltage. Tube V111B is operated Class A, bias being secured from the drop across cathode resistor R179. Resistor R180 is the plate voltage-dropping resistor. Capacitor

C227 places the follower plate at signal ground potential. The i-f signal voltage across resistor R179 is coupled to the IF OUTPUT jack through capacitor C228. The i-f output tube signal frequency is 500 kc and any converter unit to which this output is coupled must be capable of amplifying and rectifying this signal for operation of teletypewriters.

### 49. Avc and A-v-c Amplifier

The receiver a-v-c system which feeds a low impedance line, effectively eliminates blocking on strong input signals and maintains steady output signals over a wide range of input signal variations. A-v-c tube V110B produces the control voltage for triode a-v-c amplifier V111A grid.

- a. AVC V110B. The i-f signal voltage is coupled to a-v-c tube V110B through capacitor C204 and across resistor R145 (fig. 25). A-v-c tube V110B is a triode which is diode connected. The application of i-f signal voltage between cathode and plate produces a rectified a-f current flow through R145. The a-f voltage is filtered before application to the a-v-c amplifier tube by resistor R144 and C205B. The time constant of R144 and C205B is approximately .06 second. The a-v-c voltage does not have instantaneous effect on input signals because the a-v-c amplifier V111A has a d-c bias of approximately —9 volts on its grid, which makes this a delayed a-v-c system.
- b. A-v-c Amplifier V111A. The a-v-c circuit works only when the AVC switch S115 is in the ON position. Switch S115 completes tube V111A plate circuit. The complete grid circuit of tube V111A, grid to cathode, consists of series-connected R171, R144, R145, R164, and cathode resistor R168. Resistor R164 is part of the power supply voltage divider and fixes the operating bias of V111A (—9 volts). The plate voltage for tube V111A is secured from another divider consisting of resistors R147, R148, and R149. The plate (pin 1) of tube V111A is connected through plate load resistor R146 to a tap between R147 and R148. Potential at this point is more positive than the cathode divider tap. resulting in application of a positive voltage to tube V111A plate. When the rectified and filtered carrier (a-v-c voltage) across capacitor C205B exceeds the grid d-c bias (—9 volts), the a-v-c amplifier tube conducts. The plate current flow through resistor R146 produces an a-v-c voltage in proportion to the strength of the input signal. The a-v-c line is connected to the negative side of resistor R146. Degenerative feedback is employed, using resistor R167 and capacitor C208 connected between plate and ground to prevent the a-v-c amplifier tube, V111A, from responding to low audio frequencies.
- c. Manual Gain Control. When the AVC switch, S115, is in the OFF position, the a-v-c

amplifier plate circuit is open, resistor R146 is shorted by the switch, and a manually controllable bias is applied to the low impedance a-v-c line. The a-v-c line is connected between resistors R146 and RF GAIN resistor R148, which with resistor R149 are series-connected as a voltage divider from the power transformer T108 high-voltage winding center tap to ground. The RF GAIN control provides manual control of receiver gain. Tubes controlled by the a-v-c and manual voltage are V101, V107, V108, and V109.

### 50. Noise Limiter and A-f Amplifier

- a. Noise Limiter V112A. Signal input for the noise limiter tube, V112A, type 12AX7, is taken from the detector load resistor consisting of R150 and R151. The drop across resistor R151 furnishes the required a-f voltage. The noise limiter tube acts as a series conductor of the audio voltage between detector and a-f amplifier during non-noise periods. When the noise peaks occur, the limiter tube does not conduct and the a-f voltage does not reach the a-f amplifier.
- (1) Resistor R152 and capacitor C205C are series-connected from the negative side of R150 to ground. Resistor R153 is connected from the junction of R152 and C205C to the cathode of noise limiter tubes V112A. The time constant of R152 and C205C is such that all a-f is filtered and a steady negative bais applied to the cathode of V112A. The values of R152 and C205C are sufficient so that variations in a-f appearing across R150 and R151 do not affect the negative bias on the cathode of V112A. The cathode is kept at the potential of the negative end of R150.
- (2) The plate of the limiter tube is connected to the junction of resistors R150 and R151. The potential at this point, and consequently the limiter plate potential, is more positive than the limiter cathode potential, and the tube conducts at the frequency at which the a-f voltage drop across R151 varies.
- (3) On noise peaks, the voltage drop across R151 hits a simultaneous peak, which results in a large negative potential being applied to the limiter plate. Since R152 and C205C have




Figure 25. Avc and a-v-c amplifier stages, schematic diagram.

a relatively large time constant (.047 second) a slow change in potential occurs at the limiter cathode. This condition allows the limiter plate to attain a more negative potential than the cathode and the limiter tube ceases to conduct. As soon as the noise peaks diminish, the limiter tube conducts, and the audio is transferred to the a-f amplifier through C209 and across AUDIO GAIN resistor R154.

b. A-F Voltage Amplifier V112B. A-f voltage amplifier V112B, type 12AX7, is operated Class A and has cathode degeneration and controllable a-f gain. The a-f signal from the limiter stage is coupled to the amplifier through capacitor C209 and applied across the AUDIO GAIN resistor R154. The required amount of

a-f drive is taken from R154, between slider arm and ground, and applied to the grid of V112B. Cathode bias voltage is developed across cathode resistor R155. The output a-f voltage is developed across plate load resistor R156 and coupled to the a-f power amplifier through capacitor C211.

c. A-F POWER AMPLIFIER V113. The a-f power amplifier V113 uses a tube type 6AQ5. The output of the a-f voltage amplifier, V112B, is applied across the grid resistor R157 of V113. The d-c grid bias is developed across resistor R166, a part of the power supply voltage divider consisting of resistors R164, R165, and R166 (fig. 25), and applied to V113 grid through resistor R157. Tube V113 output is developed

across the primary of output transformer T107, induced in the tapped secondary winding, and applied from the appropriate portion of the secondary to either the PHONES or SPEAKER jack. Located at the rear of the receiver is a terminal strip labeled G, 4, and 600, to which external audio reproducing units can be connected. The SPEAKER and PHONES jacks are connected across the 600-ohm winding of the

transformer. Screen voltage for V113 is obtained by connection to terminal 2 of filter choke L123. Plate voltage for V113 is obtained by connecting the plate return side of the primary winding of T107 to terminal 2 of filter choke L122. Capacitor C212 connected between plate of V113 and terminal 2 of transformer T107 discriminates against the higher audio frequencies to equalize audio output.




Figure 26. Limiter and audio amplifier stages, schematic diagram.

### 51. Beat-frequency Oscillator

The beat-frequency oscillator uses a type 6BA6 pentode tube, V114, in a Hartley circuit. The oscillator inductor, tuning capacitors, grid capacitor, and grid resistor are all contained in transformer T106 shield can. Connections from the packaged elements to their external circuit are made from terminals 1, 5, and 2 of T106 (fig. 27).

a. The grid, cathode, and screen elements of tube V114 serve as a triode oscillator and output is taken from the plate through its coupling in the electron stream. The tank inductance in T106 is tapped and connected to V114 cathode for feedback path, screen to cathode. The BFO PITCH capacitor is in the T106 can and has an extension shaft to the front panel for control of beat frequency. The bfo output is fed to the detector V110A plate through capacitor C206.

b. The screen voltage for V114 is obtained through voltage-dropping resistor R160. The bfo tube plate load resistor is R161, and both R160 and R161 have their common plate return sides decoupled from the rest of the receiver by capacitor C210 and resistor R162. The BFO switch, S112, controls the screen voltage applied to V114 and consequently the operation of the bfo stage. When BFO switch S112 is in the OFF position, the screen element is grounded through the switch contacts and screen voltage is removed from the tube. Capacitor C218 is the screen r-f bypass.

### 52. Calibration Oscillator

The receiver has a 100-kc calibration oscillator which has usable harmonic output voltages up to 30.5 mc. The output of the oscillator can be applied to r-f amplifier V101 grid to provide




Figure 27. Beat-frequency oscillator, schematic diagram.

checkpoints at every 100 kc throughout the tuning range of the receiver for calibration purposes.

- a. Tube V104 type 6BA6 is arranged in a Pierce circuit and uses a 100-kc crystal in place of the conventional tank circuit of coil and capacitor. Tube V104 is a pentode and the control grid, screen, and cathode are used as a triode oscillator. The oscillator output is coupled through the electron stream to the plate and thence through coupling capacitor C173, a shielded lead, and another coupling capacitor C111 to the control grid (pin 1) of the r-f amplifier, V101 (fig. 42).
- b. Crystal Y111 is connected between V104 control and screen grids to serve as the tank circuit of the Pierce oscillator (a version of the ultra-audion oscillator). The feedback voltage to sustain oscillations is developed across C169, which with capacitor C224 forms a voltage-dividing network effectively providing an elec-

trical ground or tap for the tank circuit. Capacitor C224 is a variable panel control (CAL.) and is used to adjust the oscillator frequency to exactly 100 kc by zero beating the harmonic voltage output against a source of standard frequency transmissions such as are radiated from WWV.

- c. The calibration oscillator component functions are as follows: resistor R118 is the grid resistor, resistor R119 is the cathode bias resistor, and C170 is the cathode bypass capacitor. Screen and plate voltage for V104 are obtained through voltage-dropping resistors R120 and R121, respectively. Capacitor C171 is the screen r-f bypass. The return sides of R120 and R121 have a common decoupling unit consisting of capacitor C172 and resistor R122.
- d. The CALIBRATE switch, S118, completes the cathode circuit for V104. When S118 is at the OFF position, the cathode is open and the oscillator is inoperative.




Figure 28. Calibration oscillator, schematic diagram.

### 53. Power Supply

The receiver power supply (figs. 29 and 42) is a full-wave circuit using a rectifier tube V115, type 5V4. The supply can be operated from a 115-volt, 45- to 70-cycle source and has provisions for 230-volt operation.

a. The power transformer T108 has two primary windings parallel-connected for 110-volt operation, which can be connected in series for 230-volt operation. Fuse F101 protects the T108 primary winding and the OFF-STANDBY-ON switch S113 completes the T108 primary circuit in the STANDBY and ON positions. Switch S113, when in the ON position, also completes the B+ circuits to the i-f amplifier tubes, V107, V108, and V109. Transformer T108 has three secondary windings; the h-v winding 11-10-9 supplies the necessary potential for rectifier tube

V115 plates; the winding 5-6 supplies filament voltage for tube V115; and the winding 7-8 supplies 6.3 volts ac for the receiver tube filaments.

- b. The a-c plate voltage is applied to V115 (pins 4 and 6) and the rectified output is taken from the filament (pin 8). The filter section of the supply consists of input choke L122 followed by a pi-section consisting of choke L123 and filter capacitors C217A and C217B.
- c. Voltage for the vfo unit and the a-f power tube, V115, is taken from the junction of chokes L122 and L123. The vfo unit voltage is regulated by current limiting resistor R181 and voltage regulator tube V116 type 0A2. Voltage for the remaining receiver circuits is taken from the output side of the supply, terminal 2 of choke L123, and supplied through the ON position contact of S113 and relay K101 contacts.




Figure 29. Power supply, schematic diagram.

### 54. Input-Output Meter

A 0- to 1-ma meter mounted at the upper right side of the receiver panel functions as a tuning meter and an output meter. The meter is calibrated in 20-, 40-, 60-, 70-, and 100-db input signal levels and —10 to +6 db audio output level (6 mw reference). INPUT-OUTPUT METER switch S117, a momentary spring return toggle switch, is provided to change the meter connections.

a. Input Meter. When the INPUT-OUT-PUT METER switch S117 is in its normal position (INPUT), the meter circuit is arranged as an S meter, as shown in figure 23. The i-f amplifier tube V107 and V108 screen voltage dividers have their return through resistor R170. Resistor R170, meter M101, and resistor R163 are series-connected across i-f amplifier tube V109 cathode bias resistor R140. R140 is variable and is used as a METER ZERO resistor. With no signal input to the receiver, the voltage drops across R163 and R170 are equal and opposite in potential and no current flows through the meter. When the input signal increases, the a-v-c voltage fed back to the grid circuit of V107 and V108 increases with a resultant decrease in screen current of these tubes. The voltage drop across R170 in the return side of V107 and V108 screen voltage dividers increases, a voltage unbalance occurs across R170, M101, and R163, and current proportional to the signal strength flows through the meter.

b. OUTPUT METER. When the INPUT-OUT-PUT METER switch, S117, is in the OUTPUT position, meter M101 measures the audio output level of the receiver (fig. 26). Voltage-dropping resistor R173 and rectifier unit CR101 are in series across the 600-ohm output transformer T107 secondary winding. The rectified output level is indicated by M101 connected across CR101.

### 55. Bandswitching

The bandswitching is done by rotary switches 1 to 11. These are ganged, wafer type switches that respond to the BANDCHANGE knob by a system of gear trains. The gear trains are so arranged that the correct switch combinations are selected to cut in the appropriate tuning components. The following chart illustrates the functions of each switch for rough tuning on each band. For further information concerning the mechanical aspects of tuning, refer to chapter 4, section II, and figures 30 and 31.

# TABLE II SWITCHES

S111	Variable i-f selector two-position.	L118	L118	L118 L119	L118	L118	L119	L118	L118
S110	Variable i-f selector two-position.	L116 L117	L116	L116 L117	L116	L116	L117 L116	L116	L116
8109	Rotor attached to grid (pin 1) of V105. Connects with crystals listed.	4 mc			6 mc	8 mc	8 mc	10 mc	10 mc
	harmonic funing on various bands.	B R117	R116	R116	R116	R116	R116	R116	R116
8108	S108 has two contact waters and rotors, A and B. S108 rotor is attached to the plate (pin 5) of V105 and cuts in appropriate load resistor with B+. S108 chooses coil and capacitor combination for	A C161, C162 2d harmonic tuning C144, C145 3d harmonic tuning	L121						
S107	Rotor attached to SIIO. Connects with —	V103 thru L124	S104	S104	8106	8106	S106	LS106	8106
S106	Rotor attached to plate (pin 5) of V102. Connects with —	L114 L115	:		S107	S107	S107	L107	S107
S105	Rotor attached to grid (pin 1) of — V102. Connects with —	L110			L111	L111	L111	L111	L112
S104	Rotor attached to plate 5 (pin 5) of V101. Connects with —	B-line	2107	S107	L107	L107	L107	L107	L108
S103	Rotor attached to grid (pin 1) of V101. Connects with —	L101	L102	L103	L104	L104	L104	L104	L105
S102	Rotor attached to antenna matching capacitor C230. Connects with —	C230	C234	C235	C236	C236	C236	C236	C231
S101	Rotor attached to antenna input. Connects with —	C233	C234	C235	C236	C236	C236	C236	C237
ncy		1.5	2.5	3.5	4.5	5.5	6.5	7.5	8.5
Frequency		ë.	1.5 to	2.5 to	3.5 to	4.5 to	5.5 to	6.5 to	7.5 to
Band		-	27	ಣ	4	5	9	2	∞

# TABLE II (contd)

# SWITCHES

S111		L118 L119	L118	L118	L119	L118	L118	L119	118	) !		L118	L119		L118			L118	L119		L118			L118	L119	1	L118	
S110		L116 L117	L116	L116	L117	L116	L116	L117	1,116	)     		L116	L117		L116			L116	L117		L116			L116	L117	1	L116	
8109		12 mc	12 mc	14 mc		14 mc	8 mc		8 m			9 mc			9 mc			10 mc			10 mc			11 mc		1	11 mc	
	В	R116	R116	R116	-	R116	R117		R117	1		R117			R117		_	R117			R117			R117		1	K117	
8108	A						C157, C158	2d harmonic	tuning C157 C158	2d harmonic	tuning	C155, C156	2d harmonic	tuning	C155, C156	2d harmonic	tuning	C153, C154	2d harmonic	tuning	C153, C154	2d harmonic	tuning	C152	2d harmonic	tuning	C152 2d barmonia	tuning
S107		S106	8106	8106		8106	8106		2106	2		8106			8106			8106			8106			S106			2106	
S106		S107	S107	S107		S107	S107		2107	• • • •		S107			S107			S107			S107			2107		1	2107	
S105		L112	L112	L112		L112	L112		1,119			L112			L113			L113			L113		1	L113		7	L113	
8104		L108	L108	L108		L108	L108		1.108			L108			L109			L109			L109		1	L109		7	L109	
S103		L105	L105	L105		L105	L105		1.105			L105			$\Gamma 106$			$\Gamma 106$			$\Gamma106$			$\Gamma106$		1	L106	
S102		C231	C231	C231		C231	C231		(7931			C231			C232			C232			C232			C232		0	C232	
S101		C237	C237	C237		C237	C237		(937			C237			C238			C238			C238			C238		0	C238	
Frequency		8.5 to 9.5	9.5  to  10.5	10.5  to  11.5		11.5 to 12.5	12.5 to 13.5		13.5 to 14.5			14.5 to 15.5			15.5 to 16.5			16.5 to 17.5			17.5 to 18.5		1	18.5 to 19.5	, .	1	19.5 to 20.5	
Band		6	10	11		12	13		14	1		15			16	•		17			18		(	Ig		6	02 02	

# TABLE II (contd)

# **SWITCHES**

S1111	L118 L119	L118	L118	118	L118	L118	L118	L118	L118 L119	L118
S110	L116 L117	L116	L116	L116	L116 L117	L116	L116 L117	L116	L116 L117	L116
8109	12 mc	12 mc	13 mc	13 mc	14 mc	14 mc	10 mc	10 mc	10.6mc	10.6me
	B R117	R117	R117	R117	R117	R117	R117	R117	R117	R117
8108	A C150 2d harmonic	tuning C <b>150</b> 2d harmonic	tuning C149-C151	C149-C151 2d harmonic	tuning C148 2d harmonic	tuning C148 2d harmonic	tuning C147 3d harmonic	tuning C147 3d harmonic	tuning C146 3d harmonic	tuning C146 3d harmonic tuning
S107	S106	S106	S106	8106	8106	S106	8106	S106	S106	S106
8106	S107	S107	S107	S107	S107	S107	S107	S107	S107	S107
S105	L113	L113	L113	L113	L113	L113	L113	L113	L113	L113
S104	L109	L109	L109	L109	L109	L109	L109	L109	L109	L109
S103	L106	L106	L106	L106	L106	L106	L106	L106	L106	L106
S102	C232	C232	C232	C232	C230	C230	C230	C230	C230	C230
S101	C238	C238	C238	C238	C238	C238	C2382	C238	C238	C2382
Frequency	20.5 to 21.5	21.5 to 22.5	22.5 to 23.5	23.5 to 24.5	24.5 to 25.5	25.5 to 26.5	26.5 to 27.5	27.5 to 28.5	28.5 to 29.5	29.5 to 30.5
Band	21	22	23	24	25	56	27	28	59	30

## Section II. MECHANICAL FUNCTIONING OF RECEIVER

### 56. General Description

The receiver is tuned by the movement of powdered iron cores (permeability tuning) in the r-f, variable i-f, and vfo coils. Movement of the cores is controlled by cams (except for vfo coils) which are turned through gearing by the KILOCYCLES and MEGACYCLES dial knob on the front panel. Band changing is accomplished by turning the r-f, i-f, and crystal switches through gearing from the BAND CHANGE knob. In addition, the BAND CHANGE knob moves the cores in the r-f coils through successive 1-mc increments (using the same cams as are used for tuning). Details of the functioning of these mechanisms, and the means of frequency indications are given in the following paragraphs of this section (figs. 30 and 42).

### 57. Tuning Mechanisms

The i-f and r-f racks are positioned by their cams through the gearing of shafts A, B, C, D, and E, from the KILOCYCLES dial knob. Shaft A is turned directly by the knob and is limited to 10 revolutions by the 10-turn stop mounted on the shaft. Each revolution corresponds to 100 kc. Shaft A also turns a lead screw in the vfo which positions the core of coil L001 (fig. 42). Shaft B makes only 1/10 of a turn for each turn of shaft A, and thus can make only one complete revolution because A is limited to 10 turns.

- a. I-F RACK. Shaft E is geared to shaft B through the 74-tooth gear and the detent gear, both of which act as idlers. Shaft E makes almost a full turn, and thus lifts the i-f rack from the lowest to the highest position during the complete turn of shaft B.
- b. R-F RACKS. Shaft D is geared to shaft B through shaft C, and the 16- and 41-tooth gears (fig. 30). The gearing ratio (48 to 48) is such that shaft C turns exactly as much as shaft B. The 41-tooth gear serves as an idler gear to transmit motion and change the direction of

motion. Shaft D makes 4/35 of a turn for the complete turn of shaft B. Since only a half-turn of the heart-shaped cams is required to lift the r-f racks from their lowest to their highest positions, and since somewhat less than the full travel is used, this 4/35 of a turn corresponds to exactly 1/4 of the full movement for the 4to 7-mc rack. That is, it corresponds to a 1-mc movement. The cam for the 8- to 15-mc rack turns only half as far as the first cam and, therefore, lifts the 8- to 15-mc rack only 1/8 of the full rack movement, or also 1 mc, for the same full turn of shaft C. Similarly, the cam for the 16- to 30-mc rack turns only half as far as the cam for the 8- to 15-mc rack and therefore lifts the 16- to 30-mc rack only 1/16 of the full rack movement, or 1 mc, for a full turn of shaft C. Thus, regardless of which set of coils may be connected in the circuit, that is, whatever tuning step the receiver is set to, the turning of shaft C one full turn always corresponds to an r-f rack movement proportional to 1 mc. Turns less than a full turn are also in exact proportion.

### 58. Band Change Mechanisms

a. R-F RACKS. The cams for the r-f racks are turned for band changing purposes by means of shaft D, shaft C, and the two sets of sun and planet gears which are used for tuning. However, shaft B does not turn; instead, the planet gears are caused to walk around the sun gears by turning the spider gear in which the shaft of the planet gears is mounted. The spider gear is turned, through an idler, by the 85-tooth gear on the shaft of the BAND CHANGE knob. Every half-turn of the BAND CHANGE knob causes the spider gear to turn one half revolution. This makes the planet gears walk halfway around their respective sun gears. As both planet gears are fixed to the same shaft, and as the 50-tooth sun gear does not turn when the KILOCYCLES dial knob is stationary, the 30-tooth sun gear is thereby caused to rotate exactly one full turn for each half turn of the spider gear. Shaft C is thus rotated one full turn (the same as if shaft B had been turned a full turn) and the cams for the r-f racks are moved precisely the right amount for 1 mc.




Figure 30. Functional diagram of tuning, band changing and frequency indicating mechanisms.

To summarize, shaft C can be turned by *either* the BAND CHANGE knob and the spider gear or by the KILOCYCLES dial knob and shaft B.


- b. DETENT. In order to insure that the BAND CHANGE knob is turned only in half-revolution steps, a ball detent is provided between the 30-tooth sun gear (which makes one full turn per half turn of the knob) and the detent gear. (Note that the detent gear cannot turn when the KILOCYCLES dial knob is stationary.)
- c. I-F RACKS. Note that turning the BAND CHANGE knob does not affect the position of shaft E and variable i-f rack. Shaft E turns only when the detent gear is turned, and the detent gear can be turned only through shaft B and the KILOCYCLES dial knob. Thus band changing does not affect the tuning of the i-f coils.
- d. R-F SWITCHES. R-f switches S101 through S107 are 18-position rotary switches of which only the first 16 positions are used. Of the 16 operative positions, one each is used for bands 1 through 15, while the sixteenth position is used for all 15 remaining bands. The position of the r-f switches is controlled by the BAND CHANGE knob through the 16- and 144-tooth gears, each half-turn of the knob causing a one-position shift of the switches until position 16 is reached. To prevent further turning of the BAND CHANGE knob from moving the switches beyond position 16, an overtravel coupler is interposed between the 144-tooth gear and the switches. The coupler permits the knob and associated gears to be turned beyond band 16, to band 30, and at the same time leaves the switches stationary at position 16. The coupler is driven by the detented ball held between it and the 144-tooth gear. The coupler thus follows the gear to each of the first 15 positions until, at position 16, the pin on the periphery of the coupler is arrested by the stationary stop pin, making only the gear free to move to the higher positions. When returning to the lower bands, the pin on the gear again engages the pin on

the coupler at position 16, so that the gear can drive the coupler and switches to the lower band positions.

- e. CRYSTAL SWITCHES. The crystal switches S108 and S109 are 18-position switches, of which only the first 16 positions are used, and are so operated that each position is used for two bands. The switches are turned by the BAND CHANGE knob through the Geneva wheel and shafts H and I. The Geneva wheel makes 1/6 of a turn each time it is engaged by the drive pin on the 85-tooth gear attached to the shaft of the BAND CHANGE knob. Since this occurs only once each full turn of the knob, and since each half-turn of the knob equals a 1-mc band change, the switches are turned one position only once every two bands.
- f. I-F SWITCHES. The i-f switches S110 and S111 are rotary switches, having two positions, with every other position electrically the same. These switches are turned one position for each half-turn of the BAND CHANGE knob, by means of shafts G and K.

### 59. Frequency Indication

The tuned frequency of the receiver is shown on two dials which must be read in combination. The KILOCYCLES dial which shows the units and tens figures of the frequency in kilocycles is turned directly by the tuning knob on the end of shaft A. The hundreds and thousands figures of the frequency in kilocycles are located on a slide rule type scale on the MEGACYCLES dial drum and are actually marked in decimal and unit megacycles. The pointer which indicated these figures is moved by a cable and pulley on shaft B which is turned by the main tuning knob. The scales on the MEGACYCLES dial drum extend over a range of 1 mc only and 30 scales are thus needed to cover the full frequency range of the receiver. The proper scale on the drum is turned into viewing position by means of a cord and pulley which are turned by the BAND CHANGE knob, each half-turn of the knob causing another scale to come in view.



CROSS-SECTIONAL VIEW

SHAFT "A"	SHAFT "E"	SHAFT "A"	SHAFT "E"
0	0	2 + 270°	91° 23'
0 +90°	8° '8'	3	99° 42'
0 ÷180°	16° 37'	3 + 90°	108°
0 + 270°	24° 55'	3 + 180°	116° 181
1	33°14'	3 + 270°	124° 37'
1 + 90°	41° 32'	4	132° 55'
1 + 180°	49° 51'	4 + 90°	141° 14'
1 + 270°	58° 9'	4 + 180°	149° 32'
2	66° 28'	4 + 270°	157° 51'
2 + 90°	74° 46'	5	166° 9'
2 + 180°	83° 5'	5 + 90°	174° 28'

SHAFT "A"	SHAFT "E"	SHAFT"A"	SHAFT"E"
5 + 180°	182° 46'	8 + 90°	274° 9'
5 + 270°	191° 5'	8 + 180°	282° 281
6	199° 23'	8 + 270°	290° 461
6 + 90°	207° 42'	9	299° 51
6 + 180°	216°	9 + 90°	307° 23'
6 + 270°	224° 181	9 + 180°	315° 42'
7	232° 37'	9 + 270°	324°
7 + 90°	240° 55'	10	332° 18'
7 + 180°	249° 141	10 + 90°	340° 37'
7 + 270°	257° 32'	10 + 180°	348° 55'
8	265° 51'	10 + 270°	357° 14'

POSITION OF SHAFT "A" GIVEN IN NO. OF TURNS PLUS DEGREES FROM CCW STOP. SHAFT "E" MUST POSITION WITHIN 27' OF ITS SPECIFIED FIGURE FOR EACH INCREMENT OF ROTATION ON SHAFT "A" SETTINGS ON "A" (EXCEPT END POSITIONS) TO BE APPROACHED IN BOTH CW AND CCW DIRECTIONS.

PART NAME

QUAN ITEM TITY NO.

QUAN- TITY		PART NAME
	Α	BACK GEAR PANEL
_	В	REV. GEARS AND SHAFT ASSEMBLY
1	C	WASHER
2	D	WASHER
4	Ε	RETAINING RING I
	F	I.F DRIVER GEAR AND SHAFT ASSY
2	G	WASHER
- 1	Н	GEAR ASSEMBLY - SWITCH I.F.
2	7	WASHER
	K	RETAINING RING
	L	MC KNOB SHAFT
_ !	М	KNOB GEAR AND HUB ASSEMBLY
1	N	GROOVE PIN
	0	SHAFT ASSEMBLY - BAND SWITCH

QUAN TITY	NO.	PART NAME
2	Ρ	BALL
1	Q	SHAFT ASSEMBLY-GENEVA WHEEL
	R	THRUST BEARING
	S	HUB ASSEMBLY - GENEVA WHEEL
1	Т	CENTERING SPRING
2	U	6-32 X I/8 PBH SCREW
1	٧	HUB ASSEMBLY - DETENT GEAR
	W	WASHER
- 1	×	DETENT SPRING ASSEMBLY
	Y	CENTER PLANET-GEAR AND HUB ASSY
	Z	HUB ASSEMBLY - FLOATING
	AA	SHAFT AND GEAR ASSEMBLY
- 1	AB	STOP IDLER GEAR HUB ASSEMBLY
	AC	FRONT GEAR PANEL
- 1	AD	POINTER PULLEY ASSEMBLY

TITY	NO.	· · · · · · · · · · · · · · · · · · ·
_	AE	PULLEY - DRUM
2	AF	POST - LOWER SPACING
2	AG	POST - UPPER SPACING
4	АН	SCREW, 8-32 X 5/16
4	AJ	WASHER, NO. 8 FLAT
4	AK	6-32 X I/4 SCREW
4	AL	WASHER, NO 6 FLAT
4	AM	WASHER, NO 8 SHAKE
6	AN	WASHER, NO 6 SHAKE
6	AO	SET SCREW, 6-40 X 1/8
4	AP	WASHER
_	AQ	GROOVE PIN
2	AR	LOADING CABLE
1	AS	SPRING

NOTE:

DESIGNATION OF PARTS CONFORMS TO MANUFACTURER'S ASSEMBLY DRAWING 505 2189 004.

TM 854-31

Figure 31. Dial and bandswitch gear box.

### CHAPTER 5

### FIELD MAINTENANCE INSTRUCTIONS

*Note*. This chapter contains information for field maintenance. The amount of repair that can be performed by units having field and depot maintenance responsibility is limited only by the tools and test equipment available, and by the skill of the repairman.

## Section I. TROUBLE SHOOTING AT FIELD MAINTENANCE LEVEL

**Warning:** Be extremely careful when servicing the receiver; dangerous high voltages are present. When checking voltages, use probes that are completely insulated except for the tip. Observe polarities to protect the meter. Take no continuity readings unless the receiver power is removed. Discharge capacitors before checking.

### 60. Trouble-shooting Procedures

- a. The first step in servicing a set is to attempt to sectionalize the fault. Sectionalizing means tracing the fault to the major component, circuit, or stage in the receiver responsible for abnormal operation of the set. The second step is to localize the fault. Localization means tracing the fault to the defective part responsible for the abnormal condition. Some troubles such as burned-out resistors, r-f arcing, and shorted transformers can be located by sight, smell, or hearing. The majority of faults must, however, be localized by checking the voltage and resistance.
- b. The tests listed below aid in isolating the source of trouble. To be effective, the procedure should be followed in the order given. Remember that servicing procedure should cause no further damage to the receiver. The service procedure is summarized as follows:
- (1) Visual inspection. The purpose of visual inspection is to locate any visible trouble. This

is best done by using a strong light or a flashlight in areas of shadow. Through this inspection alone the repairman may frequently discover the trouble or determine the stage in which the trouble lies. This inspection is valuable in avoiding additional damage to the receiver that might otherwise occur as a result of improper servicing, and in forestalling future failures.

- (2) Input resistance measurements. These measurements prevent further damage to the receiver from possible short circuits. Since this test gives an indication of the condition of the filter circuits, its function can be considered as being more than preventive.
- (3) Operational tests. The operational test is important because it frequently indicates the general location of the trouble. In many instances the information gained will determine the exact nature of the fault. In order to utilize this information fully all symptoms must be interpreted in relation to one another.
- (4) *Trouble shooting chart*. The trouble symptoms listed in this chart aid in localizing trouble.
- (5) Signal substitution. The principal advantage of the signal substitution method is that it usually enables the repairman to localize the trouble accurately and quickly to a given stage when the general location of the trouble is not immediately apparent from other tests.
- (6) Stage gain charts. These charts can be used to localize obscure, hard-to-find troubles and should be referred to only after having exhausted other means.
- (7) Intermittents. In all these tests, the possibility of intermittents should not be overlooked. If present, this type of trouble often may be made to appear by tapping or jarring the set. It is possible that the trouble is not in the receiver itself but in the installation or the trouble may be due to external conditions. In this event check the installation, if possible.

### 61. Trouble-shooting Data

Take advantage of the material supplied in this manual. It will help in the rapid location of faults. Consult the following trouble shooting data:

Figure No.	Description
Fig. 42	Radio Receiver R-388/URR, schematic diagram.
Fig. 32	Tube socket voltage and resistance chart.
Fig. 33	Radio Receiver R-388/URR, top view.
Fig. 34	Radio Receiver R-388/URR, bottom view, compartmented.
Fig. 35	Bottom view of chassis compartment 1, capacitors.
Fig. 37	Bottom view of chassis compartment 2.
Fig. 38	Bottom view of chassis compartment 3.
Fig. 5	Radio Receiver R-388/URR, rear view.
Fig. 36	Bottom view of chassis compartment 1.

### 62. Test Equipment Required for Trouble Shooting

The test equipment required for trouble shooting the Radio Receiver R-388/URR is listed below. The technical manuals associated with the test equipment are also listed.

Test equipment	Publication
Signal Generator AN/ URM-25 (*) (range 10 kc to 50 mc)	Navship 91379
Signal Generator TS- 497(*)/URR (range 2 to 400 mc)	TM 11-5030

Test equipment	Publication
Audio Oscillator TS-382(*)/U	TO 16-35TS382-2
Tube Tester I-177-(*)	TM 11-2627
Frequency Meter Set SCR-211-(*) (range 125 kc to 20 mc)	TM 11-300
Frequency Meter TS-174(*)/U	TM 11-5044
Electronic Multimeter TS-505(*)/U	TM 11-5511
Ballantine VTVM Model No. 300	
Multimeter TS-352(*)/U	USAF Handbook AN-16- 35TS352-3
Output Meter TS-585(*)/U	TM 11-5017

### 63. General Precautions

Careless replacement of parts can cause additional troubles. Observe the following points.

- a. Before a part is unsoldered, note the position of the leads. If a part, such as a transformer, has many taps, tag each lead for correct identification.
- b. Be careful not to damage other leads by pulling or pushing them out of the way.
- c. Do not allow drops of solder to fall into the set as they may cause shorts. If possible, place strip of cardboard beneath part to be soldered to catch drippings. Be sure iron is hot, clean and tinned.
- d. A carelessly soldered connection may create a new fault and is extremely difficult to locate.
- e. When a part is replaced in the r-f or i-f circuits it must be placed exactly as the original one was. A part which has the same electrical value, because of a difference in physical size,

may cause trouble in the higher-frequency circuits, where slight resistance and capacitance changes can cause erratic operation. Give particular attention to proper grounding when replacing a part. Use the same ground as in the original wiring. Burnish or scrape the ground area before attaching wire. Failure to observe these precautions may result in decreased gain or, possibly, in oscillation of the circuit.

### 64. Checking Filaments and B+ Circuits for Shorts

- a. The filaments operate at 6.3 volts ac from a 1-v (low-voltage) winding on the secondary of power transformer T108. A short in the filament circuit would hardly cause damage to the filaments, unless of course, a short circuit occurred across the h-v and l-v windings of transformer T108. Before applying power, check taps on transformer. Visual inspection of the miniatue tubes with the power on should show whether each is lighted. A continuity check of the filament pins of the tube will determine if the tube is at fault, otherwise, check the filament contact at the sockets for shorts.
- b. Before applying power to a set known to be defective, it is advisable to check the B+ line for shorts. Be sure the power is removed before checking for a short. The preferable check is to replace the plug-in filter can. A resistance reading at the terminals of filter choke L122 should read approximately 100 ohms. A resistance reading at the terminals of out-put filter choke L123 should read approximately 300 ohms. If the output filter choke reading is appreciably less than 300 ohms, remove filter

capacitor unit C217 connections and check pins for break-down before replacing filter choke.

c. Refer to tube socket resistance and voltage chart (fig. 32). With power removed, check resistances at pins against reading as outlined. Apply power and check voltages.

### 65. Operational Test

- a. For rapid orientation with the operation of the receiver and for ready reference to the logical and usual sources of trouble, refer to the equipment performance checklist (par. 36).
- b. Use of the receiver meter in either the input and output position with the avc off may be helpful in determining whether the trouble is located before the detector stage or following it.

### 66. Trouble-shooting Chart

The following chart is supplied as an aid in locating trouble in the receiver. This chart lists the symptoms which the repairman observes, either visually or audibly, while making a few simple tests. The chart also indicates how to localize the trouble quickly to the various stages. The signal substitution tests (par. 68) can then be used to supplement this procedure and to determine the defective stage. Once the trouble is localized to a stage or circuit, a tube check and voltage and resistance measurement of this stage or circuit should ordinarily be sufficient to isolate the defective part. Normal voltage and resistance measurements are given in figure 32.






Figure 32. Tube voltage and resistance chart.



TM854-33

Figure 33. Radio Receiver R-388/URR, top view.





COMPARTMENT 3

TM 854-34

Figure 34. Bottom view of chassis, compartmented.




Figure 35. Bottom view of chassis, compartment 1, capacitors.




Figure 36. Bottom view of chassis, compartment 1.




Figure 37. Bottom view of chassis, compartment 2.




Figure 38. Bottom view of chassis, compartment 3.

Symptom	Probable trouble	Correction
1. OFF - STANDBY - ON switch at ON position		Check power source.
Receiver inoperative	, Blown fuse.	Replace fuse. If it blows again, check filter capacitor plug-in unit C217.
	Break in a-c cord, usually at plug end or where cord enters set.	Check cord for continuity, bending cord every few inches while watching ohmmeter for needle deflections.
	Crack in fuse holder or holder leads disconnected.	Check fuseholder and leads. Make repairs.
2. No receiver output wit.  RF GAIN and AUDIO  GAIN set at 10. Signa	Second i-f.	Check tubes V109, V110, V111, V112, and V113.
input indicated by me ter with switch in IN PUT position. No out put from receiver.	- -	Check transformers T104, T105, and T107 for open cir- cuits.
put from receiver.		Check capacitors C211 and C209 by replacing with capacitor of equal value.
		Check resistances R152 and R153.
		Check AUDIO GAIN control R154.
3. Receiver inoperative. Meter does not respond a	· · ·	Replace tube and/or chokes.
receiver is tuned. Dia lamps light.	_ ·	Replace filter capacitor unit.
	Defect exists between antenna terminal and detector stage V110.	Check tubes V101 through V109. Check continuity, primary and secondary, of transformers T105, T104, T103, T102, T101.
		Check continuity of L116, L117, L118, and L119 with the BAND CHANGE switch on the odd and even tuning steps.

Symptom	Probable trouble	Correction
	Trouble may occur in the switching. Try tuning on each band to determine whether the entire set is inoperative, one particular band, or the variable i-f switches S110 and S111.	Refer to mechanical trouble shooting data (par. 67).
	With CALIBRATE and BFO switches ON and the main tuning dial turned through 100 kc, an oscillatory note is heard at the output of the receiver.	Antenna relay K101 defective. Repair or replace.
4. A-m signals received but	Bfo defective.	Replace tube V114.
no c-w apparent at output with BFO switch ON and the set tuned to a c-w station.		Check bfo coupling capacitor C206.
to a c-w station.	·	Check socket resistances and voltages against figure 32. Check T106 unit.
5. With CALIBRATE	Calibration oscillator defec-	Check tube V104.
switch ON, and receiver tuned to WWV, no oscillatory note is heard at output.	tive.	Check capacitor C111 and C173.
		Check switch S118.
		Check voltages and resistances at socket of V104 against figure 32.
		Check plug in crystal Y111.
6. Reception weak. With no signal tuned in, rushing noise is not apparent at output, when	Poor antenna hookup and watching.	Tighten antenna connections. Check for grounds. Adjust ANT. TRIM control.
AUDIO GAIN and RF GAIN controls are rotated through maximum. CRYSTAL FILTER switch at 0 position.	Weak tubes, particularly the rectifier, V115.	Check tubes. If receiver has been operated constantly over a long period, replace entire tube set.

Symptom	Probable trouble	Correction
7. With a station tuned i receiver output is loom. Meter appears slugish.	w. to shorted capacitor in	Check voltages and resistances at sockets against figure 32.
	Receiver not properly alined.	Realine as outlined in chapter 5, section IV.
8. Reception distorted.	Open grid resistor in audio stage V113.	Check voltages and resistances at sockets against figure 32.
	Incorrect grid biases.	Check terminal 10 (h-v winding center tap), on secondary of power transformer T108 for high resistance connection. Repair. Check grid voltages against chart number with AVC control at OFF. RF GAIN control R148 open or shorted.
	Poor output impedance match.	Check secondary taps of transformer T107 and speaker connections.
	Improper operating potentials.	Check tube voltages against chart number.
		Check filter chokes L122 and L123 for shorted turns, and filter capacitor C217 for excessive leakage.
	Leaky screen bypass and plate decoupling capacitors.	Shunt bypass capacitors with good capacitors of equal value.
	1,250 kc heterodyne.	Adjust L124 (par. 94).
		Check grid return resistors in mixers.
	Strong signal with AVC control at OFF.	Reduce RF GAIN control, R148 setting.

Symptom	Probable trouble	Correction
9. Noise and fading signals.	Faulty RF GAIN and AUDIO GAIN controls.	Tune to station. First short AUDIO GAIN, then short RF GAIN control. If signals become stable under either one of these procedures, or noise is produced, a defective control is indicated and should be replaced.
	Swinging antenna.	Reduce sag in antenna. Tighten connections.
10. Hum at output.	Shorted turns in filter chokes L122 and L123.	Check resistance of chokes L122, 100 ohms; L123, 300 ohms.
	Defective filter capacitor unit C217.	Replace plug in unit.
11. Intermittent noise.	Defective tube, resistor, or capacitor.	With an insulated probe, gently tap and slightly move all tubes, resistors, capacitors, and soldered connections to locate loose elements in tubes, or faulty connections.
12. Whistle or howl in receiver.	Defective tube, poor shielding and grounding.	Check tubes. Shunt bypass capacitors with capacitors of equal value to locate open unit.

### 67. Mechanical Trouble-shooting Data

Failure of the receiver to operate properly may often be due to mechanical faults. Some of the more probable mechanical sources of trouble are listed in the following table. See section III for repair instructions.

Symptom	Probable trouble	Correction
1. No detenting of bands takes place when BAND CHANGE knob is turned.	Ball and detent-spring assembly (on shaft C, fig. 30) bent or broken.	Repair or replace detent-spring assembly.
2. BAND CHANGE knob turns only one revolution, and then jams.	Centering spring for Geneva wheel loose, bent, or broken.	Tighten, repair or replace spring.
3. Receiver will not tune on some or all frequencies.	Cam rider for r-f slug rack or i-f slug rack stuck because of broken spring or dirty guide.	Clean and replace parts as required.
4. Turning BAND CHANGE knob causes wrong bands to be tuned in.	Overtravel coupler out of alinement.	Realine band-change mechan- ism.
5. Too much backlash occurs when reversing direction of tuning with KILOCYCLES dial knob.	Broken loading cord between shafts B and E (fig. 31).	Replace loading cord.
6. Band indicator drum does not turn.	Broken drum-drive cord.	Replace cord.
7. Dial pointer does not move.	Broken pointer cord.	Replace cord.

### 68. Signal Substitution Notes

- a. Signal substitution requires a source of audio, i-f, and r-f signals. See paragraph 62 for a listing of suitable test equipment.
- b. In addition, a headset or permanent magnet speaker is necessary.
- c. A tube tester and voltohmmeter are also needed to isolate the defective part after the faulty stage has been indicated by signal substitution.
- d. In the test indicated in the following paragraphs, ground one side of the signal generator to the receiver chassis and connect the other side through a series capacitor (about .05 uf) to the receiver point as directed.
- e. Note the volume and listen for serious distortion from the speaker or headset at various points in the signal substitution procedure. When working back from the output toward the input stages, decrease the output as much as possible. If possible, compare with a receiver known to be in good condition.

- f. Check the wiring and soldering in each stage during the procedure.
- g. Misalinement of one or more stages in the receiver will cause reduced output. Misalinement of the oscillators, except the bfo, may prevent any output.
- h. When trouble is localized to a given stage, first test the tube, then the voltage, and finally the resistance at the tube socket of that stage against figure 32.
- i. Trouble in a circuit or stage may not cause changes in voltages or resistance measurements at the tube sockets. The instructions included in these paragraphs are merely a guide and should suggest other procedures, such as voltage and resistance measurements on individual parts, or any other tests that may be in order.
- j. Remove only one tube at a time when testing. Check the tube, and, if it is not defective, return it to the proper socket before another tube is removed.
- k. At each step, it is assumed that all previous steps were completed satisfactorily. Isolate and repair any troubles located before proceeding further.

### 69. A-f Tests

- a. Apply an audio signal through a .05-uf capacitor to terminal 7 of V113. Listen for a signal at the headset. If no output signal is apparent, check tube V113 and taps of transformer T107. Check contacts at PHONES jack J103.
- b. Apply an audio signal at tap 3 of the secondary of transformer T105. If no signal is audible at the output, check in turn, V112, AUDIO GAIN control R154, capacitor C209, and resistors R150, R152, and R153. Check the socket voltages of V112 and V113.

### 70. Fixed I-f Tests.

For fixed i-f tests, set the controls as follows:

RF GAIN
AUDIO GAINMaximum.
BFOOFF.
AVCOFF.
LIMITEROFF.
CRYSTAL FILTER
SELECTIVITY0.

- a. Apply a 500-kc modulated signal through a .05-uf capacitor to the plate (pin 5) of V109. The signal should be heard in the phones. If the signal is not heard, check the continuity of primary and secondary of transformer T105. Check capacitor C201.
- b. Apply the 500-kc modulated signal to the grid (pin 1) of V109. The output signal should be louder. If not, check the voltage and resistance at the pins to determine cause.
- c. Repeat the procedure as outlined above with V108 and V107. Decrease the signal with each tube.
- d. Apply the modulated 500-kc signal to the plate (pin 5) of V106. If no signal is heard at output, check T101 for continuity.

### 71. Variable I-f Tests

- a. Tune the receiver through its range on the odd- and even-numbered tuning steps. Notice the output.
- b. If it is apparent that the receiver is not functioning properly only on the odd-numbered bands, check inductors L117 and L119 and capacitor C221.
- c. If received signals develop insufficient or no output on the even-numbered bands, check inductors L116 and L118, and capacitor C220.
- d. Check switches S110 and S111 on odd- and even-numbered tuning steps.
- e. Refer to paragraphs 88 and 89, variable i-f alinement.

### 72. R-f Tests

a. The quickest r-f test and over-all check of the receiver can be made by using the calibration oscillator V101. Turn the CALIBRATE switch to ON, the BFO switch to ON, and the RF GAIN and AUDIO GAIN controls at the halfway point (5). Revolve the main tuning knob across the spectrum of one of the lower bands. If a tone is heard at the harmonic frequencies of 100 kc throughout the tuning range, the receiver is operating. Defective r-f coils and capacitors can be detected by repeating this procedure over the 30 tuning steps. Also, faults in the switching can be brought to light.

b. If there is reason to suspect that the calibration oscillator is defective, an r-f modulated signal of known frequency can be applied to the grid (pin 1) of V101. If the set is operating properly, the signal should be audible at the output, and the main tuning control should read the correct frequency. A defective tuning step can be located by applying a modulated r-f signal from an accurately calibrated signal source.

### 73. Stage Gain Chart

The stage gain chart given in this paragraph lists the approximate input voltages required to produce a minimum of 500-mw signal output. Use these charts as standards when trouble shooting, to check the over-all gain of the receiver and the gain of each stage listed below. When the receiver output is low and the tubes are performing in a satisfactory manner (as indicated by a tube checker), localize the defective stage by checking the signal voltage level of the stages against the chart, while using either the signal substitution or signal tracing method of trouble shooting.

a. Set the CALIBRATE, AVC, and BFO controls at OFF, and set the SELECTIVITY knob at 0. Increase the RF GAIN control setting until a reference voltage of 4 volts can be measured across the diode load resistor R151.

b. Allow 15 minutes for the signal generator to warm up. Ground the signal generator to the receiver chassis. Use short, well-shielded leads when applying signals. Feed the generator signals modulated 30 percent at 400 cycles through a 100-uuf capacitor and 50-ohm resistor.

Frequency	Signal generator output applied at	Signal generator output (microvolts)	Stage gain
500 kc	3d i.f. V109, pin 1	53,000	73.5
500 kc	2d i.f. V108, pin 1	1,500	35.5
500 kc	1st i.f. V107, pin 1	27	55.5
2 or 3 mc	2d mixer V106, pin 7	29	.93
11 mc*	intermediate mixer V103, pin 7	22	1.32
1 mc	1st mixer V102, pin 1	3	7.33
40 to 30 mc	1st mixer V102, pin 1	1.2 to 1.5	24 to 19.7
1 mc	r-f amplifier V101, pin 1	.3	10
2 to 30 mc	r-f amplifier V101, pin 1	.8 to 1.6	16 to 29

<sup>\*</sup> Dial tuned to 1 mc.

### Section II. REPAIR

### 74. Replacement of Parts

- a. For the most part, the components of Radio Receiver R-388/URR are readily accessible and are easily replaced if found faulty. The sockets, capacitors, filter chokes, and inductors are securely mounted to the chassis with hexnuts and Phillips head screws. The power transformer is bolted to the chassis. The bolts can be easily removed with socket wrenches, longnose pliers, and/or a Phillips screw driver. The dial knobs are removed with either of the wrenches mounted on the under side of the dust-cover. The crystal filter shield is lifted by removing one Phillips head screw on top of can and a hexnut beside the power transformer, beneath the receiver.
- b. If any of the switch wafers require replacement, carefully mark the wires connected to the wafer with tags or other devices to avoid misconnection when the new switch is installed. Follow this practice whenever replacement requires the disconnection of numerous wires.
- c. The parts that require special attention in their removal are listed in the following paragraphs.

### 75. Removal of Vfo

- a. When trouble occurs in the Vfo unit, it is generally recommended that the entire unit be replaced. To begin this task, remove the V001 and V002 tube shields, then remove the tubes.
- b. With the fluted socket type wrenches, remove the dial knobs listed below.

SELECTIVITY
PHASING
Main tuning
BAND CHANGE
ANT. TRIM
BFO PITCH

- c. Remove the front panel by removing the 11 screws that secure the front panel and unhook the 2 dial lamps over the MEGACYCLE dial drum and allow it to swing forward on wires.
  - d. Remove the KILOCYCLES dial.
- *e*. Remove the three screws and spacers holding the oscillator to the chassis.
- f. Tip rear of oscillator downward. Turn slightly to clear shaft, and lift out.

### 76. Tuning and Band-change Gearing

- a. General. Although the tuning and bandchange gearing of the receiver can be removed as a complete unit, this is not usually necessary in order to make repairs. Almost all repairs can be made with the gears still in the receiver. Complete instructions for gaining access to the gearing, reassembling the gearing, and removing the entire gearing as a unit are given in the following subparagraphs.
- b. Gaining Access to Gearing. (1) Remove the top and bottom dust covers from the receiver
- (2) Remove the SELECTIVITY, PHASING, BFO PITCH, KILOCYCLES dial, and BAND CHANGE knobs.
- (3) Remove the front panel screws as described in paragraph 75, and lift off the panel but do not detach it from the wiring to the chassis.
- (4) Remove the pin holding the pointer pulley assembly to shaft B.
- (5) Loosen the setscrews in the pulleys, and remove the pulleys.
  - (6) Remove retaining ring from shaft I.

**Caution:** Do not disassemble any further without marking those mating gears which are referenced, 1, 2, and 3 on figure 31, rotate shaft C to its extreme counterclockwise position (band 1). Mark the tooth of gear 85 on shaft G and the pin on gear 144 on shaft H that are oppo-

site each other. With paint, scribe a long mark on gear 90 on shaft F and gear 85 on shaft G, using the top edge of the front gear panel as a straight line.

- (7) Remove the four screws and lockwashers from the front gear panel assembly and carefully lift off the panel assembly, making sure that shafts C and H come with the front gear panel assembly.
- (8) All gears and parts are now accessible and repairs can be made as required. Replace loading cord, if in poor condition.
- c. REASSEMBLY OF GEARING. The following instructions are given as a guide to the proper method of replacing parts. Apply a thin film of AN-G-25 or equivalent grease to all bearing surfaces when reassembling.
- (1) Loading cord. When installing a new loading cord, cut the cord in half and tie a small loop in one end of each piece for attachment to the springs. To assemble, push the other end of each piece through the hole in the proper gear and knot it. The lengths of the cords (5 inches between knots) and the amount around each gear drum should be such that it will allow the stops on shaft A to operate before the spring strikes either gear drum. The spring is loaded to 6 pounds pull by disengaging a gear in the affected group, and winding the cord up on one of the gear drums. Coat the knots with Duco cement to prevent them from becoming untied.
- (2) Precautions in reassembling band-change gearing. Observe the following precautions when reassembling the band-change gearing, shafts G and H.
- (a) Place the centering spring so that it holds the slots in the Geneva wheel in the path of the driving pin on the gear of shaft G.
- (b) The radial pin on the overtravel coupler in the bandswitch shaft assembly should be placed about 60° clockwise from the stop pin in the rear plate. After replacing ball, assemble Geneva-wheel shaft assembly, with the pin in the gear against the clockwise side of the radial pin.

- (c) Use washers to shim shaft C so that a pull of 8 pounds minimum is required on the pin drive of shaft C for detent disengagement. These washers are shims which should be used on shafts C and H, respectively, in the quantity required to keep end play at a reasonable minimum.
- (d) With shaft H assembled as explained, the two stop pins will be in the position shown in figure 31: one pin toward shaft E and the other 120° clockwise from it. The stop-idler gear should be rotated counterclockwise until its pin approaches the pin on shaft H as shown, with the ball detent on shaft C in its hole or detented position, and with the pin in the gear on shaft G directly under the shaft as shown in figure 30.
- (e) Shaft G, when turned clockwise, must hit the stop after about 45° rotation. The ball on shaft C will then detent shaft G every 180°. When shaft G has rotated 71/2 revolutions counterclockwise (or 15 detent positions), the pin in the gear on shaft H and the radial pin on bandswitch shaft assembly, must have rotated clockwise until the radial pin is just touching or about to touch the pin in the rear plate. Further rotation of shaft G should cause the pin in the gear to leave the radial pin arrested by the pin in the rear plate. If the stop pins hit before 15 detent positions are made, readjust the mating of the gears. Shaft G must be able to rotate a minimum of 141/2 revolutions (29 detent positions) (figs. 30 and 31).

### 77. R-f Slug Rack

- a. General. Except for lubrication, the r-f slug rack requires very little maintenance. It should not be taken apart except to replace worn or broken parts. Use the following procedure to check the proper alinement of cams when reassembling.
- b. CAM POSITIONS. Three cam locating holes are located in the front plate of the r-f slug rack assembly. When correctly phased or synchronized, the tips of all three cams will appear simultaneously before their respective alining holes. It may be necessary to use a small mirror

to observe the holes accurately. If this is not practicable, another method of checking the operation of the cams is as follows:

- (1) Turn the BAND CHANGE knob to tuning step 30 (29.5 to 30.5 mc) and turn the tuning dial to the extreme clockwise position. View the cam of camshaft assembly (right-hand end) from the front. The cam rider, or follower, should be located approximately 1/16 inch to the right of the tip of the cam. The cam rider should descend the right-hand edge of the cam when the tuning dial is turned counterclockwise.
- (2) Turn the BAND CHANGE knob to tuning step 16 (15.5 to 16.5 mc) and turn the tuning dial to the extreme counterclockwise position. The cam rider should be on the descending portion of the cam but should not be bottomed at the lowest point of the cam.
- (3) Turn the BAND CHANGE knob to tuning step 15 (14.5 to 15.5 mc) and turn the tuning dial to the extreme clockwise position. Viewing the center cam from the front, the cam rider should be positioned about 1/16 inch to the left of the tip of the cam.
- (4) Turn the BAND CHANGE knob to tuning step 8 (7.5 to 8.5 mc) and turn the tuning dial to the extreme counterclockwise position. Viewing the center cam from the front, the cam rider should be on the descending portion of the cam but should not be bottomed at the lowest point of the cam.
- (5) Turn the BAND CHANGE knob to tuning step 7 (6.5 to 7.5 mc) and turn the tuning dial to the extreme clockwise position. Viewing the left-hand cam from the front, the cam rider should be located approximately 1/16 inch to the right of the tip of the cam. The cam rider should descend the right-hand edge of the cam when turning the tuning dial counterclockwise.
- (6) Turn the BAND CHANGE knob to tuning step 4 (3.5 to 4.5 mc) and turn the tuning dial to the extreme counterclockwise position. The cam rider should be on the descending portion of the cam but should not be bottomed at the lowest point of the cam.
- c. REALINEMENT OF CAMS. If the cams are not properly alined, they can be realined by loosening the setscrews in the driving coupler

on shaft C (fig. 31), adjusting the cam positions, and tightening the setscrews again.

### 78. Replacement of Dial Cables (fig. 39)

- a. GENERAL. To replace either the slide-rule pointer cable or the drum cable, it is necessary to remove the front panel. Use the following procedure:
- (1) Remove the top and bottom dust covers from the receiver.
- (2) Remove the SELECTIVITY, PHASING, BFO PITCH, ANT. TRIM, KILOCYCLES dial, and BAND CHANGE knobs.
- (3) Remove the front panel screws and lift off the panel but do not detach it from the wiring to the chassis.
- b. Pointer Cable. To replace the pointer cable, a 36%-inch length of nylon-covered cable is required.
- (1) Turn pulley A counterclockwise to the stop.
- (2) Tie a loop in the end of the cable and string the cable on pulley A.
- (3) Wind the cable twice around pulley A, run it around pulley D, then attach it to the pointer, and run it around pulley C.
- (4) Terminate the cable at the end of the spring on pulley A. The spring should be pulled to full tension.
- (5) Replace the front panel by reversing the procedure in subparagraph a above.
- c. DRUM CABLE. To replace the drum cable, a 27-inch length of nylon-covered string is required.
- (1) Turn the BAND CHANGE shaft to tuning step 30 (29.5 to 30.5 mc) position, thus causing pulley B to reach its clockwise stop.
- (2) Tie a loop in the end of the cable and attach it to pulley B and wind it around as shown in figure 39.
- (3) Turn pulley E about  $\frac{1}{2}$  turn and hold it against the tension of the spring.

- (4) Run the cable to pulley E and work it around the pulley  $1\frac{1}{2}$  turns or more as required, before attaching the end.
- (5) Loosen the setscrew in the hub of the drum and aline the 29.5- to 30.5-mc scale so that it will show in the window when the front panel is replaced. Tighten the setscrew.




Figure 39. Replacement of dial cables.

### 79. Refinishing

Instructions for refinishing badly marred panels are given in TM 9-2851.

# Section III. ALINEMENT PROCEDURES

### 80. General

a. While alinement of the receiver can be considered a periodic necessity, the repairman should not go about this task in a haphazard manner or with inadequate facilities. Alinement should be undertaken only after all other tests and checks fail to improve the operation of a malfunctioning set.

- b. Before beginning alinement, allow a warmup period of at least 15 minutes for the receiver and test equipment.
- c. While an adequate list of test equipment follows in paragraph 81, it is possible to aline the receiver, using the built-in calibration oscillator as a signal generator and the S meter M101 in the OUTPUT position to trim the various capacitors for maximum output.

### 81. Test Equipment for Alinement and Adjustment

In addition to the test equipment listed in paragraph 62, the following items are required for alining and adjusting Radio Receiver R-388/URR:

- a. Two bakelite alinement tools, with  $\frac{1}{8}$  and  $\frac{5}{16}$ -inch screw-driver type bits, are required for adjusting cores and trimmer capacitors.
- b. A headset or a permanent magnet type speaker (4-ohm voice coil or 600-ohm matching transformer equipped) will be required to provide aural response, since the receiver is not equipped with a speaker.

### 82. Crystal Oscillator V105 Trimmer Adjustment

- a. Trimmer capacitor C167, marked XTAL on chassis, should be adjusted to provide an input capacity of 32 uuf across the crystal holders. If this capacitor is badly mistuned, the crystals will be off frequency and low in output.
- b. Connect a 470,000-ohm resistor to pin 7 of V102. Connect vtvm (vacuum-tube voltmeter) between free end of 470,000-ohm resistor and chassis. (Resistor is used to reduce capacity of meter probe.)
- c. In all the following adjustments, the trimmers should be peaked if the indicated voltage is not more than 2 volts. If the voltage is more than 2 volts, detune the trimmer toward minimum capacity until voltage reads 2. (See fig.

33 for location of trimmer.) Repeat this procedure when performing the following adjustments.

- (1) When tuning trimmer marked 30, with BAND CHANGE switch on tuning step 30 (29.5 to 30.5 mc).
- (2) When tuning trimmer marked 28, with BAND CHANGE switch on tuning step 28 (27.5 to 28.5 mc).
- (3) When tuning steps 26 through 14, tuning correspondingly marked trimmers (see par. 4b for MEGACYCLES dial markings).
- (4) With BAND CHANGE switch on tuning step 1. Adjust trimmer labeled BC which is nearest V105.
- d. Remove the 470,000-ohm resistor. Connect the resistor to pin 1 of V103. Connect vtvm, between free end of resistor and chassis.
- e. Place BAND CHANGE switch on tuning step 1. Tune trimmer marked BC that was not previously tuned as described above.

### 83. 100-kc Calibration Oscillator Adjustment

Calibrate the 100-kc crystal oscillator as explained in paragraph 17.

## 84. I-f Amplifiers and Crystal Filter Unit Alinement

Connect the signal generator between the grid (pin 7) of V106 and chassis. Connect one end of a clip lead between C173 and C111 at the output side of the calibration oscillator. Hold the other end of the lead near the grid of V106. Set the CALIBRATE switch at ON. Set the signal generator to zero beat at 500 kc. Turn the calibrator oscillator off by setting the CALIBRATE switch to OFF. Connect detuning net-

work (.01-uf capacitor in series with 4,700-ohm resistor) from plate of V107 to chassis. Connect a vtvm across diode load resistor R151. Place SELECTIVITY switch S114 in the 0 position.

- a. Tune the secondary (bottom) slug or T103 for maximum indication. Keep diode load voltage below 3 volts by adjusting signal generator output.
- b. Connect detuning network from terminal 4 of T103 to chassis. Tune the primary (top) slug for maximum indication.
- c. Connect the detuning network from plate of V108 to chassis. Tune the secondary of T104 for maximum indication.
- d. Connect the detuning network to terminal 4 of T104. Tune the primary of T104 for maximum indication.
- e. Connect the detuning network to the plate of V109. Tune secondary of T105 for maximum indication.
- f. Connect the detuning network to terminal 4 of T105. Tune the primary of T105 for maximum indication.
  - g. Tune T101 for maximum vtvm indication.

### 85. Bfo Adjustment

- a. Turn the BFO switch to ON. Connect the signal generator (500 kc signal) between the grid (pin 7) of V106 and chassis. Set the BFO PITCH capacitor to midrange.
- b. With a Bristo wrench loosen the BFO PITCH knob, and match the index line to line on the chassis. Tighten the knob.
- c. Adjust the tuning core in T106 for zero beat, using insulated screw driver.

### 86. Alinement of Dial

- a. Loosen the two front setscrews on the vfo coupler with the wrench. (Insert the wrench from the right side of the oscillator cylinder.)
- b. Turn the vfo shaft by hand to an extreme clockwise position.
- c. Turn BAND CHANGE switch to tuning step 2 (1.5 to 2.5 mc). Turn main tuning dial to 2.0 mc. Set the KILOCYCLES dial to zero-zero. Tighten setscrews.
- d. Connect one end of the clip lead to pin 7 of V106. Connect the other end of the lead between C173 and C111. Turn the CALIBRATE control to ON.
- e. Rotate the vfo shaft counterclockwise by hand, noting beat note once every revolution. Stop at the sixth beat note and carefully set to zero beat. Tighten the coupler screws.

### 87. Tuning Step 2 and Variable I-f (for Evennumbered Steps)

- a. Connect the signal generator with a 270-ohm series resistor to the ANTENNA jack. Set BAND CHANGE switch to tuning step 2 (1.5 to 2.5 mc). Set the MEGACYCLE tuning dial to read 1.6 mc. Connect the vtvm between diode load resistor R151 and chassis.
- b. Turn the BFO switch to ON and adjust the signal generator for 1.6-mc output. Adjust the output of signal generator to give some value of diode load voltage below 5 volts. Tune adjustments marked 1.6 (slugs in L116, L118, and L102) for a maximum indication (figs. 30 and 33). Continue to adjust signal generator output so that the diode load voltage does not rise over 5 volts.

- c. Set the MEGACYCLE tuning dial to read 2.4 mc. Set generator to zero beat at 2.4 mc with the bfo. Tune adjustments marked 2.4 (trimmer capacitors C174, C180, and C104) for a maximum indication, keeping diode load voltage below 5 volts (fig. 33).
- d. Repeat the tuning process as outlined above at 1.6 and 2.4 mc until no further increase in output can be obtained.

### 88. Tuning Step 3 and Variable I-f (for Oddnumbered Steps)

- a. Connect the signal generator and the vtvm as directed in paragraph 87.
- b. Set the MEGACYCLES dial to read 2.6 mc. Set signal generator to zero beat at 2.6 mc with bfo. Turn off the bfo. Adjust the tuning cores of L117, L119, and L103 (fig. 33) marked 2.6 for maximum indication on the vtvm.
- c. Set the MEGACYCLES tuning dial to read 3.4 mc. Set signal generator to zero beat at 3.4 mc with the bfo. Turn off the bfo. Adjust the trimmer capacitors marked 3.4 (C176, C182, and C106) for maximum indication on the vtvm. This completes the alinement of the variable i-f stage.

### 89. Tuning Steps 4 Through 7

- a. Connect the signal generator and the vtvm as directed in paragraph 87. Set the BAND CHANGE switch to tuning step 4 (3.5 to 4.5 mc).
- b. Set main tuning dial to read 4.0 mc. Set signal generator to zero beat at 4.0 mc with the bfo. Turn off the bfo. Adjust tuning cores marked 4.0 (in L104, L107, and L111) for maximum indication on the vtvm.

- c. Set the BAND CHANGE switch to tuning step 7 (6.5 to 7.5 mc). Set main tuning dial to read 7.0 mc. Set signal generator to zero beat at 7.0 mc with the bfo. Turn off the bfo. Tune trimmer capacitors marked 7.0 (C108, C120, and C128) ) for maximum indication on the vtvm.
- d. Repeat tuning procedures at 4.0 and 7.0 mc until no further increase is noticeable on the vtvm.

### 90. Tuning Steps 8 Through 15

- *a*. Connect signal generator and the vtvm as directed in paragraph 87.
- b. Set the BAND CHANGE switch to tuning step 8 (7.5 to 8.5 mc). Set the MEGACYCLES tuning dial to 8.0 mc. Set the signal generator to zero beat with the bfo at 8.0 mc. Turn off the bfo. Adjust tuning cores marked 8 (L105, L108, and L112) for maximum indication on the vtvm.
- c. Set the BAND CHANGE switch to tuning step 15 (14.5 to 15.5 mc). Set the MEGACY-CLES dial to read 15.0 mc. Set the signal generator to zero beat with the bfo at 15.0 mc. Turn off the bfo. Tune trimmer capacitors marked 15 (C110, C122, and C130) for maximum indication on the vtvm.
- d. Repeat the tuning procedures at 8.0 mc until no further increase in output can be obtained.

### 91. Tuning Steps 16 Through 30

- a. Connect the signal generator and vtvm as outlined in paragraph 87.
- b. Set the BAND CHANGE switch to tuning step 16 (15.5 to 16.5 mc). Set the MEGACY-CLES tuning dial to 16.0 mc. Adjust the tuning cores marked 16 (L106, L109, and L113) for maximum indication at the vtvm.

- c. Set the BAND CHANGE switch to tuning step 30 (29.5 to 30.5 mc). Set the MEGACY-CLES tuning dial to 30.0 mc. Adjust trimmer capacitors marked 30 (C124 and C132) for a maximum indication on the vtvm.
- d. Repeat tuning procedures at 16 and 30 mc until no further increase in output is apparent.

### 92. R-f Alinement, Tuning Step 1

- a. Connect the signal generator and the vtvm as directed in paragraph 87.
- b. Set the BAND CHANGE switch to tuning step 1 (.5 to 1.5 mc). Set the MEGACYCLES tuning dial to .6 mc. Set the signal generator to zero beat with bfo at .6 mc. Turn off the bfo. Adjust core in L114 so that it is approximately in the same position in the inductor as the cores in L116 and L118.
- c. Adjust tuning cores marked .6 (in L101 and L110) for a maximum indication
- d. Adjust trimmer capacitor marked .6 (C140) for a maximum indication.

*Note*. Two peaks may be found when tuning capacitor C140. Use the peak that requires the higher value of capacity.

- e. Set the MEGACYCLES tuning dial to 1.4 mc. Set signal generator to zero beat with the bfo at 1.4 mc. Turn off the bfo. Tune trimmers marked 1.4 (C102 and C119) for a maximum indication of the vtvm. Adjust tuning core marked 1.4 (L115) for a maximum indication of the vtvm.
- f. Repeat the tuning procedures at .6 and 1.4 mc until no further increase in output can be obtained.

### 93. Vfo Alinement

- a. Due to the careful design of the vfo used in Radio Receiver R-388/URR, it is unlikely that the dial calibration will become inaccurate through normal use or treatment. However, should the dial calibration become inaccurate, the following paragraphs will enable a capable technician with adequate facilities to correct the dial calibration.
- b. If the slide-rule calibration only is off frequency in the same directions on all bands, the dial pointer can be corrected by grasping the dial cord and sliding the pointer along the cord until the correct position for the pointer is found.
- c. If the venier dial calibration is incorrect by the same amount for all bands, aline in accordance with instructions in paragraph 86.
- d. If all other correction measures fail and the calibration continues erratic or inaccurate, it can be assumed that one of the parts within the oscillator can is defective. In this case the oscillator must be removed as outlined in paragraph 75.

**Caution:** The vfo is inclosed in a hermetically sealed container. No attempt should be made to remove this shield unless adequate repair facilities are available.

### 94. Alinement of Inductor L124

- a. Turn the BAND CHANGE switch to tuning step 1 (.5 to 1.5 mc).
- b. Tune to the spurious signal (whistle) at 1,250 kc.
- c. From the bottom of the receiver adjust L124 for the greatest attenuation of the spurious signal.

### Section IV. FINAL TESTING

### 95. General

This section is intended as a guide to be used in determining the quality of the repaired receiver. The minimum test requirements outlined in the following paragraphs may be performed by maintenance personnel with adequate test equipment and the necessary skills. Repaired equipment meeting these requirements will furnish uniformly satisfactory operation.

### 96. Test Equipment Required for Final Testing

The instruments needed for testing the repaired equipment are listed in paragraph 62. No attempt should be made to run performance checks unless the performance characteristics of the available test equipment are equal or superior to the equipment listed.

### 97. Beat-frequency Oscillator

- a. Calibration oscillator can be used. Tune receiver.
  - b. Turn the BFO switch to ON.
- c. Turn the main tuning dial through 1 mc of tuning.
- d. An oscillatory note will be heard when the kc indicator reads zero-zero with the hairline zero adjustment at dead center. The mc slide rule dial pointer will be superimposed on one of the calibration marks of the dial.

### 98. Sensitivity

a. Set the controls as follows:

AVC switch . . . . . OFF

RF GAIN control.....Maximum

AUDIO GAIN control.. As required for 10-1 signal plus noise-to-noise

SELECTIVITY ......0

LIMITER switch .....OFF

BFO.....OFF

- b. Apply an r-f signal, modulated 30 percent at 400 cps, to the ANTENNA jack through a 47-ohm resistor in series with a 100-uuf capacitor.
- c. Make tests at the low-, middle-, and high-frequency points of each band.
- d. The sensitivity on tuning step 1 shall be better than 15 uv. The sensitivity on tuning steps 2 through 30 shall be better than 5 uv.
- e. The over-all gain on tuning steps 2 through 30 shall be enough to give 1 watt of audio with less than 5 uv input (AVC off).
- f. The c-w sensitivity on tuning step 1 shall be better than 5 uv and on tuning steps 2 through 30, the c-w sensitivity shall be better than 1.6 uv.

### 99. Signal Plus Noise-to-noise Ratio

- a. This test is made most conveniently along with the sensitivity test described above.
- b. After each section of the band is tested as outlined in paragraph 98, apply a 1,000-uv signal modulated 30 percent at 400 cps. The AUDIO GAIN should be adjusted to give 500 mw output.
- c. Turn the generator modulation off. The noise level should be better than 45 db below the 500-mw level.

### 100. Selectivity

- a. Turn SELECTIVITY to 0.
- b. Set the signal generator modulated 30 percent at 400 cps at a frequency on tuning step 1.
- c. Tune receiver to signal generator frequency.
- d. Measure the selectivity at the 6-db and 60-db attenuation points.
- e. The bandwidth at 6-db point shall be between 5.5 kc and 6.5 kc.
- f. The bandwidth at the 60-db point shall be between 17 kc and 20-kc.

### 101. A-v-c Characteristic

The avc will begin to take over on tuning step 1 at a threshold of 6 uv of input signal. On tuning steps 2 through 30, the avc will begin to take over at a threshold of 3 uv of input signal. For a rise of .5 uv of input signal to 125 uv of input signal, the output level should increase no more than 3.5 db. For a rise of 125 uv to 500,000 uv in the input signal, the output level should not increase more than 5 db. For references, apply a 4.9-mc input signal modulated 30 percent at 400 cps to the ANTENNA jack through a seriesconnected 100-uuf capacitor and a 47-ohm resistor.

### 102. Over-all Distortion for an Input of 1,000 Uv

Modulation percent	Output	Max distortion percent
30	500 mw	7.5
30	1.5 w	11
80	500 mw	11
80	1.5 w	14
80	2.5 w	17

### **CHAPTER 6**

# SHIPMENT AND LIMITED STORAGE AND DEMOLITION TO PREVENT ENEMY USE

# Section I. SHIPMENT AND LIMITED STORAGE

### 103. Disassembly

The circumstances involved in shipment and storage vary, therefore no definite procedure for repacking can be given. The following instructions are recommended as a guide for preparing the radio receiver for transportation and storage. To disassemble the equipment reverse the procedure for setting up the unit.

- a. Turn the OFF-STANDBY-ON switch to OFF.
  - b. Remove power plug P101.
- c. Disconnect antenna and ground from the receiver. Remove the handset plug from the receiver PHONES jack.
  - d. Remove receiver from rack.

## 104. Repacking for Shipment and Limited Storage

- a. The exact procedure in repacking for shipment or limited storage depends on the material available and the conditions under which the equipment is to be shipped or stored. Refer to paragraph 10 and figure 7 and reverse the instructions given.
- b. Whenever practicable, place a dehydrating agent, such as silica gel, inside the receiver. Box or package the headset. Wrap each unit in corrugated paper and protect each package with a waterproof barrier. Seal the seams of the paper barrier with a waterproof sealing compound or tape. Pack the protected components

in a wooden case, providing at least 3 inches of excelsior padding or other similar material between the paper barrier and the packing case.

# Section II. DEMOLITION OF MATERIAL TO PREVENT ENEMY USE

### 105. General

The instructions below should be followed only upon order of the commander.

### 106. Destruction of Equipment

- a. SMASH. Smash the controls, tubes, coils, switches, capacitors, and headsets, using sledges, axes, handaxes, pickaxes, hammers, crowbars, or other heavy tools.
- b. Cut. Cut cords, headsets, and wiring, using axes, handaxes, or matches.
- c. Burn. Burn technical manuals, cords, resistors, capacitors, coils, and wiring, using gasoline, kerosene, oil, flame throwers, or incendiary grenades.
  - d. BEND. Bend panels, cabinet, and chassis.
- e. EXPLOSIVES. If explosives are necessary, use firearms, grenades, or TNT.
- f. DISPOSAL. Bury or scatter the destroyed parts in slit trenches, fox holes, or other holes, or throw them into streams.
  - g. Destroy Everything.

### **APPENDIX I**

### **REFERENCES**

Note. For availability of items listed, check SR 310-20-3 and SR 310-20-4. Check Department of the Army Supply Catalog SIG 1 for Signal Corps supply catalog pamphlets.

### 1. Army Regulations

AR 380-5	Safeguarding Military Information.
AR 750-5	Maintenance of Supplies and Equipment (Maintenance Responsibilities and Shop Operation).

### 2. Supply Publications

SIG 1	Introduction and Index.
SIG 3	List of Items for Troop Issue.
SIG 5	Stock List of All Items.
SIG 6	Sets of Equipment.
SIG 7&8	Organizational Maintenance Allowances and Field and Depot Maintenance Stockage Guide.
SB 11-6	Dry Battery Supply Data.
SB 11-47	Preparation and Submission of Requisitions for Signal Corps Supplies.
SB 11-76	Signal Corps Kit and Materials for Moisture- and Fungi-Resistant Treatment.

### 3. Publications on Test Equipment

Navships 91379	Signal Generator AN/URM-25(*).
TM 11-300	Frequency Meter Set SCR-211-(*).
TM 11-2627	Tube Testers I-177 and I-177-A.
TM 11-5017	Output Meter TS-585A/U.
TM 11-5030	Signal Generator TS-497A/URR.
TM 11-5044	Frequency Meter TS-174(*)/U.
TM 11-5511	Electronic Multimeter TS-505(*)/U.
TM 11-5527	Multimeter TS-352/U.
TO 16-35TS382-2	Audio Oscillator TS-382(*)/U.

### 4. Painting, Preserving, and Lubrication

TB SIG 13 Moistureproofing and Fungiproofing Signal Corps Equipment.

TB SIG 69 Lubrication of Ground Signal Equipment.

TM 9-2851 Painting Instructions for Field Use.

5. Camouflage

FM 5-20 Camouflage, Basic Principles.

6. Decontamination

TM 3-220 Decontamination.

7. Demolition

FM 5-25 Explosives and Demolitions.

8. Other Publications

FM 24-18 Field Radio Techniques.

SR 310-20-3 Index of Training Publications (Field Manuals, Training Cir-

culars, Firing Tables and Charts, Army Training Programs, Mobilization Training Programs, Graphic Training Aids, Joint Army-Navy-Air Force Publications, and Combined Communi-

cations Board Publications).

SR 310-20-4 Index of Technical Manuals, Technical Regulations, Technical

> Bulletins, Supply Bulletins, Lubrication Orders, Modification Work Orders, Tables of Organization and Equipment, Reduction Tables, Tables of Allowances, Tables of Organization, and

Tables of Equipment.

SR 700-45-5 Unsatisfactory Equipment Report (Reports Control Symbol

CSGLD-247).

SR 745-45-5

Report of Damaged or Improper Shipment (Reports Control NAV DEPT SERIAL 85P00 Symbols CSGLD-66 (Army), SandA-70-6 (Navy), and AF-

AFR 71-4

TB 11-300-3 Rectifier Power Unit RA-133 and RA-133-A.

TB 11-499-()† Basic Radio Propagation Predictions.

Tube Test Data Cards for use with Tube Tester I-177. TB 11-2627-2

MC-U2 (Air Force)).

TB SIG 5 Defense Against Radio Jamming.

TB SIG 25 Preventive Maintenance of Power Cords.

TB SIG 66 Winter Maintenance of Signal Equipment.

TB SIG 72 Tropical Maintenance of Ground Signal Equipment.

Desert Maintenance of Ground Signal Equipment. TB SIG 75

**TB SIG 123** Preventive Maintenance Practices for Ground Signal Equipment.

Preventive Maintenance Guide for Radio Communication Equip-**TB SIG 178** 

ment.


TB SIG 219	Operation of Signal Equipment at Low Temperatures.
TM 9-2857	Storage Batteries Lead-Acid Type.
TM 11-314	Antennas and Antenna Systems.
TM 11-415	Dry Batteries.
TM 11-453	Shop Work.
TM 11-455	Radio Fundamentals.
TM 11-472	Repair and Calibration of Electrical Measuring Instruments.
TM 11-477	Fixed Station Radio Repair and Maintenance (Personnel Training Text).
TM 11-483	Suppression of Radio Noises.
TM 11-486	Electrical Communication Systems Engineering.
TM 11-490	Electrical Fundamentals.
TM 11-496	Training Text and Applicatory Exercises for Amplitude-Modulated Radio Sets.
TM 11-499	Radio Propagation Handbook.
TM 11-875	Intermediate and High Frequency Receiver, Model AR-8506-B.
TM 11-4000	Trouble Shooting and Repair of Radio Equipment.

<sup>†</sup> A new TB in this series is issued monthly which gives propagation predictions three months in advance.

### 9. Abbreviations

a-calternating-current	JANJoint Army-Navy
a-faudio-frequency	kckilocycle
a-mamplitude-modulated	l-flow-frequency
ampampere	LPlowpass
amplamplifier	mamilliampere
avcautomatic volume control	mcmegacycle
bfobeat-frequency oscillator	mcwmodulated continuous wave
BPband pass	mh or MHmillihenry
Ccentigrade	mvmillivolt
cpscycles per second	mwmilliwatt
cwcontinuous wave	papower amplifier
dbdecibel	r-fradio-frequency
$ ext{d-c}$ direct-current	rmsroot mean square
diamdiameter	SLC straight-line capacity
dimendimension	termterminal
FFahrenheit	ufmicrofarad
f-mfrequency-modulation	uufmicromicrofarad
h-fhigh-frequency	uwmicrowatt
h-vhigh-voltage	uvmicrovolt
icwinterrupted continuous wave	vfovariable-frequency oscillator
i-fintermediate-frequency	

### RESISTOR COLOR CODES



TL32454S

Figure 40. Resistor color codes.




Figure 41. Capacitor color codes.

# APPENDIX II

# IDENTIFICATION TABLE OF PARTS

# 1. Requisitioning Items

The fact that a part is listed in this table is not sufficient basis for requisitioning the item. Requisitions must cite an authorized basis, such as T/O&E, T/A, SIG 7&8, list of allowances of expendable material, or another authorized supply basis. The Department of the Army Supply Catalog applicable to the equipment covered in this manual is SIG 7&8-R-388/URR. For an index of available supply catalogs in the Signal portion of the Department of the Army Supply Catalog, see the latest issue of SIG 1, Introduction and Index.

# 2. Identification Table of Parts for Radio Receiver R-388/URR

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
	RECEIVER, radio: Radio Receiver R-388/URR; receives MCW, CW, or AM voice transmissions; for communication use; .5 to 30.5 mc in thirty 1-mc ranges; for 115- to 230-v operation at 45 to 70 cyc; 85 w power consumption; chassis w/panel 10½" h x 19" w x 3/16" thk for standard rack mtg; 10½" h x 19" wd x 13½" d behind panel; self-contained (does not incl speaker); 16-tube superheterodyne circuit; uses single, double, or triple conversion depending upon freq of received signal; 500 kc if HF osc is crystal-controlled; BFO; crystal filter; integral calibration crystal osc (100 kc); amplified AVC; series type noise limiter; Collins Model 51,33.	Reception of MCW, CW, and voice (AM) signals.	2C4180-388
	BALL, bearing: steel; spherical, 3/16" dia; Norma-Hoff-man per Collins part #309 5200 00.	Part of main gear assembly.	3H227-2
	BOARD, terminal: 2 riveted brass solder lug term; ½" between ctr; phenolic sheet LTS-E4; 1.375" lg x 1" wd x 27/64" h o/a; two .140" dia mtg holes diagonally on 1.125" x .750" ctr; Collins part/dwg #505 2124 001; spec MIL-P-3115A.	Mounts antenna coil, tuning steps 16 to 30.	3Z770-2.101

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
	BOARD, terminal: general purpose; 2 brass solder lug cad pl term; $\frac{7}{8}$ " lg x $\frac{3}{8}$ " wd x 1/16" thk o/a.	Component mounting.	3Z770-2.79
	BOARD, terminal: general purpose; 3 brass solder lug term; 11/8" lg x 3/8" wd x 1/16" thk o/a.	Component mounting.	3Z770-3.49
	BOARD, terminal: general purpose; 3 brass solder lug term, 3 cad pl steel screws; $21/8$ " lg x $5/8$ " wd x $11/16$ " h o/a; two .136" dia mtg holes $13/4$ " between ctr.	Tie points.	3Z770-3.44
	BOARD, terminal: general purpose; 3 brass solder lug. term; phenolic board; $11/8''$ lg x $3/8''$ wd x $1/16''$ thk o/a.	Tie points.	3Z770-3.48
	BOARD, terminal: general purpose; 2 solder lug term, brass, cad pl; terms $\frac{3}{8}$ " between ctr; phenolic board; $\frac{5}{8}$ " lg x $\frac{1}{2}$ " wd x 23/32" h; one .140" dia mtg hole.	Component mounting.	3Z770-2.102
	BUTTON, plug: brass, nickel pl; for 3/8" dia hole; .050" to .062" thk; 1/2" dia x 15/64" thk; Collins part #308 0051 00.	Covers holes.	2Z1480.78
	BUTTON, plug: fits $1/2$ " hole; $41/64$ " dia x $1/16$ " d, $7/32$ " lg prongs.	Covers holes.	2Z1607-76
	CABLE, assembly: stranded SS core .018" dia w/nylon coating .032" dia OD; 7 strands; 35 lbs pull; 8" lg; 1 end terminates in loop stripped of nylon, secured by brass sleeve; loop passes .031" min dia wire; Berkley Fly Co per Collins part #432 1011 00.	Loading cable (part of main gear assembly).	2Z1588-13
	CABLE, mechanical: stranded steel core .012" dia w/nylon coating .032" OD.	Dial cable.	2Z8877.406
	CABLE, power: underwriters type SJ; two #18 AWG stranded cond (41 strands #34 AWG bare copper).	A-c power cable.	1B3018-2.28
0106, 0118	CAM.	Variable i-f slug rack cams.	6C10A-2

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
0116	CAMSHAFT ASSEMBLY.	H-f, r-f slug rack cam assembly.	2Z8203-515
0117	CAMSHAFT.	Medium-frequency r-f slug rack cam assembly.	2Z8203-514
0115	CAMSHAFT ASSEMBLY.	L-f, r-f slug rack cam assembly.	2Z8203-516
C116	CAPACITOR, fixed: ceramic; 1.0 uuf $\pm$ .25 uuf; 500 vdcw; JAN type CC30CK010C.	V102 grid coupling.	3D9001-29
C133	CAPACITOR, fixed: ceramic; 1.5 uuf $\pm$ .25 uuf; 500 vdcw; JAN type CC30CK1R5C.	V102 grid coupling tuning steps 4 to 7.	3D9001E5-11
C111, C117, C192, C196, C201, C221	CAPACITOR, fixed: ceramic; 2 uuf ± .25 uuf; 500 vdcw; JAN type CC30CK020C.	C111: 100 ke signal coupling to V101. C117: V101 grid coupling, tuning step 1. C192: T103 top coupling. C196: T104 top coupling. C201: T105 top coupling. C221: Variable i.f. top coupling.	3D9002-27
C220	CAPACITOR, fixed: ceramic; 4 uuf $\pm$ .25 uuf; 500 vdcw; JAN type CC30CK040C.	Variable i-f top coupling.	3D9004-25
C238	CAPACITOR, fixed: ceramic; 5 uuf $\pm$ 1/2 uuf; 500 vdcw; JAN type CC30CK050D.	Tuning steps 16 to 30 antenna coupling.	3D9005-121
C173, C187, C237	CAPACITOR, fixed: ceramic; 10 uuf $\pm$ 1 uuf; 500 vdcw; JAN type CC30CK100F.	C173: 100-kc signal coupling to V101. C187: Filter xtal parallel. C237: Tuning steps 8 to 15 antenna coupling.	3D9010-180
C151, C165	CAPACITOR, fixed: ceramic; 15 uuf $\pm 5\%$ ; 500 vdcw; JAN type CC30CK150J.	C151: V105 xtal oscillator plate tuning. C165: V105 xtal oscillator feedback.	3D9015-133
C139	CAPACITOR, fixed: ceramic; 20 uuf $\pm 5\%$ ; 500 vdcw; JAN type CC30CK200J.	L115 trimmer.	3D9020-63

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Name of part and description  CAPACITOR, fixed: ceramic; 22 uuf ±5%; 500 vdcw;  JAN type CC30CK220J.  CAPACITOR, fixed: ceramic dielectric; 24 uuf ±5%; 500 vdcw;  JAN type CC30CK240J.  CAPACITOR, fixed: ceramic; 36 uuf ±5%; 500 vdcw;  JAN type CC30CK360J.  CAPACITOR, fixed: ceramic; 47 uuf ±5%; 500 vdcw;  JAN type CC30CK470J.	vdew; vdew; vdew;	Function of part  Antenna coupling, tuning step 7.  Antenna coupling, tuning steps 16 to 30.  C153: V105 xtal oscillator plate tuning.  C235: Antenna coupling, tuning step 3.  V105 xtal oscillator plate tuning.	Signal Corps stock No. 3D9022-57 3D9024-56 3D9036-14
CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; 500 vdcw; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $+60$ °C).  CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; 500 vdcw; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $\pm$ 60°C).	50 uuf $\pm 2\%$ ; 500 vdcw; does not vary more than over temp range of $0^{\circ}$ C to 50 uuf $\pm 2\%$ ; 500 vdcw; does not vary more than over temp range of $0^{\circ}$ C to	Part of bfo assembly (compensating cap).  Part of bfo assembly (compensating cap).	3D9050-160 3D9050-161
CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; 500 vdcw; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $+60$ °C).	$7/6$ ; 500 vdcw; ary more than ange of $0^{\circ}$ C to	Part of bfo assembly (compensating cap).	3D9050-159
CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; Neg. temp. coef. 1200 (tol $\pm$ 180) uuf/uf/°C; 500 vdcw*; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $+60$ °C).	$^{6}$ ; Neg. temp. $^{7}$ dcwf; (choose an $\pm$ 300 cps $^{2}$ C to $+60^{\circ}$ C).	Part of bfo assembly (compensating cap).	3D9050-170

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

1.7. 7.50		And the state of t	damata	Service of the servic	La resident order	
Signal Corps stock No.	3D9050-171	3D9050-168	3D9050-169	3D9051-68	3D9068-27	3D9100-230
Function of part	Part of bfo assembly (compensating cap).	Part of bfo assembly (compensating cap).	Part of bfo assembly (compensating cap).	Antenna coupling, tuning step 2.	V105 xtal oscillator plate tuning.	C231: Coil L105 (tuning steps 8-15) trimmer. C233: Antenna coupling, tuning step 1.
Name of part and description	CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; 500 vdcw; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $+60$ °C).	CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; 500 vdcw; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $+60$ °C).	CAPACITOR, fixed: ceramic; 50 uuf $\pm 2\%$ ; 500 vdcw; (choose 1 of 7, so that freq does not vary more than $\pm$ 300 cps from freq at 30°C over temp range of 0°C to $+60$ °C).	CAPACITOR, fixed: ceramic; 51 uuf $\pm 5\%$ ; JAN type CC30UK510J.	CAPACITOR, fixed: ceramic; 68 uuf $\pm 5\%$ ; 500 vdcw; JAN type CC30UK680J.	CAPACITOR, fixed: ceramic; 100 uuf $\pm 5\%$ ; 500 vdcw; JAN type CC30UJ101J.
m Ref symbol	C5	C2	CS	C234	C157	C231, C233

 $2. \ \,$  Identification Table of Parts for Radio Receiver R-388/URR (contd)

$ m Ref \ symbol$	Name of part and description	Function of part	Signal Corps stock No.
C114,	CAPACITOR, fixed: ceramic; 10,000 uuf, guaranteed mini-	C114: V101 ave isolation.	3DA10-527
C115,	mum value tolerance; 350 vdcw.	C115: V101 screen r-f bypass.	
C126,		C126: V101 plate circuit decoupling.	
C134,		C134: V102 cathode r-f bypass.	
C135,		C135: V102 screen r-f bypass.	
C137,		C137: L114 to L115 coupling.	
C138,		C138: V102 plate circuit decoupling.	
C141,		C141: V103 cathode r-f bypass.	
C142,		C142: V103 screen r-f bypass.	•
C163,		C163: V105 plate circuit decoupling.	
C164,		C164: V105 screen r-f bypass.	
C170,		C170: V104 cathode r-f bypass.	
C172,		C172: V104 plate circuit decoupling.	
C178,		C178: V103 plate circuit decoupling.	
C183,		C183: V106 cathode r-f bypass.	
C185,		C185: V106 screen r-f bypass.	
C186,		C186: V106 plate circuit decoupling.	
C189,		C189: V107 grid decoupling.	
C190,		C190: V107 screen r-f bypass.	
C191,		C191: V107 plate circuit decoupling.	
C193,		C193: V108 grid decoupling.	
C194,		C194: V108 screen r-f bypass.	
C195,		C195: V108 plate circuit decoupling.	
C197,		C197: V109 grid decoupling.	
C199,		C199: V109 screen r-f bypass.	
C200,		C200: V109 plate circuit decoupling.	
C207,		C207: A-c line filter.	

Signal Corps stock No.		3DB8-222	3DB20-112		3D9005-123	3D9020-77	3D9075-51	3D9100-294
Function of part	C208: Avc ampere degenerative feedback. C209: Audio grid coupling to V112. C211: Audio grid coupling to V113. C213: Avc bypass. C218: V114 screen r-f bypass. C219: V114 plate circuit decoupling. C227: I-f output V111 plate bypass. C228: I-f output coupling.	B+ isolation.	C215: V111 cathode bypass. C216: Bias filter for V113.	Power supply filter.	V114 to V110 bfo coupling.	L105 trimmer.	C123: L108 trimmer. C129: L112 trimmer.	C113: V101 grid coupling. C136: V102 injection coupling. C143: V103 injection coupling. C166: Oscillator feedback network. C171: V104 screen bypass. C184: V106 grid bypass for harmonic amplitude control. C204: Avc rectifier coupling. C205: V111 voltage divider.
Name of part and description		CAPACITOR, fixed: electrolytic; 8 uf; 350 vdcw; JAN type CE63B080P.	CAPACITOR, fixed: electrolytic; 20 uf; 150 vdcw; JAN type CE63C200J.	CAPACITOR, fixed: electrolytic; 2 sect; 35 uf ea sect; 450 vdcw ea sect; JAN type CE52F350R.	CAPACITOR, fixed: mica; 5 uuf $\pm 5\%$ ; 500 vdcw.	CAPACITOR, fixed: mica; 20 uuf $\pm 5\%$ ; 500 vdcw.	CAPACITOR, fixed: mica; 75 uuf $\pm 5\%$ ; 500 vdcw.	CAPACITOR, fixed: mica; 100 uuf $\pm 5\%$ ; 500 vdcw.
Ref symbol	C208, C209, C211, C213, C218, C219, C227,	C223	C215, C216	C217	C206	C109	C123, C129	C113, C136, C143, C166, C171, C184, C204,

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

$\operatorname{Ref}$ symbol	Name of part and description	Function of part	Signal Corps stock No.
C107	CAPACITOR, fixed: mica; 130 uuf ±5%; 500 vdcw.	L104 trimmer.	3D9130-23
C145, C159	CAPACITOR, fixed: mica; 150 uuf $\pm 5\%$ ; 500 vdcw.	C145: L121 trimmer. C159: 1,250-kc filter trimmer.	3D9150-92
C175, C179	CAPACITOR, fixed: mica; 180 uuf $\pm 2\%$ ; 500 vdcw.	C175: L117 trimmer. C179: L118 trimmer.	3D9180-38
C161	CAPACITOR, fixed: mica; 200 uuf $\pm 2\%$ ; 500 vdcw.	V105 xtal oscillator plate tuning.	3D9200-109
C105, C121, C127, C168	CAPACITOR, fixed: mica; 220 uuf $\pm 2\%$ ; 500 vdcw.	C105: L103 trimmer. C121: L107 trimmer. C127: L111 trimmer. C168: V106 grid trap.	3D9220-34
C177, C181	CAPACITOR, fixed: mica; 300 uuf $\pm 2\%$ ; 500 vdcw.	C177: L117 trimmer. C181: L118 trimmer.	3D9300-69
C202	CAPACITOR, fixed: mica; 330 uuf $\pm 2\%$ ; 500 vdcw.	Diode load bypass.	3D9330-27
C103	CAPACITOR, fixed: mica; 430 uuf $\pm 2\%$ ; 300 vdcw.	L102 trimmer.	3D9430-5
C101	CAPACITOR, fixed: mica; 820 uuf $\pm 2\%$ ; 500 vdcw.	L101 trimmer.	3D9820-14
C118	CAPACITOR, fixed: mica; 910 uuf ±1%; 500 vdcw.	L110 trimmer.	3D9910-3
C212	CAPACITOR, fixed: mica; 6800 uuf $\pm 10\%$ ; 500 vdcw; JAN type CM40B682K.	Audio output equalizer.	3K4068221
C214	CAPACITOR, fixed: paper; 2 sect; $100,000-100,000$ uuf $\pm 20\% - 10\%$ ; $600$ vdcw; JAN type CP53B4EF104V.	K101 contact spark suppressor.	3DA100-770
C198A, B	CAPACITOR, fixed: paper; 2 sect; 100,000-100,000 uuf +20% —10%; 600 vdcw; JAN type CP54B4EF104V.	C198A: V109 cathode bypass. C198B: T108 filament winding bypass.	3DA100-777
C205A, B, and C	CAPACITOR, fixed: paper; 3 sect; 100,000 uuf +20% -10% ea sect; 600 vdcw ea sect; JAN type CP54B5EF-104V.	C205A: Bias line bypass. C205B: Part of avc filter. C205C: Noise limiter filter.	3DA100-732

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

m Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
C167	CAPACITOR, variable: ceramic; rotary type; 3 to 12 uuf 1 sect.	Crystal trimming.	3D9012V-25
C110, C122, C124, C130, C132, C146, C148, C148, C169	CAPACITOR, variable: ceramic; rotary type, 1 sect; 5 to 25 uuf.	C110: L105 trimming. C122: L108 trimming. C124: L109 trimming. C130: L112 trimming. C132: L113 trimming. C146: Xtal oscillator plate tuning. C147: Xtal oscillator plate tuning. C148: Xtal oscillator plate tuning. C149: Xtal oscillator plate tuning. C149: C169: Calibration oscillator feedback.	
C188	CAPACITOR, variable: air dielectric; single sect plate meshing type; 3.5 to 27 uuf; SLC characteristic.	Xtal filter PHASING.	3D9027V-6
C102, C104, C106, C108, C119, C128, C128, C144, C152, C152, C152, C156, C156, C156, C156, C156, C156, C156,	CAPACITOR, variable: ceramic; rotary type; 8 to 50 uuf, 1 sect.	C102: L101 trimmer. C104: L102 trimmer. C106: L103 trimmer. C108: L104 trimmer. C120: L107 trimmer. C128: L111 trimmer. C128: L111 trimmer. C140: L115 trimmer. C150: Xtal oscillator tuning. C154: Xtal oscillator tuning. C156: Xtal oscillator tuning. C156: Xtal oscillator tuning. C158: Xtal oscillator tuning. C174: L116 trimmer. C176: L117 trimmer.	3D9050V-117

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
C180, C182		C180: L118 trimmer. C182: L119 trimmer.	
C224, C230	CAPACITOR, variable: air dielectric; single sect, plate meshing type; 7 to 100 uuf; SLC characteristic.	C224: CAL. control for 100-kc oscillator frequency adjustment. C230: ANT. TRIM capacitor.	3D9100V-85
	CLAMP: xtal; for .093" dia crystal holder; incl 3%" x 3/8" x 1/8" sponge rubber pad cemented to clamp.	Secures 100-kc crystal.	2Z2642.359
L114, L116	COIL, RF: replacement coil.	L114: First mixer V102 plate coil for tuning step 1. L116: Variable i-f coil.	3C607B-1
L118	COIL, IF transformer: replacement coil.	Variable i-f coil.	3C607B-2
L115	COIL, RF: unshielded phenolic form, beryllium copper silver pl term rings.	Intermediate mixer V103 grid coil for tuning step 1.	3C357-48
L117, L119	COIL, RF: replacement coil.	L117: Variable i-f plate coil. L119: Variable i-f coil.	3C607B-3
L102	COIL, RF: antenna; single layer wnd; 48 turns #28E wire; 23/8" lg x .437" dia phenolic coil form; adj iron core (not incl).	Antenna coil, tuning step 2.	3C1084S-65
L103	COIL, RF: antenna; single layer wnd; 43 turns #28E wire; 25/8" lg x .437" dia phenolic form; adj iron core (not incl).	Antenna coil, tuning step 3.	3C1084S-64
L121	COIL, RF: single layer wnd; 46 turns #30 double E wire, closely spaced, tapped at 13 turns; $\frac{3}{4}$ " lg x .187" dia bakelite form w/core.	V105 crystal oscillator plate coil.	3C1084S-47
L101, L110	COIL, RF: single layer wnd; 75 turns #35E wire; 2" lg x .295" dia phenolic form; slug tuning (core not incl).	L110: Antenna coil, tuning step 1. L110: V102 grid coil, tuning step 1.	3C1084S-43
L120	COIL, RF: choke; 3 universal wnd.	V105 xtal oscillator cathode choke.	3C357-49

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
L106, L109, L113	COIL, RF: single layer wnd; 15 turns #28E wire; 2" lg x .295" dia phenolic form; slug tuned (core not incl).	L106: Antenna coil, tuning steps 16 to 30. L109: R-f amplifier V101 plate coil, tuning steps 16 to 30. L113: First mixer V102 grid coil, tuning steps 16 to 30.	3C1084S-46
L105, L108, L112	COIL, RF: single layer wnd; 20 turns #28E wire; 2" lg x .295" dia phenolic form; slug tuned (core not incl).	L105: Antenna coil, tuning steps 8 to 16. L108: R-f amplifier V101 plate coil, tuning steps 8 to 16. L112: First mixer V102 grid coil, tuning steps 8 to 16.	3C1084S-45
L104, L107, L111	COIL, RF: single layer wnd; 27 turns #28E wire; 2" lg x .295" dia phenolic form; slug tuned (core not incl).	<ul> <li>L104: Antenna coil, tuning steps 4 to 7.</li> <li>L107: R-f amplifier V101 plate coil, tuning steps 4 to 7.</li> <li>L111: First mixer V102 grid coil, tuning steps 4 to 7.</li> </ul>	3C1084S-44
L125	COIL, RF: 3 pie universal wnd; 500 uh $\pm 10\%$ at 1000 kc; powdered iron form.	Part of V106 500-kc grid trap.	3C357-57
0136	COLLAR, shaft: SS; circular; $\frac{1}{2}$ " OD x $\frac{1}{4}$ " ID x .221" thk; two #6-40 NF-2 tapped holes at 90 deg.	For tuning knob tension.	2Z2935-93
P101	CONNECTOR, plug: 2 parallel blade male cont; straight.	Line cord plug.	6Z1727
J101, J104	CONNECTOR, receptacle: single round female cont; straight.	J101: Antenna coax connector. J104: IF OUTPUT connector.	2Z3062-251
	CONTACT, tube socket: phosphor bronze, silver pl; .57" lg x .102" wd x .104" h; mts in xtal or tube socket base; for .050" dia prong; Amphenol part #9-028-12.	Xtal socket contact.	2Z3193-136

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

<del></del>			***		and the Color, and the			
Signal Corps stock No.	2Z3262-61	2Z3262-46	2Z3262-45	2Z3262-44	2Z3290	2Z3295-148	2Z3295-152	2Z8203-493
Function of part	Part of coil assembly.	E149: Tunes coil L104. E150: Tunes coil L105. E151: Tunes coil L106. E152: Tunes coil L107. E153: Tunes coil L108. E154: Tunes coil L109. E155: Tunes coil L111. E156: Tunes coil L111. E157: Tunes coil L113.	E144: Tunes coil L102. E145: Tunes coil L103. E146: Tunes coil L114. E147: Tunes coil L116. E148: Tunes coil L118.	E142: Tunes coil L101. E143: Tunes coil L110.	Xtal PHASING control coupler.	O102: Oscillator switch shaft coupling. O103: Antenna switch shaft coupling.	Coupler on shaft extension.	Part of i-f drive shaft assembly.
Name of part and description	CORE, adjustable tuning: powdered iron core w/brass cad pl stud; freq 12 mc max; 1.187" lg x .242" dia; fits inside coil; Aladdin per Collins part #288 1062 00.	CORE, adjustable tuning: 3-13/16" lg o/a x .256" dia.	CORE, adjustable tuning: 3-7/16" lg x .25" dia.	CORE, adjustable tuning: 4-9/16" lg o/a; .255" dia.	COUPLING, flexible: for $1/4$ " shafts; $11/4$ " wd x $11/4$ " h x $23/32$ " d.	COUPLING, flexible: ½" to 3%" shaft coupling; 1.094" dia x .672" lg o/a.	COUPLING, flexible: $1/4$ " - $1/4$ " shaft coupling 1.094" dia x .672" lg o/a.	COUPLING, rigid: sleeve type; .2505" shaft size ea end; 1" lg x ½" dia o/a, shaft 9.234" lg extension from coupling.
Ref symbol	The second secon	E149, E150, E151, E152, E153, E154, E156,	E144, E145, E146, E147,	E142, E143		0102, 0103		0139

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
0128	COUPLING, rigid: sleeve type; .2505" shaft size ea end; 1" lg x $1/2$ " dia o/a.	Part of i-f drive shaft assembly coupling.	2Z3273-213
0108	COUPLING, rigid: sleeve type; .253" shaft size ea end; $1/2$ " lg x $1/2$ " dia o/a.	Xtal filter shaft coupling.	2Z32T3-239
Y104	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 9,000.00 kc.	Crystal for tuning steps 15 and 16.	2X209-9000
Y108	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 8,000.00 kc.	Crystal for tuning steps 5 and 6.	2X209-8000
Y102	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 13,000.00 kc.	Crystal for tuning steps 23 and 24.	2X209-13000
Y103	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 11,000.00 kc.	Crystal for tuning steps 19 and 20.	2X209-11000
Y106	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 12,000.00 kc.	Crystal for tuning steps 9, 10, 21, and 22.	2X209-12000
Y110	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 4,000.00 kc.	Crystal for tuning steps 1 and 2.	2X209-4000
Y109	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 6,000.00 kc.	Crystal for tuning steps 3 and 4.	2X209-6000
Y107	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 10,000.00 kc.	Crystal for tuning steps 7, 8, 17, 18, 27 and 28.	2X209-10000
Y101	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 10,666.67 kc.	Crystal for tuning steps 29 and 30.	2X209-10666.67
Y105	CRYSTAL UNIT: Crystal Unit CR-18/U; single xtal plate, Crystal Holder HC-6/U; 14,000.00 kc.	Crystal for tuning steps 11, 12, 25 and 26.	2X209-14000
Y1111	CRYSTAL UNIT, quartz: single xtal plate; 100 kc nominal.	Calibration crystal.	2X226-100

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

m Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
Y112	CRYSTAL UNIT: Crystal Unit CR-7/U; single xtal plate; 500 kc $\pm 500$ cyc.	I-f filter crystal.	2X225-500
	DIAL: vernier dial; c/o dial hub and washer in soldered assem; brass hub, SS washer; circular; 11/4" dia x .343" d; mts on 1/4" shaft; has two #4-48 NF-2 holes at 90 deg for set screws.	Vernier dial.	2Z3723-292
1105	DIAL: drum.	Band indicating MEGACYCLES drum.	2Z3723-231
1124	FILTER, band suppression: $11/2$ " lg x $3/4$ " dia o/a; .260" dia hole thru coil form for mtg; 2 wire lead term.	Part of spurious 1250-kc filter Z111.	2Z4376-111
T102	FILTER, band pass: 490 to 510 kc min range (shunted by 65 uuf); 1-7/16" x 1-7/16" x 3-9/16" max h o/a; 270,000-ohm parallel impedance; rectangular metal case; two 3%" studs on bottom diagonally located, 1.312" between ctr; 2 solder lug term on top, 2 solder lug term on bottom; MFP, core adj from top or bottom.	Crystal filter output.	2Z4376-110
F101	FUSE, cartridge: 1.5 amp; 250 v.	A-c line fuse.	3Z2601.5
	GEAR ASSEMBLY: c/o:       Collins part         Item       dwg. No.         Back gear panel       505 2179 003         Front gear panel       504 3111 002         I-f driver gear and shaft assem       504 3111 002         Gear assem, switch IF       504 304 001         Mc knob shaft       504 306 001         Knob gear and hub assem       504 3013 001         Shaft assem, band switch       504 3016 001         Ball, 3/16" dia (2 ea)       504 3012 001         Thrust bearing       504 2972 001	Tuning and band changing gears.	2Z4875-412

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Signal Corps stock No.		6Z4856-53	6Z4886	6Z4856-56	6Z4914	6Z4895
Function of part		Prevents abrasion.	Prevents abrasion.	Prevents abrasion.	Prevents abrasion.	Prevents abrasion.
Name of part and description	Tem	GROMMET: synthetic rubber or neoprene; fits 13/16" dia hole.	synthetic rubber or neoprene; fits $7/16$ "	GROMMET: synthetic rubber or neoprene; fits 7/8" dia hole.	GROMMET: synthetic rubber or neoprene; fits $1/4$ " dia hole.	GROMMET: synthetic rubber or neoprene; fits 5/16" dia hole; ANA std type AN931-3-S.
Ref Na:	Item Hub assem, Geneva wheel Centering spring Hub assem, detent gear Detent spring assem Center planet, gear and hu Hub assem, floating Shaft and gear assem Stop idler gear hub assem Pointer pulley assem Pulley, drum Post, lower spacing Post, upper spacing Loading cable Spring Miscellaneous assem hdw 171%" Ig x 6"wd x 4" d dia holes irregularly space 2189 004.	GROMMET: syn dia hole.	GROMMET: syr	GROMMET: syn hole.	GROMMET: syn hole.	GROMMET: syn hole; ANA std

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
XF101	HOLDER, fuse: extractor post; for one 3AG cartridge fuse.	Holds fuse F101.	3Z3285-2
O101A	HUB: coupler; SS, unfinished; rd 1.090" dia x .327" thk o/a; .1880" dia ctr mtg hole for shaft, two #6-40 NF-2 tapped holes at 90 deg and perpendicular to shaft hole.	Part of vfo coupler.	2Z5180-35
0101C	HUB: SS, unfinished; 1.090" dia x .327" thk; .250" dia ctr mtg hole for shaft, two #6-40 NF-2 tapped holes at 90 deg and perpendicular to shaft hole.	Part of vfo coupler.	2Z5180-36
	INSULATOR, stand-off: round post shape; natural bakelite; .750" lg; $\%$ " OD, tapped #6-32 NC-2 x $1/2$ " dia ea end.	Part of audio meter board assembly.	3G350-119
J102	JACK: Jack JJ-033; for 3 cond plug .206" dia x 1.093" lg.	SPEAKER jack.	2Z5533
J103	JACK: Jack JJ-034; for 2 cond plug .250" dia.	PHONES jack.	2Z5534
	KNOB: round; black phenolic; for 1/4" dia shaft.	Controls.	2Z5822-484
	KNOB: round, tapered; black phenolic; for ½" dia shaft; one #8-32 tapped hole for set screw; 11/16" dia x 13/32" lg o/a; 11/32" dia shaft hole; surface knurled.	Control.	2Z5822-580
	KNOB: round; black phenolic; for $1/4$ " shaft; indicator mark filled white; $11/8$ " dia x $13/16$ " lg o/a; no insert.	Controls.	2Z5822-485
	KNOB: round, w/pointer; black phenolic; for $1/4$ " dia shaft.	Control.	2Z5821-4.1
	KNOB: rd; black phenolic; for .253" dia shaft; two #8-32 tapped holes for set screws; 1¾" dia skirt; 1¾%" dia x ¼" lg o/a; brass; 23/32" dia shaft hole; indicator mark filled white.	Control.	2Z5822-581
L101, L102, L103	LAMP, incandescent: Lamp LM-52; 6 to 8 v, .15 amp; miniature bayonet base.	Dial illuminations.	2Z5925.1

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Signal Corps Function of part stock No.	net; 31/32" lg x 25/32" Holder for I103.	let; 13/8" lg x 7/16" wd x XI101: Holder for I101. XI102: Holder for I102.	meter calibrated for db; Audio level meter. 3F3307.5-8, flush panel mtg case.	core (.375" OD); steel, 1" Ig x 29/64" wd x .274" 17 dia hole and .080" dia	2C2722-6 25/8" wd x 27/8" h approx; om main rectifier unit; 32 NC-2 tapped holes on part #70E15, dwg #505	bfo; incl capacitors C1, lins part $\#912\ 0967\ 00$ ), 0 uuf $\pm 1$ uuf temp coef 13 0065 00), C4, 50 uuf sating capacitor, C5, 100 cto. B1 LAM turn PC20	#9-41 Litz tapped at 31 turns, olic tubular form; encl in alumined range; 2" lg x 1-7/16" wd x C-2 x 5/16" mtg studs on 13 '16" de bolts on 1-5/16" ctr.	Litz tapped at 31 turns, ular form; encl in alum- ge; 2" lg x 1-7/16" wd x 16" mtg studs on 13/16" 5 on 1-5/16" ctr.	Litz tapped at 31 turns, ular form; encl in alum- ge; 2" lg x 1-7/16" wd x 16" mtg studs on 13/16" s on 1-5/16" ctr.	Litz tapped at 31 turns, ular form; encl in alumege; 2" lg x 1-7/16" wd x 16" mtg studs on 13/16" s on 1-5/16" ctr.		Litz tapped at 31 turns, ular form; encl in alumege; 2" lg x 1-7/16" wd x 16" mtg studs on 13/16" s on 1-5/16" ctr.  Indicator on MEGACYCLE drum. 2Z7258.94
Name of part and description	LAMPHOLDER: miniature bayonet; $31/32''$ lg x $25/32''$ dia o/a.	LAMPHOLDER: miniature bayonet; $13/8'' \text{ lg x 7/16}'' \text{ wd x}$ $15/16'' \text{ thk o/a}.$	METER, audio level: dc milliammeter calibrated for db; range 0 to 1 ma; round, plastic, flush panel mtg case.	MOUNTING, coil: holds coil and core (.375" OD); steel, cad plate; irregular shape; 41/64" lg x 29/64" wd x .274" h above mtg surface; mts in .417 dia hole and .080" dia hole, .310" between ctr.	OSCILLATOR, RF: 2.0 to 3.0 mc; not crystal controlled; approx.001 w output; 5½" lg x 25%" wd x 27%" h approx; integral coil; receives power from main rectifier unit; mts on front panel by three #6-32 NC-2 tapped holes on 1.75" x 1.468" ctr; HS; Collins part #70E15, dwg #505 4011 004.	OSCILLATOR SUBASSEMBLY: bfo; incl capacitors C1, 1600 uuf button silver mica (Collins part #912 0967 00), C2, 5 to 50 uuf variable air, C3, 50 uuf ± 1 uuf temp coef —1200 ±15% (Collins part #913 0065 00), C4, 50 uuf (selected item) ceramic compensating capacitor, C5, 100 uuf ±10% ceramic or silver resistor R1 JAN type RC20-BR104M coil: 81 turns #9.41 Litz tannod of 21 turns	powdered iron core, phenolic tubular form; encl in aluminum can; 480 to 520 kc freq range; 2" lg x $1-7/16$ " wd x $43$ %" h o/a; two #4-40 NC-2 x $5/16$ " mtg studs on 13 '16" ctr; two #6-32 NC-2 spade bolts on 1-5/16" ctr.	powdered iron core, phenolic tubular form; encl in aluminum can; 480 to 520 kc freq range; 2" lg x 1-7/16" wd x 43%" h o/a; two #4-40 NC-2 x 5/16" mtg studs on 13 '16" ctr; two #6-32 NC-2 spade bolts on 1-5/16" ctr.	powdered iron core, phenolic tubular form; encl in aluminum can; 480 to 520 kc freq range; 2" lg x 1-7/16" wd x 43%" h o/a; two #4-40 NC-2 x 5/16" mtg studs on 13 '16" ctr; two #6-32 NC-2 spade bolts on 1-5/16" ctr.	powdered iron core, phenolic tubular form; encl in aluminum can; 480 to 520 kc freq range; 2" lg x 1-7/16" wd x 43%" h o/a; two #4-40 NC-2 x 5/16" mtg studs on 13 '16" ctr; two #6-32 NC-2 spade bolts on 1-5/16" ctr.	powdered iron core, phenolic tubular form; encl in aluminum can; 480 to 520 kc freq range; 2" lg x 1-7/16" wd x 43%" h o/a; two #4-40 NC-2 x 5/16" mtg studs on 13 '16" ctr; two #6-32 NC-2 spade bolts on 1-5/16" ctr.	powdered iron core, phenolic tubular form; encl in aluminum can; 480 to 520 kc freq range; 2" lg x 1-7/16" wd x 43%" h o/a; two #4-40 NC-2 x 5/16" mtg studs on 13/16" ctr; two #6-32 NC-2 spade bolts on 1-5/16" ctr.  POINTER, indicator: sliding.
Ref symbol	XI103	XI101, XI102	M101		Z101	T106					H101	H101

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

1	Name of part and description	Function of part	Signal Corps stock No.
PO	POST, spacing: cad pl steel; 3/8" lg x 3/16" OD; .130" ID	Band switch spacer.	2Z7259-119
PU.	PULLEY: CRS, tin pl; circular; 2.125" dia x $\frac{1}{4}$ " thk; 3.75" dia hole.	Dial drive pulley, large.	6Z7678-2
PU	PULLEY: dial drive; CRS, tin pl; circular; 3/8" dia x .193" thk; .127" dia hole.	Dial drive pulley, small.	6Z7678-3
$\Xi$	REACTOR: 3.0 hy, 120 ma; 100 ohms DC resistance; 2500 v RMS test; HS metal case; 2-1/16" wd x 2-7/32" lg x 3-9/32" h; four #6-32 NC-2 mtg inserts on 11/4" x 13/8" ctr; 2 solder lug terms on 5/16" ctr.	Power supply input d-c filter choke.	3C547-37
<u>교</u>	REACTOR: 5 hy, 80 ma; 300 ohms DC resistance; 2500 v RMS test; HS metal case; 1-25/32" wd x 17%" lg x 2-25/32" h; four #6-32 NC-2 mtg inserts on 15/16" x 1-1/16" ctr; 2 solder lug term on 5/16" ctr.	Power supply output d-c filter choke.	3C547-38
ద	RECEIVER SUBASSEMBLY: vernier drive assembly; 1-3/32" lg x .812" dia o/a; .092" dia shaft for mtg.	Vernier drive assembly.	2C4180-388-1
æ	RECEIVER SUBASSEMBLY: incl coil L104 and capacitors C107 and C108; 1%" lg x 1" wd x 2" h o/a; two .140" dia mtg holes diagonally located on 11%" x ¾" ctr.	Tuning steps 4 to 7 (antenna).	2C4180-388-4
84	RECEIVER SUBASSEMBLY: incl capacitors C122 and C123 and coil L108; 13%" lg x 1" wd x 2" h o/a; two .140" dia mtg holes on opposite corners of 11%" x 3/4" mtg ctr.	R-f tuning steps 8 to 15.	2C4180-388-6
M	RECEIVER SUBASSEMBLY: incl coil L112, C129 and C130; 13/8" lg x 1" wd x 2" h o/a; two .14" dia mtg holes on opposite corners of board; 11/8" x 13/4" mtg ctr.	R-f tuning steps 8 to 15.	2C4180-388-6
æ	RECEIVER SUBASSEMBLY: incl coil L109 and capacitor C124; 13/8" lg x 1" wd x 2" h o/a; two .140" dia mtg holes on opposite corners of 11/8" x 3/4" mtg ctr.	R-f tuning steps 16 to 30.	2C4180-388-7

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

m Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
Z103	RECEIVER SUBASSEMBLY: incl coil L113 and capacitor C132; 13%" lg x 1" wd x 2" h o/a; two .14 dia mtg holes on opposite corners of board; 11%" x 134," mtg ctr.	R-f tuning steps 16 to 30.	2C4180-388-7
Z106	RECEIVER SUBASSEMBLY: incl coil L107 and capacitors C120 and C121; 13/8" lg x 1" wd x 2" h o/a; two .140" dia mtg holes on opposite corners of 11/8" x 3/4" mtg ctr.	R-f tuning steps 4 to 7.	2C4180-388-3
<b>Z</b> 107	RECEIVER SUBASSEMBLY: incl coil L111, C127 and C128; 1%" lg x 1" wd x 2" h o/a; two .14" dia mtg holes on opposite corners of board; 11%" x 13/4" mtg ctr.	R-f tuning steps 4 to 7.	2C4180-388-3
Z115	RECEIVER SUBASSEMBLY: incl coils L101, L102, L103, fixed capacitors C101, C103, C105, and var capacitors C102, C104, C106 mtd on board; 25/8" lg x 2" wd x 21/2" h o/a; four .140" mtg holes on .875" x 1.750" ctr.	Tuning steps 1 to 3 (antenna).	2C4180-388-2
Z109	RECEIVER SUBASSEMBLY; incl coil L105, C109, and C110 mtd on board; 1%" lg x 1" wd x 2" h o/a; two .140" dia mtg holes diagonally located on 11/8" x ¾" ctr.	Tuning steps 8 to 15 (antenna).	2C4180-388-5
CR101	RECTIFIER, metallic: selenium; input 12.5 v AC, 1 to 5000 cyc, single ph; output 6.28 v DC, 64 ma max, full wave.	Meter M101 rectifier.	3H4955
K101	RELAY, armature: right 1C, left 1C cont arrangement (viewed from mtg end); 3 amp, 150 w cont rating; palladium cont; single wnd coil, 12 v DC, .016 amp DC max release, .021 amp DC max oper, 375 ohms DC resistance, ins; solder lug term; 1-37/64" lg x 1-1/32" wd x 1-5/16" h max; two #4-40 holes on diagonally .437" vert between ctr; fast acting.	Disabling relay.	2Z7599A-328
R143	RESISTOR, fixed: comp; 10 ohms $\pm 10\%$ ; ½ w; JAN type RC20BF100K.	V112 filament voltage dropping	3RC20BF100K

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Signal Corps stock No.	3RC20BF101K	3RC20BF161J	3RC20BF471K	3RC20BF821K	3RC20BF102K	3RC42BF102K	3RC20BF222K	3RC30BF222K
Function of part	INPUT meter circuit load resistor.	INPUT meter balancing resistor.	R107: V102 cathode bias. R111: V102 cathode bias. R127: V106 cathode bias.	Determines minimum bias.	I-f output VIII bias resistor.	B+ isolation.	R110: V102 plate decoupling. R116: V105 tuning steps 2 to 12 plate load. R124: V102 plate decoupling. R129: V106 plate decoupling. R135: V107 plate decoupling. R138: V108 plate decoupling. R162: V114 bfo decoupling. R162: V111 avc amplifier bias. R173: AUDIO meter voltage dropping resistor. R180: V111 i-f output plate voltage dropping.	V109 plate decoupling.
Name of part and description	RESISTOR, fixed: comp; 100 ohms ±10%; ½ w; JAN type RC20BF101K.	RESISTOR, fixed: comp; 160 ohms $\pm 5\%$ ; $\frac{1}{2}$ w; JAN type RC20BF161J.	RESISTOR, fixed: comp; 470 ohms ±10%; ½ w; JAN type RC20BF471K.	RESISTOR, fixed: comp; 820 ohms $\pm 10\%$ ; ½ w; JAN type RC20BF821K.	RESISTOR, fixed: comp; 1000 ohms $\pm 10\%$ ; ½ w; JAN type RC20BF102K.	RESISTOR, fixed: comp; 1000 ohms $\pm 10\%$ ; 2 w; JAN type RC42BF102K.	RESISTOR, fixed: comp; 2200 ohms ±10%; ½ w; JAN type RC20BF222K.	RESISTOR, fixed: comp; 2200 ohms $\pm 10\%$ ; 1 w; JAN type RC30BF222K.
Ref	R170	R163	R107, R111, R127	R149	R179	R174	R110, R124, R124, R129, R138, R162, R168, R168, R168,	R142

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

	Name of part and description	Function of part	Signal Corps stock No.
RESISTOR, fixed: cctype RC20BF332K.	ed: comp; 3300 ohms $\pm 10\%$ ; $\frac{1}{2}$ w; JAN?332K.	A-f volt amplifier cathode bias.	3RC20BF332K
RESISTOR, fixed: cotype RC20BF472K.	red: comp; 3300 ohms $\pm 10\%$ ; ½ w; JAN F472K.	R119: 100-kc oscillator cathode bias. R132: Xtal filter selectivity.	3RC20BF472K
RESISTOR, fixed: ctype RC20BF682K.	RESISTOR, fixed: comp; 6800 ohms $\pm 10\%$ ; $1/2$ w; JAN type RC20BF682K.	V101 plate decoupling.	3RC20BF682K
RESISTOR, fixed: co type RC20BF103K.	RESISTOR, fixed: comp; 10,000 ohms ±10%; ½ w; JAN type RC20BF103K.	R105: V101 tuning step 1 plate load resistor. R122: 100-kc oscillator decoupling. R133: V107 avc decoupling. R136: V108 avc decoupling. R139: V109 avc decoupling.	3RC20BF103K
RESISTOR, fixed: cc type RC20BF223K.	RESISTOR, fixed: comp; 22,000 ohms $\pm 10\%$ ; 1/2 w; JAN type RC20BF223K.	Xtal filter selectivity.	3RC20BF223K
RESISTOR, fixed: co type RC20BF273K.	RESISTOR, fixed: comp; 27,000 ohms $\pm 10\%$ ; 1/2 w; JAN type RC20BF273K.	R126: V107 screen bleeder. R147: Bias bleeder. R169: V108 screen bleeder.	3RC20BF273K
RESISTOR, fixed: co type RC20BF333K.	RESISTOR, fixed: comp; 33,000 ohms ±10%; ½ w; JAN type RC20BF333K.	R104: V101 screen voltage dropping. R113: V103 screen voltage dropping. R114: V105 screen voltage dropping. R128: V106 screen voltage dropping. R151: Diode load. R161: V114 bfo plate load.	3RC20BF333K
RESISTOR, fixed: cotype RC20BF473K.	RESISTOR, fixed: comp; 47,000 ohms ±10%; ½ w; JAN type RC20BF473K.	<ul> <li>R109: V102 screen voltage dropping.</li> <li>R117: V105 tuning steps 14-30 plate voltage dropping.</li> <li>R134: V107 screen voltage dropping.</li> <li>R137: V108 screen voltage dropping.</li> <li>R141: V109 screen voltage dropping.</li> <li>R146: V111 plate load (avc).</li> </ul>	3RC20BF473K

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Signal Corps stock No.	3RC20BF474K	3RC20BF684K	3RC20BF105K	3RW18921	3RW21327	3RV21012	3RV41510	3RV55048	6R15490.1	2Z8204-162	.10.   2Z8203-598
Function of part	R125: V107 grid. R144: Avc filter. R152: Noise limiter filter. R153: Noise limiter load. R172: Static drain.	100-ke oscillator grid.	V101 grid.	Part of bias voltage divider.	Part of bias voltage divider.	METER ZERO control.	RF GAIN control.	AUDIO GAIN control.	Screw driver (Phillips head).	Xtal filter shaft extension.	Shaft for switches S109 and S110.
Name of part and description	RESISTOR, fixed: comp; 470,000 ohms ±10%; ½ w; JAN type RC20BF474K.	RESISTOR, fixed: comp; 680,000 ohms ±10%; ½ w; JAN type RC20BF684K.	RESISTOR, fixed: comp; 1 meg ±10%; ½ w; JAN type RC20BF105K.	RESISTOR, fixed: WW; 120 ohms $\pm 5\%$ ; 8 w; JAN type RW30G121.	RESISTOR, fixed: WW; 310 ohms $\pm 5\%$ ; 8 w; JAN type RW30G311.	RESISTOR, variable: comp; JAN type RV4ANSD101A; 100 ohms $\pm 10\%$ ; 2 w at $70^{\circ}$ C; 3 solder lug term; linear taper; ins cont arm.	RESISTOR, variable: comp; 10,000 ohms ±10%; 2 w; JAN type RV4ANFK103A.	RESISTOR, variable: comp; JAN type RV4ANFK504C; 500,000 ohms $\pm 10\%$ ; 2 w min at $70^{\circ}$ C; 3 solder lug term; $10\%$ clockwise log taper; ins cont arm.	SCREWDRIVER: 90° offset; Phillips L shape; 1 end $31_4$ " lg other end 1" lg, $31_4$ " lg o/a; .188" dia round shank; #1 Phillips head both ends; Vaco type O1V.	SHAFT: extension; 1.375" lg x .250" dia.	SHAFT: extension; steel, cad pl; round $4\%$ " lg x $1/4$ " dia; mts in coupling; opposite sides flatted $41\%$ ", .015" x 45 deg chamfer both ends.
Ref symbol	R125, R144, R152, R153, R172	R118	R101	R164, R166	R165	R140	R148	R154		0133	0137

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

avtension 7 875	neion: 7.875" lo v 949" dia	Rfo mitch adiustment.	stock No. 2Z8202-68
SHAFT: extension; 7.875″ lg x .249 SHAFT: 33/4″ lg x .375″ dia o/a, portion.	wd at flatted	bro prten adjustment. Xtal switch shaft.	2Z8204-161
SHAFT: $10''  \text{lg x}$ .375" dia o/a, .310" wd at flatted portion.		R-f switch shaft.	2Z8204-160
SHIELD, tube: bayonet mtg; 13/16" ID x $2l_4$ " lg inside.		Tube shield for V113.	2Z8304.237
SHIELD, tube: steel, cad pl; cylindrical, open top; bayonet mtg; .810" ID x 13%" lg inside; JAN type TSF0T101.		E107: Tube shield for V101. E108: Tube shield for V102.	2Z8304.57
SHIELD, tube: steel, cad pl; cylindrical, open top; bayonet mtg; .810" ID x 1¾" lg inside; JAN type TSF0T102.		E109: Tube shield for V103. E110: Tube shield for V104. E111: Tube shield for V105. E112: Tube shield for V106. E113: Tube shield for V107. E114: Tube shield for V108. E115: Tube shield for V109. E116: Tube shield for V114. E001: Tube shield for V001.	2Z8304.154
SHIELD, tube: cad pl; cylindrical; bayonet mtg; .950" ID x 1-15/16" lg inside; JAN type TSF0T105.		E104: Tube shield for V110. E105: Tube shield for V111. E106: Tube shield for V112.	2Z8304.183
SOCKET: crystal.		Socket for crystal Y111.	2Z8761-64
SOCKET, tube: 7 cont miniature; 1 piece saddle mtg; JAN type TSE7T101.		XV101: Socket for V100. XV102: Socket for V102. SV103: Socket for V103. XV104: Socket for V104. XV105: Socket for V105. XV106: Socket for V106. XV107: Socket for V107. XV108: Socket for V107.	2Z8677.94

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Signal Corps stock No.		2Z8678.326	2Z8679.30	2Z8636-23	2Z3295-167	2Z8877.615	2Z8877.332	2Z8877.333	2Z8877.334	2Z8877.335	2Z8877.336	2Z8877.614
Function of part	XV109: Socket for V109. XV113: Socket for V113. XV114: Socket for V114.	Socket for V115.	XV110: Socket for V110. XV111: Socket for V111. XV112: Socket for V112.	Sockets for crystals Y101 thru Y110.	Part of main oscillator coupling.	Gear loading spring (part of main gear assembly).	Variable i-f rack spring.	R-f slug rack spring.	R-f slug rack gear loading.	Dial spring loading.	MEGACYCLES drum dial tension.	Part of slug table assembly of r-f tuner assembly.
Name of part and description		SOCKET, tube: octal; 1 piece under chassis saddle mtg; JAN type TSB8T101.	SOCKET, tube: 9 cont noval; 1 piece saddle mtg; JAN type TSE9T101.	SOCKET ASSEMBLY, crystal: for 10 crystals.	SPIDER, coupling: phosphor bronze; cylindrical; 1.090" dia x .157" thk; .250" dia ctr mtg hole.	SPRING: helical extension type; .029" dia spring wire, type 302 SS; .574" lg x .125" OD o a; 133/4 turns; 90 deg hook term 1 ea end.	SPRING: helical compression; .025" dia spring wire, #302 SS; 31/2" lg x .312" OD o/a; 33 turns.	SPRING: helical extension type; 1.262" lg x .312" OD; 39 turns.	SPRING: helical extension type; 3/8" free lg x .130" dia o/a; 6 turns.	SPRING: helical extension type; 13/32" lg x 5/32" dia o/a; 7 turns closely wnd.	SPRING: torsion type; 1" lg x .874" OD; 131/4 turns closely wnd.	SPRING: loop type; SS wire type 302, .030 dia; .229" lg x .225" wd x .030" thk.
Ref symbol	XV109, XV113, XV114	XV115	XV110, XV111, XV112	XY101	O101B							

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

rps o.	0.14	0.13	0.15	0.12	ম্	198	<del>-</del> :	~ 관		
Signal Corps stock No.	3Z9903E-10.14	3Z9903E-10.13	3Z9903E-10.15	3Z9903E-10.12	3Z9825-50.2	3Z9825-58.198	3Z9825-50.1	3Z9863-52R	6Q335-2	6Q335-1
Function of part	Variable i-f selecting.	Xtal oscillator harmonic selecting.	<ul> <li>S101: Antenna coil selecting.</li> <li>S102: Antenna coil selecting.</li> <li>S106: First mixer plate coil selecting.</li> <li>S107: First mixer plate circuit selecting.</li> <li>S109: Xtal selecting.</li> </ul>	<ul><li>S103: R-f coil selecting.</li><li>S105: Mixer grid circuit selecting.</li><li>S104: R-f amplifier plate coil selecting.</li><li>ing.</li></ul>	S112: BFO ON-OFF. S115: AVC ON-OFF S116: Noise LIMITER ON-OFF. S118: CALIBRATE ON-OFF.	Receiver ON-STANDBY-OFF.	SELECTIVITY switch.	METER switch.	Alinement tool.	Alinement tool.
Name of part and description	SWITCH SECTION, rotary: 12 position (p/o rotary switch): 1 nole. 2 throw.	SWITCH SECTION, rotary: 18 position (p/o rotary switch); 2 pole, 15 throw.	SWITCH SECTION, rotary: 18 position (p/o rotary switch); 1 pole, 17 throw.	SWITCH SECTION, rotary: 18 position (p/o rotary switch); 1 pole, 18 position.	SWITCH, rotary: DPDT.	SWITCH, rotary: 2 pole, 3 position; 1 sect.	SWITCH, rotary: 1 pole, 5 position; 1 sect.	SWITCH, toggle: DPDT; JAN type ST52R.	TOOL, alinement: natural phenolic, LTS-M3; $63/4$ " lg x $1/2$ " dia o/a; $3/8$ " lg scdr tip tapered to $1/32$ " at tip; phenolic grip.	TOOL, alinement: natural phenolic, LTS-M3; 5-13/16" lg x .315" dia o/a; 1½" lg scdr tip tapered to 1/32" at tip w/1/16" d x 5/32" wd notch in tip; opposite end has flat insert 5/16" lg w/1/16" d x 5/32" wd notch in end.
Ref	S110,	S108	S102, S102, S106, S106, S109	S103, S105, S104	S112, S115, S116, S118	S113	S114	S117	Ÿ	

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

	Name of part and description	Function of part	Signal Corps stock No.
TRANSFORMER, AF: line ance, 1500 v test; secd 600 tapped at 4 ohms; HS me 134" wd x 3" h; 3 w oper response; 100 cps ± 3 db, reference, 2500 cps ± 1 dl term; four #6-32 x 3%" h;	TRANSFORMER, AF: line type; pri 5000 ohms impedance, 1500 v test; secd 600 ohms impedance, 1500 v test, tapped at 4 ohms; HS metal case, iron core; $178$ " lg x $134$ " wd x 3" h; 3 w oper level; turns ratio 2.89:1; freq response; 100 cps $\pm$ 3 db, 300 cps $\pm$ 1 db, 1000 cps zero reference, 2500 cps $\pm$ 1 db, 5000 cps $\pm$ 3 db; solder lug term; four $\pm$ 6-32 x $\frac{3}{8}$ " h studs on 1-5/16" x 1-1/16" ctr.	Audio output transformer.	2239551.158
TRANSFORMER, IF: 490 to x 1-7/16" wd x 25/8" h less secd; adj iron core tuning;	TRANSFORMER, IF: 490 to 510 kc; shielded; 1-7/16" lg x 1-7/16" wd x 2%" h less term and mtg; tuned pri and secd; adj iron core tuning; solder lug term on bottom.	Crystal filter input.	2Z9642.132
TRANSFORMER, IF: 500 kc; shielded; 2" lg x 1-7/16" d x 31/2" h o/a; tuned pri and secd; adj powdered iron core tuning.	RANSFORMER, IF: 500 kc; shielded; 2" lg x 1-7/16" d x 31/2" h o/a; tuned pri and secd; adj powdered iron core tuning.	T103: First i-f transformer. T104: Second i-f transformer. T105: Third i-f transformer.	2Z9641.328
TRANSFORMER, power: fil and plate; input 115 v 60 cyc, single ph; secd #1, 5 v, 2 amp; secd #2, 6.3 v, 5 amp; secd #3, 700 v CT, .090 amp; HS metal case; 3-15/16" lg x 3-5/16" d x 23/4" excluding term; solder lug ceramic bushing term.	fil and plate; input 115 v 60 cyc, 2 amp; secd #2, 6.3 v, 5 amp; amp; HS metal case; 3-15/16" cluding term; solder lug ceramic	Power transformer.	2Z9613.719
TUBE, electron: JAN type 6AK5.	.K5.	V101: R-f amplifier. V105: Crystal oscillators.	2J6AK5
TUBE, electron: JAN type 6BE6.	·E6.	V102: First mixer. V103: Third mixer. V106: Second mixer.	2J6BE6
TUBE, electron: JAN type 6BA6.	3.46.	V001: Vfo. V002: Vfo. V104: Crystal oscillator. V107: First i-f. V108: Second i-f. V109: Third i-f. V114: Bfo.	2J6BA6

2. Identification Table of Parts for Radio Receiver R-388/URR (contd)

Ref symbol	Name of part and description	Function of part	Signal Corps stock No.
V110, V112	TUBE, electron: JAN type 12AX7.	V110: Detector and avc rectifier. V112: Noise limiter, first audio.	2J12AX7
V1111	TUBE, electron: JAN type 12AU7.	Avc amplifier.	2J12AU7
V113	TUBE, electron: JAN type 6AQ5.	Audio output.	2J6AQ5
V115	TUBE, electron: JAN type 5V4G.	Power supply rectifier.	2J5V4G
	WRENCH: Bristo set screw.	For No. 4 Bristo set screw.	6RK55232
	WRENCH: Bristo set screw.	For No. 6 Bristo set screw.	6R55230
	WRENCH: Bristo set screw.	For No. 8 Bristo set screw.	6R55231.1
	WRENCH: Bristo set screw.	For No. 10 Bristo set screw.	6R55230-10
1104	LAMP, glow: Navy type #VG-12; 105 to 125 v, ½ w, striking v 65 v AC, 90 v DC; 1½" lg o/a; double cont bayonet base candelabra; requires 30,000 ohms ext resistance on 105 to 125 v; GE type NE-48.	Antenna circuit voltage discharge path.	2Z5889-3
R181	RESISTOR, fixed: WW; JAN type RW32F402.	Current limiting resistor.	3RW27929
V116	TUBE, electron: JAN type 0A2.	Voltage regulator.	2J0A2





Figure 42. Radio Receiver R-



Receiver R-388 WRR, over-all schematic.